





#### **LCG-France Tier-1**

#### Status and Plans

Fabio Hernandez
IN2P3/CNRS Computing Centre - Lyon
fabio@in2p3.fr

2<sup>nd</sup> LCG-France Workshop Clermont, March 13<sup>th</sup>-14<sup>th</sup> 2007




#### Contents

- Activities and contribution during 2006
- Plans for 2007
- Conclusions
- Questions



#### Contribution

- Revised planned contribution of LCG-France Tier-1
  - % of required resources for all tier-1s in 2008 (experiment's requirements as of March 2007)




Source: Comparison of New Requirements with Current Pledges - 24/10/2006




# Contribution (cont.)

- Revised planned contribution of LCG-France tier-1
  - % of required resources in all tier-1s in 2008





### Planned Evolution




Increase rate over the period 2006-2010:

CPU: x 17 DISK: x 16 MSS: x 18



# Site overview (current status)





## Site overview (cont.)


 Operating also several grid services for non-LHC VOs


		alice	atlas	cms	lhcb	auvergrid	biomed	calice	cdf	dteam	dzero	egeode	embrace	esr	hone	ilc	sdo	virgo
	CE	✓	✓	✓	✓		<b>✓</b>	✓	✓	✓	<b>✓</b>	<b>✓</b>		<b>✓</b>	✓	✓	✓	✓
	dCache/SRM SE	✓	✓	✓	✓					✓							✓	
မွ	Classic SE	✓	✓	✓	✓		✓			✓	✓	✓		✓	✓	✓	✓	✓
Ξ̈́	Local LFC	✓	✓	✓	✓													
Sel	VO Box	✓	✓	✓	✓				✓									
Grid Service	FTS	✓	✓	✓	✓													
ō	Central LFC						✓											
	RLS/RMC						✓											
	VOMS					✓	✓					✓	✓					



#### Contribution in 2006

- CPU time contributed by the LCG-France tier-1 in 2006
  - % of CPU time (grid and non-grid) used by the experiments in all the tier-1s






The CC-IN2P3 contribution to the global effort in 2006 was 10% of the total CPU used by the 4 experiments in all the tier-1s.




# Contribution in 2006 (cont.)

 CPU utilisation by LHC experiments at all the tier-1s and at CC-IN2P3

All Tier-1s (does not include non-grid usage of some sites)



#### CC-IN2P3 (grid and non-grid)




Source: http://www3.egee.cesga.es/gridsite/accounting/CESGA/tier1\_view.html




# Grid vs. non-grid usage


- Site usage (grid vs. non-grid) greatly varies from one experiment to another
  - Both in terms of consumed capacity and number of jobs







## Efficiency (CPU time vs. wallclock)












#### CPU planned vs. actual consumption






### Observed Experiment Activity at the Site

LHC experiments CPU activity vs. time


F. Hernandez

NOTE: Y axis scale is not the same in all plots



13

# Delivered CPU capacity



Several service interruptions in August and September due to incidents with the cooling or power infrastructure


4 days-long scheduled complete shutdown of the site for replacing some central electric and cooling equipement



# CPU capacity - allocation

#### Allocated CPU Capacity

December 2006




■ LHC Experiments ■ Other Experiments



# CPU capacity - consumption

- CPU time consumed by LHC experiments
  - % of consumed CPU time by all experiments at CC-IN2P3



■ Other Experiments ■ LHC Experiments



## Delivered Storage


- Disk storage capacity
  - Delivered 34% (180 TB out of 520 TB planned)
  - More on this later
- Tape storage capacity
  - Installed capacity (as planned) of 535 TB (of which 73% was actually used)



#### Data transfer exercises


#### CERN → CC-IN2P3 (disk)

April 2006



#### CERN → CC-IN2P3 (MSS)

April 2006




Target: 75 MB/sec

LCG

## Data transfer exercises (cont.)

- ATLAS: data transfer tests from Tier-1 to linked Tier-2s
  - July 7th 2006





## Data transfer exercises (cont.)

**BAD** 

#### **ATLAS**

## DDM Functional Test 2006. Summary Table

	Tier-1	Tier-2s	Se	pt 06	Od	et 06	Nov 06		
	ASGC	IPAS, Uni Melbourne		Failed within the		Failed for Melbourn		T1-T1 not testd	
	BNL	GLT2, NET2,MWT2,SET2, WT2		cloud done		done		2+GB & DPM	
	CNAF	LNF,Milano,Napoli,Roma1		65% failure		done			
	F7K	CSCS, CYF, DESY-ZN, DESY-HH, FZU, WUP		Failed from %		dCache		T1-T1	
	LYON	BEIIJING, CPPM, LAPP, LPC, LPHNE, SACLAY, TOKYO		done 2		done, FTS conn		not testa	
	NG			tested		=<_6 tested		net tested	
	PIC	IFAE, IFIC, UAM		Failed within the		done		100104	
	RAL	CAM, EDINBOURGH, GLASGOW, LANCS, MANC, QMUL		cloud Failed within the		Failed for Edinbrg .		done	
	SARA	IHEP, ITEP, SINP		cloud Failed		IHEP not tested		IHEP in progress	
	TRIUMF	ALBERTA, TORONTO, UniMontreal, SFU, UVIC		Failed within the		Failed		T1-T1 not testd	

ATLAS SW week

Dec 11. 2006. A.Klimentöv

OK


Eric Lançon, Comité de Direction

5 février

F. Hernandez 20

4 / 3 >

## Data transfer exercises (cont.)




févri S France 5 O Direction O Comité Charlot, Claude

LCG

#### Data transfer exercises

#### Ressources – stockage et transferts


• Sep-Nov 2006, test FTS,  $T0 \rightarrow 5 T1s$ 



2007 février 2 CG-France Direction de Comité Yves Schutz,



# Site availability



IN2P3-CC

av.reliability last 3 mths

target (90% of MoU) last 3 month averages: all sites

65%

F. Hernandez 23

Source: http://lcg.web.cern.ch/LCG/MB/availability/site\_reliability.pdf

### Computing capacity increase in 2006

#### CPU

- +265 worker nodes (IBM, dualprocessor dual-core AMD Opteron 275, 2.2 GHz, 2 GB/core, 290 GB internal disk)
- Theoretical power: 1573
   SI2000 per core
  - Total: 1,6 M SI2000
  - Observed power with typical applications is ~30% less than theoretical

#### Disk storage

 +400 TB of rack-mounted Sun Fire X4500 (aka Thumper)





#### Computing capacity increase in 2006 (cont.)

#### Tape storage

- Call for tender for a new cartridge library
- Selected Sun/StorageTek SL8500
  - 10.000 slots (500 GB cartridges)
  - 30 T10000 drives
  - 10 LTO-3 drives
  - Will progressively replace the current one
- Installation started: expected to be finished by end of April 2007








#### Computing capacity increase in 2006 (cont.)

#### Databases

- Reconfiguration of Oracle cluster
  - Extensible hardware architecture
- +1 TB added to the dedicated SAN (2 TB total)
- +3 front-end database servers (5 total)
  - 2 of them will share the load of the LHC experiments
- International connectivity
  - Dedicated link CC-IN2P3 ← CERN 10 Gbps



2 x 1 Gbps links CC-IN2P3 ↔ Fermilab



## Hardware procurement


- Procurement process (evaluation, publication, selection) is more or less under control
  - Delivery delays are not!
  - In 2006, we suffered delivery delays of several months for some equipment
- Procurement of equipment is an issue
  - Several constraints: space in the machine room, budget constraints, delivery delays, requested availability, ...



# Courtesy of Dominique Boutigny

# Facility Upgrade

- Major effort for upgrading the electric and cooling infrastructure of the site
  - Currently reaching the limits of the installation
  - When the current works will be finished (April 2007)
    - from 500 kW to 1000 kW usable for computing equipment






# Facility Upgrade (cont.)

#### Infrastructure (2)

CC-IN2P3 average electrical power in kW



An important work is going on in order to upgrade the computer room

- Electrical distribution
- Cooling
- Uninterruptible Power Supply
- → Up to ~1.6 MW of computing equipment + cooling (1 MW for computing equipment)
- The exponential increase of the computing resources has a significant impact on the computing centre infrastructure

Courtesy of Dominique Boutigny



# Facility Upgrade (cont.)

- Scheduled 4 days-long complete shutdown of the site in December 2006 for replacing central electric equipment
  - Vital services (network equipment, mail servers, web servers, Oracle, FTS, LFCs, VOMS,...) were kept alive by ad hoc means)
    - Extensive use of virtual machines
  - Others services have been switched to partner sites
    - CIC Portal was hosted by CNAF during the shutdown and switched back to CC-IN2P3 afterwards
    - Failover procedure tested in real conditions



31







LCG

## Site Operation

#### Batch operations


- Passing the LCG job requirements to the local batch scheduler is still necessary
  - Turnaround implemented to modify individual job requirements (memory and CPU) while it is in the BQS queue
    - Set to less than 2 GB for LHCb and more than 2 GB for CMS (in some cases)
- Redefinition of maximum CPU time for some BQS queues to better fit the demand
- Modification of the built-in BQS job monitoring mechanism to detect (and stop the execution of) pathological jobs
  - So not to block selected users while they do some testing (with pilot jobs, for instance)
- Temporary solution for implementing priorities within the same VO based on the VOMS role
  - Tested with Atlas jobs. An equivalent solution will be put in place for CMS
- Increase the usage of the BQS taging of jobs capability
  - For instance, for tagging the jobs requesting dCache so that when dCache (or HPSS) is not available, those jobs are not put in execution
  - Feature also used to regulate the execution of jobs with the same tag

LCG

- Batch operations (cont.)
  - Improvements to BQS planned for 2007
    - Priority handling between jobs within the same VO and between grid and non-grid jobs
    - Associate the whole user's proxy to job information (in addition to just the proxy's subject) and other grid-related attributes of the job (i.e. grid name, grid job id, ...)
    - Use the user's proxy as a criterion for scheduling
      - For instance to prevent execution of a particular user's jobs
  - Currently developing the BQS interface for gLite CREAM computing element
    - Expected to test it by the end of 2007Q1
    - Thanks to Massimo Sgaravatto for his support
    - Many difficulties encountered with the gLite CE interface (reported to the <u>TCG on 01/11/2006</u>)



- Grid services operations
  - Storage Element
    - Stabilizing the SRM-based SE service since the deployment of dCache/SRM v1.7 has been extremely difficult
      - Current service is not yet as stable as with previous release



Traffic into and out of dCache since september 2006



- Grid services operations (cont.)
  - Storage Element (cont.)
    - Service unstability and unavailability severely impacted experiments during late november and december 2006
      - In spite of the efforts deployed by the dCache/SRM developers for finding the roots of the problem
    - Detailed report done by Lionel Schwarz during the <u>dCache workshop</u> in January 2007
    - IMHO, the real issue is how to test, in near real load conditions, a key component such as dCache/SRM before putting a new release in production?




- Continuous effort to develop/adapt/deploy tools for easing the operations of the various grid services
  - Monitoring of FTS activity per channel, dCache activity and dCache errors
  - the ultimate goal is that the operations of the grid services be handled as the operations of the « traditional » services



LCG

## Site Operation (cont.)



## Site Operation (cont.)

#### Grid services

- Target availability of the tier-1 sites require that the grid services be designed and implemented with this goal in mind
  - Redundancy in the services must be possible without the need of current « gymnastics »
- We need to improve the manageability of the grid services
  - Standard interfaces for administering, (remotely) controling, monitoring their activity and standard locations for logs and traces would help a lot in this direction



## Alice

#### PDC06: conclusions

- En 2006 les ressources CPU fournies par LCG-France (T1 & T2s) sont à peu-près celles déclarées dans le MoU LCG
- Ces ressources sont insuffisantes
- Les ressources pour le stockage de données n'ont pas été utilisées du fait de l'absence de SE
- Les tests de transfert T0 → CC ont atteint les taux requis, mais la stabilité du service reste insatisfaisante
- Pas de tests de transfert CC ↔ T2s
- Depuis le début de l'année, le suivi des opérations au CC est problématique, en l'absence d'un contact sur place.

5 fevrier 2007

ALICE@LCG-France

39



Comité Yves Schutz



#### Atlas

## Conclusion provisoire

- Le Tier-1 influence l'efficacité des Tier-2 mais pas toujours
  - Problèmes récurrents de srm au CC
- Chaque Tier-2 a des problèmes spécifiques
- Il faut améliorer :
  - Le monitoring,
  - Plus de checks systématiques,
  - L'implication des sites,
  - Les relations avec les sites
- Cependant...
  - L'efficacité du nuage français est reconnu!

Eric Lançon,

05-fevrier-2007

Eric Lancon

20



# Plans for 2007



## Facility Upgrade


- Project scheduled to be finished by June 2007
  - 3 additional UPS
  - New diesel power generator
  - Additional power distribution equipment in the machine room
  - Additional cooling equipment
- Let's cross our fingers!



## Connectivity

 Increase network bandwidth with tier-2s and backup link to other tier-1s through


FZK





# Courtesy of Jérôme Bernier

## Connectivity (cont.)







## Network bandwidth requirements

#### Summary by experiment

Experiment	Number of Sites	Input		Output	
		Average Bandwidth [MB/sec]	Peak Bandwidth [MB/sec]	Average Bandwidth [MB/sec]	Peak Bandwidth [MB/sec]
Alice	14	30,7	40,7	22,3	29,5
Atlas	17	373,8	522,4	251,6	359,8
CMS	36	132,7	132,7	174,2	404,2
LHCb	9	28,4	28,4	31,8	31,8
	Total	565,6	724,2	479,9	825,3






## Network bandwidth requirements (cont.)

#### Summary by tier level

Tier-1	Number of Sites	Input		Output	
		Average Bandwidth [MB/sec]	Peak Bandwidth [MB/sec]	Average Bandwidth [MB/sec]	Peak Bandwidth [MB/sec]
Tier-0	1	157,0	157,0		
Tier-1	11	229,6	229,6	262,5	262,5
Tier-2	42	179,0	337,6	217,4	562,8
	Total	565,6	724,2	479,9	825,3



Source: https://edms.in2p3.fr/document/I-010099



## Local Network Requirements

- We need to better understand how the data will be accessed by the jobs running in the site
  - Direct impact on the needs of the local network



## Compute Capacity Increase

- On-going call for tenders for compute nodes and disk servers
  - +4,5 M SI2000
    - Non-LHC: 1 M SI2000
    - LHC
      - o Needs for 2007: 1,3 M SI2000
      - Provision for 2008: 2,2 M SI2000 (~40% of capacity required in 2008)
  - +1200 TB (DAS)
    - LHC needs for 2007: 400 TB
    - LHC provision for 2008: 800 TB
  - +160 TB (SAN)



## Compute Capacity Increase (cont.)

#### Cartridge library

10.000 slots, 30 drives, up to 5 PB






LCG

## Grid Services

- Consolidate current grid services and integrate them into « normal » operations
  - Works towards the stability desired not only by the experiments but by the people operating the services at the site



# Consolidation of grid services (by the end of June 2007)



## **Analysis Facility**

- We need to understand what it really means to design and operate an analysis facility
  - A big help from the experiments is required (also) in this area




## New building

- On-going project for building an additional machine room
  - 800 m² floor space
  - Electric power for computing equipment: 1 MW at the beginning, with capacity for increasing up to 2,5 MW
- Offices: for around 30 additional people
- Meeting rooms, 140+ seats amphitheatre
- Target availability: mid 2009



## New building (cont.)





## Conclusions

- Ramp up plans of the site is rather aggressive
  - Several constraints don't really make our life easier
- Operating the grid services in their current status is complex and requires (highly competent and motivated) people
- On-site people dedicated for supporting the experiments are instrumental in optimising the utilisation of the site resources
- Don't understimate your infrastructure needs



## Acknowledgments

- Thanks to the people that contributed material to this talk
  - This presentation would be even longer if I listed them all



## More Information

- LCG-France website <a href="http://lcg.in2p3.fr">http://lcg.in2p3.fr</a>
- LCG-France T2-T3 Technical coordination wiki page: <a href="http://lcg.in2p3.fr/wiki/index.php/T2-T3">http://lcg.in2p3.fr/wiki/index.php/T2-T3</a>
- CC-IN2P3: <a href="http://cc.in2p3.fr">http://cc.in2p3.fr</a>



## Questions







Fabien Wernli, 2006