

# The BEAST II project: Status & Goals



[New logo, courtesy Peter Lewis]

# Contents


- What is BEAST ?
- BEAST II @ SuperKEKB
  - Phases 1 & 2, MiniBEAST
  - Main goals
  - Systems to be installed
  - Status of each
  - Challenges ahead

# BEAST = Beam Exorcisms for A Stable Belle Experiment

*a.k.a. Commissioning Detector*

## Goals:


1. Protect Belle II: Ensure radiation levels safe before Belle roll-in
2. Measure individual beam background components
3. System tests (beam abort, VXD occupancy, cooling, mask control system)
4. Provide real-time feedback to SuperKEKB



BEAST I in the Cave, ca. 1998


*There already was a BEAST. The current effort is really BEAST II.*

# SuperKEKB: Two Commissioning Phases



## BEAST Phase 1: assuming ~ Jan 2016

- Vacuum scrubbing of beam pipe.
- No collisions. Belle will not roll-in.
- Variety of subsystems on fiberglass support structure



## BEAST Phase 2: assuming ~ Feb 2017

- Belle rolled in.
- VXD BEAST (see Marinas, Tanaka talks)
- He-3 & TPC neutron detectors in VXD dock space

*BEAST systems resulted from what could be done, in time, at low cost, by institutes involved. Not the ideal system one would build if starting design from scratch.*

# Systems to be installed


Core BEAST: Part of BEAST stand-alone DAQ

|  | no QCS<br>no solenoid<br>no Belle<br><b>Phase 1</b> | QCS, solenoid, Belle<br>No PXD<br>No SVD<br><b>Phase 2</b> | Full Belle<br><b>Phase 3</b>      |
|--|---|--|-----------------------------------|
| PIN Diodes                                   | 64  | 64   | ?                                 |
| Micro-TPCs fast neutron detectors            | 2-4   | 8 in SVX dock  | 2 - If space allows               |
| He-3 thermal neutron detectors               | 2   | 4 in SVX dock  | 2- If space allows                |
| BGO  | 8   | 8 – if space allows  | -                                 |
| Csl Crystals                                 | 8   | -  | -                                 |
| Beam abort: diamonds                         | final prototype , 4 sensors                         | final system   | final system                      |
| Synchrotron x-ray measurement                | -   | SDDs & ATLAS FE-I4 pixels                                  | -                                 |
| SVD, PXD ladders & monitors                  | -   | 2 PXD half ladders (L1+L2)<br>4 SVD single modules (L3-L6) | Full VXD                          |
| Loss monitors for collimator auto adjustment | -   | PIN diodes<br>Scintillator + MPPC                          | PIN diodes<br>Scintillator + MPPC |
| PLUME CMOS pixels                            | -   | ?  | -                                 |

Will focus on “core BEAST”, overall goals, and non-VXD topics - complementary to other talks

# Phase 1 Design



- Hawaii delivering phase 1 mechanical mounting structure
- Lead: Rosen



- Variety of detector systems on fiberglass support structure
- Some detectors (TPCs, He-3 tubes, PIN diodes) can be easily moved manually
- Full 3D CAD exists (Rosen). Also has been incorporated in the Belle II simulation (Jaegle).
- All parts procured, most assembly, to be used for “MiniBEAST” system test January 2015.
- Disassemble and ship to KEK August 2015.



# Mechanical Mockups



Small-scale mockups have been built to validate mechanical interfaces.

# MiniBEAST

To ensure timely readiness, robustness, mechanical & software compatibility, MiniBEAST integration test starting this month:


- BEAST (Standalone) DAQ
- 2 BGO, 8+ PIN, 2TPCs, 1 He-3, 1 CsI(pure) and 1 CsI (TI)
- Final 37m cables (HV, LV, DAQ) and EPICs code – each institute must supply



MiniBEAST at the University of Hawaii.




# Installation Plan, Phase 1



1.

Install IP bridge: Completed



3.

Install BEAST Phase 1 at IP: Sep & Oct 2015



2.

IP1 chamber for Phase 1.

Repair & Install IP chamber: ~April & May 2015



4.

Add IP shield wall w/ crane Oct-Nov 2015 [tbd]

# Phase 1 Activities


from BEAST, as apposed to SuperKEKB, point of view:

- Phase 1 ends when it is “safe” to roll-in Belle, i.e.
  - SVX beam abort is functional and tested (protects BEAST SVX setup & rest of Belle)
  - Radiation level are acceptable, as measured by PIN diode system. **Need to define quantitative goal.**
- Critical activities
  - Measure x-ray and total particle dose at 64 positions with PIN diode system. More by moving PINs.
  - Test Diamond sensor VXD beam abort system, cross-check abort threshold against PIN diodes
- Desired activities
  - Measure Csl background using 4 pure Csl & 4 Csl(Tl) crystals in ECL location w/ BEAST DAQ
  - First measurements of total dose, x-rays dose, fast neutron flux, thermal neutron flux, versus phi & z
    - Allows first comparison against beam background MC
    - w/ 64 PINs, 2-4 TPCs, 2 He-3 tubes.
    - Requires moving TPCs and He-3 tubes manually
    - Due to large x-ray dose in phase I, TPCs may require lead shields

[Would be nice to repeat for multiple beam /vacuum conditions to disentangle contributions from Touschek/Beam Gas/LER/HER → First crosscheck of beam-gas and Touschek MC]


# PIN Diode System


## Phase 1




64 channels: 8 z-positions X 4 phi positions X 2 diodes (shielded+unshielded)

## Phase 2





# PIN Diodes System II



## CLEO Measurements

Figure 5: Week-by-week integrated dose and their angular distribution.

- Lead: David Cinabro (Wayne State)
- Use PIN diodes, Siemens SFH 206K PIN to measure ionizing radiation dose
- Inexpensive & robust
- Successfully used in CLEO for ~10 years and integrated a dose of  $< 3$  Megarads
- Every 2<sup>nd</sup> diode (in phi) coated with gold-paint
- Allows separating dose from charged particles and x-rays

Synchrotron fan




# PIN Diode Status

- 8 channel prototype delivered, good good performance with final cables
- 64 channels in rack-mount enclosure being assembled at Wayne State
  - parts procured
  - assembly behind original schedule due to lack of manpower, but compatible with new KEK schedule
- Temperature monitoring essential - order placed for commercial system
- New Wayne State postdoc, now resident in Hawaii, to integrate & test
- Ship to send to Hawaii by February 2015, to KEK August 2015



8 channel prototype





# CsI Crystals

- Plan to measure CsI BGs using 4 pure CsI & 4 CsI(Tl) crystals in ECL location
- BEAST DAQ
- Beam-gas & Touschek only, unfocused beams
  - Checks whether simulation can predict these two background reliably
  - Provides data on pure CsI advantage, needed for Canadian calorimeter funding proposals




Holder for pair of crystal, preliminary mechanical design by U. of Victoria.

# Phase II Activities

- Ensure VXD services operational & detector can be safely installed
  - Final test of beam abort
  - Measurement of x-ray synchrotron flux, total dose, occupancy in VXD location
    - validate BP gold layer thickness, modify if needed
      - Use VXD specific sensors (SDDs, FE-I4s) & PIN diodes (see talks by C. Marinas & S. Tanaka )
- Provide BG levels near IP to accelerator via EPICs
- Establish system for mask control
  - Needs more detailed discussion / planning
- Measure individual beam BG components (Toucheq, RBB, Beam Gas)
  - Needed to validate BG simulation, confirm dependence on beam parameters, *and to reliably extrapolate backgrounds to full luminosity*
    - Vary accelerator beam parameters and vacuum pressure (see talk by H. Nakayama)
    - Measure x-rays/charged/neutrons vs Z and phi
      - PIN diodes / loss monitors: x-rays + neutrals vs z and phi
      - TPCs: fast neutrons versus z and phi
      - He-3 tubes: thermal neutrons versus z and phi
- Time-dependence of backgrounds
  - FE-I4 study of VXD injection backgrounds.
  - Can PLUME help?


# Motivation for Neutron Measurements



- Neutron backgrounds highly penetrating; difficult to predict & measure accurately, caused problems already at Belle and Babar
- Will be critical for Belle-II operation and lifetime
  - KLM deadtime, ECL electronics lifetime, TOP PMT lifetime
- Idea: neutrons produced at specific loss-positions along the beam-line. Fast neutrons preserve directional information and can be directionally reconstructed. Use them to “image” loss spots.



# Neutron Detectors

- He-3 tubes and micro-TPCs in dock space
- Complimentary detectors
  - TPCs image direction of incoming fast neutrons, but detected rate is low
  - He-3 tubes measure rate of thermal neutrons, which is high






18



# Measuring Individual Neutron BGs w/ TPCs

I. Jaegle (Hawaii)




(note: Distributions normalized to same area)

Directional detection motivation



1. Isolate neutrons coming directly from beam lines (rather than re-scattered)
2. Measure neutron flux versus polar angle (beam line position) → validate/tune simulation

- nominal beams:  
RBB HER dominates  
→ measure
- Run single beams
  - no RBB
  - measure  
ToucheK
  - vacuum bump  
→ measure  
Coulomb

# micro-TPC Detector Prototyping



Mean direction of nuclear recoils corresponds to neutron source location




Clear excess & peaks in expected direction!





Tiny pre-prototype demonstrated detection principle.

# micro-Time Projection Chambers

- Two constructed (for phase 1)
  - Excellent performance in lab tests
  - Working on improved x-ray rejection and better cable shielding to be ready for the tough commissioning environment
- Eight remaining (for phase 2)
  - Construct in 2015, to KEK March 2016 (needed approx. January 2017)




# He-3 Tubes



Clear response to neutron source observed. First tube being shipped to Hawaii *now*.

# BGO luminosity monitors




- Eight BGO crystals (from Belle Extreme forward Calorimeter)
- To provide independent luminosity measurement via electron coincidence, radiative Bhabha events
- Also can provide analog (real-time) back-ground level to SuperKEKB
- Working prototype w/ electronics exists
- [NTU student visiting Hawaii tomorrow for integration first two BGO crystals into MiniBEAST](#)
- Need to finalize phase II mechanical mounts (SVD endrings)



# BEAST DAQ



P. Lewis (Hawaii)



- Build pseudo-events *independently of Belle*
  - **to accelerator EPICs at 1Hz. Also to mask control?**
  - timestamp for off-line comparison with Belle/accelerator data

# Raw and processed BEAST2 data




BEAST2 has **no trigger** and **no events**. DAQ is asynchronous and slow:

P. Lewis (Hawaii)

- **PIN**: raw ADC output **sampled** at 100kHz, averaged to ~1Hz
- **BGO**: fitted **event** peak amplitude with timestamps, ~0.1s-level timing
- **He3**: Pulses with time information, timing resolution unknown
- **TPC**: triggered **events** with pixel data (time, coordinates and charge), ms-level timing


Consequently, BEAST2 data will consist of:

- Independent databases of raw detector data [ROOT files]
- Summaries and human-readable processed data in “pseudo-events” in a ROOT file
- Pseudo-events will summarize detector data for a fixed interval of time, i.e. 1 second




**Note: If we want MHz rate sensor data, e.g. to study injection backgrounds, it will need to go via a different DAQ path. E.g. beam abort diamond sensors, ATLAS pixel modules.**

# BEAST DAQ Location – 20-30 m from IP




# Monitor DAQ diagram (outdated?)



# Topics I Skipped

The following topics are critical, but I did not really discuss them today. I think/assume they are covered in the talks by Nakayama, Tanaka, and Marinas:

- BEAST II VXD
  - Synchrotron radiation detection
  - Beam abort system
- Mask / Collimator control





# Conclusion & Outlook

- BEAST detectors to provide a rich set of measurements
- Next Major Milestones
  - MiniBEAST at U. Hawaii: Jan 2015
  - Install BEAST at IP: approx. Sep 2015
  - Operate with first beams: mid Jan 2016
- Next Challenges
  - Include PLUME? Urgent to decide. Has impact on rack space, cable space, VXD mechanics. Which DAQ path?
  - Finalize VXD space mechanics (material?)
  - Deliver subsystems to Hawaii on time
  - Finalize cable routing through dock space
  - Develop phase 2 installation plan w/ schedule
  - Develop measurement plan (incl. with accelerator group)

Mini-workshop at KEK Feb 4<sup>th</sup>

# **BACKUP SLIDES**