

Status SiW Ecal

Roman Pöschl







On behalf of



CALICE-France Meeting Paris – October 2016





• SiW ECAL is baseline for future LC detectors



Jet energy resolution 3-4%, Excellent photon-hadron separation



The SiW ECAL in the ILD Detector

Basic Requirements:

- Extreme high granularity
- Compact and hermetic (inside magnetic coil)

Basic Choices:

- Tungsten as absorber material X₀=3.5mm, R_M=9mm, ⊕=96mm Narrow showers Assures compact design

- Silicon as active material

Support compact design Allows for pixelisation Robust technology Excellent signal/noise ratio: ~10



SiW ECAL for a future LC



Physics Prototype

Proof of principle

2003 - 2011



Technological Prototype

Engineering challenges



LC detector



Number of channels : 9720

Weight : ~ 200 Kg

Number of channels : up to 45360 Weight : ~ 700 Kg ECAL : Channels : ~100 10⁶ Total Weight : ~130 t

All well integrated in international collaborations as CALICE, AIDA-2020 and the ILD detector concept

- Jean Claude Brient Contact for ILD Ecal
- R.P. Coordinator of AIDA2020 WP14 on Calorimetry
- D. Grondin, V. Boudry, D. Zerwas: TL WP14
- H. Videau, Executive Team ILD

Roman Pöschl





Tracks in SiW Ecal





PhD Thesis S. Bilokin (LAL) Accepted as CALICE Preliminary Paper over winter



Photon-pion: Separation



PhD Thesis K. Shpak (LLR) In CALICE Editorial Board



CALICE France October 2016



Our sponsors ...





Funding of SiW Ecal since 2002



Horizon2020 European Research Infrastructure SiW Ecal Beneficiaries: LAL, LLR, LPNHE, LPSC, OMEGA Materiel, HR, Travel 2015 - 2019



P2IO "Projet emblematique" SiW Ecal Beneficiaries: LAL, LLR Material, HR, Travel 2016- 2019



European MSC RISE Action Research stays in Japan for machine and detector related R&D SiW Ecal Beneficiaries: All IN2P3 Institutes (in principle) 2015 - 2019

Support from partner bodies like Ecole Polytechnique, Universite Paris Sud, UPMC is herewith explicitly acknowledged as well



AIDA2020 Workpackages









AIDA-2020-MS14

Advanced European Infrastructures for Detectors at Accelerators

Milestone Report

Assembly and QA chain demonstration for highly granular silicon calorimeters

Boudry, V. (CNRS) et al

23 June 2016



The AIDA-2020 Advanced European Infrastructures for Detectors at Accelerators project has received funding from the European Union's Horizon 2020 Research and Innovation programme under Grant Agreement no. 654168.



- Stack of short layers
- Important validation of procedures
- (Combined) beam test in June 2016 ... to be continued in 2017



Assembly chain - Overview





V. Boudry, ECFA Workshop 2016









LLR Palaiseau CNRS, LAL Orsay CNRS, SPP + SEDI Saclay CEA

13



SiW ECAL – Long layer





Successful realisation of a long layer is maybe one of the most challenging R&D projects in worldwide detector R&D

Roman Pöschl

CALICE France October 2016

SiW Wafer R&D

SiW Wafer tests:

Desktop setup with unglued sensors

Well advanced infrastructure for full wafer characterisation Common interest for LC, CMS, ATLAS

High resistive Si Wafer from Hamamatsu Photonics

- Excellent quality!!! e.g. leakage current O(nA/pixel)
- However, expensive (2kEUR/wafer) and Large quantity needed requires quest for further producers e.g. Lfoundry, Infineon, ...

Laser station

SKIROC (Silicon Kalorimeter Integrated Read Out Chip)

SiGe 0.35µm AMS, Size 7.5 mm x 8.7 mm, 64 channels High integration level (variable gain charge amp, 12-bit Wilkinson ADC, digital logic) Large dynamic range (~2500 MIPS), low noise (~1/10 of a MIP) Auto-trigger at ½ MIP, on chip zero suppression Low Power: (25µW/ch) power pulsing

DAQ system

Standard: Giga-ethernet, 8b10b encoded local link, diff. pairs lvds signals over HDMI

Scalable: architecture of a computing network w/o routing, modular software configured using XML, scripted using python.

Compact: one cable for slow control, data acquisition, fast signals and possibly power

ASICs – Recent Production

Two options:

BGA packaged chips

BGA version is safe incremental step: test of chips before soldering ; Space for external decoupling capacitors Symmetric stacking will improve flatness, good for wafer gluing Optimal shielding of signal traces Solution for technological prototype

PCB with naked die

Thin board (~1.2mm)maximal channel density

Tests since 2015
Intensive test programme
e.g. Noise and cross talk

- New production for 2017

Versatile Gluing Robot

Done, FEV11_BGA

Done, HGTD-LGAD

Under discussion, FEV_COB

SiW ECAL Assembly

Pick and place

Precise alignment

Ready for test

- Assembly steps are validated with short layers (13 assembly steps)
- Need big step towards long layer to assure high quality product
 - Automated pick-and-place and alignment
 - Interplay of many different working steps
 - a) Assembly proper
 - b) Continuous control of up to 8 (14) ASUs during assembly
- Successful product requires a lot of testing and exercising of well trained technical staff!!!
- Synergy with ATLAS HGTD and CMS HGCAL (?)

Long slab – Test bench?

Test of HW: long slab

8-10 ASUs stitched in Power-Pulsing

- what can't be done with a small RA source ?
- perf in strong B field, with PP.

V. Boudry, ECFA Workshop 2016

R&D on carbon/fibre structures

• Construction of full size mechanical C/Fibre structures

- up to 2.5m long alveoli
- Interface to other detectors
 i.e. HCAL in ILD

Pioneering work by CALICE France for compact calorimeters

AIDA2020 Milestone on Cooling System

Document identifier:	AIDA2020-MS31
Due date of deliverable:	End of Month 18 (October 2016)
Report release date:	Dd/09/2016
Work package:	WP14: Infrastructure for advanced calorimeters
Lead beneficiary:	DESY
Document status:	Draft

Abstract:

The front-end electronics for both highly granular silicon-based electromagnetic and hadronic calorimeters requires a highly integrated and efficient cooling. Thermal properties of tungsten and carbon fibre based absorber elements drive the cooling concepts of electromagnetic calorimeters; it is the same with the properties of steel absorber stack for hadronic calorimeters. The feasibility and the development of a large leak less water cooling system has been successfully demonstrated for low power calorimeter readout electronics. Thermal modelling and measurements performed on demonstrators constructed within the EUDET project and distributed between two participating labs, fulfil the thermal requirements.

1/26

Grant Agreement 654168 PUBLIC

- Interface to cooling system for compact Carbon/Fibre structures
- Study for EUDET Module -> ILD Detector
- Design backed up by thermal simulation
- Can be adapted to other structures of same type

Towards Full Sized Cooling system

Readout, power supply and all that ...

How to fit services into ~3cm between Ecal and Hcal in ILD

N.B.: Image by M. Anduze and H. Videau (plus some more or less intelligent addenda by R.P.) Design under revision (but challenge remains unchanged)

Testbeams 2017

Standalone test beam

- Late Spring 2017 at DESY
 - ... after debugging of existing stack and progressive integration of supplementary layers
- Autumn 2017 at DESY or CERN
 - Option depending on conclusions of Spring beam test
- What about SLAC > 2017?

Combined test beams

- Autumn 2017 at CERN with SDHCAL
 - - Option if all works well
- More beam tests > 2017
 - ... with SDHCAL
 -with AHCAL

Material:

- Si Wafers
 - 10 additional short layers require 40 Si wafers + spare
 - to be shared between in2p3 and partners
 - Exact sharing to be discussed
 - Purchase would need to launched very soon

=> Conclusive results with technological prototype require investment in wafers

Travel:

- Plan for 2x2 weeks of beam tests in 2017
 - Cost DESY ~ Cost CERN
- Test beams need O(15) people from French SIW Ecal groups
 - Physicists and engineers
- Limited funding through AIDA-2020 TA and HIGHTEC
 - O(3) persons per beam test

=> Need funding for about 12 beam test participants

 \sim 24 weeks since not everybody needs to be there all the time

- SiW Ecal R&D for LC is more challenging than ever
 - Well integrated in local and international R&D networks
 - AIDA-2020 and HIGHTEC until ~end of 2019
 - Cooperation with ongoing LHC detector R&D
- Beam tests with short layers
 - First tests in 2015 and 2016
 - Continuation with extended stack in 2017 (and beyond)
- Gradual move to system aspects
 - Long layers
 - Full sized cooling system
 - Service integration in tight space
 - Quality and assembly chain
 - Stress tests for alveolar structure (not shown today)
- R&D on core components and techniques
 - Silicon wafers
 - ASICs
 - Thin PCBs
 - Gluing

Backup

- Testbeams
 - Physics prototype
 - 2005 DESY (standalone)
 - 2006-2007 CERN (with analogue Hcal)
 - 2008 and 2011 FERMILAB (2008 with analogue Hcal, 2011 with digital Hcal)
 - Technological prototype
 - 2012-2013 DESY
 - 2015-2016 CERN (2016 with SDHCAL)
- Combined testbeams within CALICE, data management through grid vo calice (data storage at DESY and CC IN2P3)
- Publications
 - 6 papers in peer-reviewed journals out of which 5 with French groups as principal authors or with major contributions
 - Numerous contributions to major conferences including peer-reviewed conference proceedings

Retriggers in successive bunch crossings

Towards model of hardware behaviour

=> Deep understanding of detector response

SiW ECAL – Short layer

Between 12 and 15 short layers for HGCFC beam tests

R. Cornat LLR

Roman Pöschl

CALICE France October 2016

In principle, front-end boards will be chained forming up to 2m long detector SLAB, most of signals in bus

Issue 1 : clock distribution (5 & 50 MHz) Interconnects are not impedance controlled (FFC) One clock line may be loaded by 40 to 80 ASICS

- ⇒ Use of MLVDS adapted with 100 Ω on both sides, 100 mVpp remaining signal at the end (6 Ohms loss/board, 20-40 pF/board, up to 10 boards)
- ⇒ Next version ASIC will have a PLL generating the highest frequency

Issue 2 : Power distribution (12 A pulses) & blocking capacitors (tested with FET switches as loads)

 \Rightarrow Current taken from a 800mF super cap (16m Ω ESR) + 2mF/board

Along 6 boards, static loss is 250 mV due to connectors (w/o chips). May foresee to distribute power in a star topology. 4 boards SLAB being assembled at LAL

R. Cornat LLR

large C-W structure exists

SiW ECAL – First short layers

Test bench and beam test setup of first short layers with preliminary assembly

V. Boudry LLR

Assembly of SiW Ecal layers

Use of Fiber-Bragg Gating Sensors for the characterisation of deformation of composites structures

Platform CAPTINNOV

... has been already used for CALICE wafer cahracterisation

R. Cornat LLR

Roman Pöschl

CALICE France October 2016

CALICO SIW ECAL Assembly – Preliminary consideration IN2P3

<u>Guiding lines :</u> Ease of assembly Easetofabricate the elements Robustness Compactness

J. Bonis/A. Thiebault