



Gravitational wave detectors and observation runs: status

Mike Landry LIGO Hanford Observatory/Caltech for the LIGO and Virgo Scientific Collaborations





O1 events







Comparing the three events



Phys. Rev. Lett. 116, 241103, Phys. Rev. X 6, 041015 (2016)







Optical configuration





Seismic Isolation LIGOSUS designed and contributed by UK/GEO Ground Motion at 10 [Hz] ~ 10⁻⁹ [m/rtHz] $\Delta L = h \ L \sim 10^{-19} \ m \ / \ Hz^{1/2}$ Need 10 orders of magnitude Test masses are suspended from 7 stages of active and passive vibration isolation Matichard, F., et al. Proc. ASPE (2010)Aston, S. M., et al. CQG 29.23 (2012): 235004. Last two stages are monolithic to improve **Brownian noise** h Cumming, A. V., et al. CQG 29.3 (2012): 035003. 6



200W Nd:YAG laser



Designed and contributed by Max Planck Albert Einstein Institute





- Stabilized in power and frequency using techniques developed for time references
- Uses a monolithic master oscillator followed by injection-locked rod amplifier
- Delivers the required shot-noise limited fringe resolution





Post-O1 commissioning: L1

- Diagnosis and reduction of noise from scattered light off moving surfaces
 - » Several scattering sites identified in L1
 - » Compensation plate now "correctly" misaligned
 - Scattering from photon calibrator periscope mirror identified, addressed in current vent (more on this later)
 - » Scattering and relative motion among one end station optics partially addressed
- Test-mass bounce/roll dampers, new photodiodes, new pre-mode cleaner, Faraday isolator, etc., in L1.
- Removed accidental noise from temperature sensor instrumentation in L1





Post-O1 commissioning: H1

- High power stage (HPO) of H1 laser activated
 - » Required enhancements to angular controls
 - » Modified thermal compensation
 - » Development of techniques to reduce buildup of optomechanical parametric instabilities
 - » Study of beam jitter/geometry noise coupling to detector: excess beam jitter (both pointing and breathing mode) noted, plus excess coupling
- Beam rotation sensors (BRS)
 - » Tilt meters at both end stations allow for tilt-horizontal decoupling
 - » More robust interferometer operation in times of high microseism and winds at LHO





- The second Advanced LIGO run began on November 30, 2016 and is in progress. As of the current vent, approximately 75 days of Hanford-Livingston coincident science data have been collected, with two breaks (holiday season, current vent)
- Average reach of the LIGO network for binary merger events have been around 70 Mpc for 1.4+1.4 Msun, 300 Mpc for 10+10 Msun and 700 Mpc for 30+30 Msun mergers, with relative variations in time of the order of 10%.
- Approx. 45% of runtime has been coincident data (50% without recent vent downtime)
- Six alerts sent to EM/v partners G1701002-v1 GV







O2 Range









LIGO network duty factor Double interferometer [44.8%] Single interferometer [28.5%] No interferometer [26.6%]





O2 Volume



Displacement noise – L1

- Noise model of highrange data segment in Livingston detector
- Tracks shot noise at high frequencies
- Tracks servo-induced noise at low frequencies.
- Slight excess 30-100 Hz, attributed to light scattering from moving surfaces.

G1701002-v1







BRS – Beam rotation sensor

- Mitigation of tilt-horizontal coupling required for good low-f detector performance
- BRSs installed in both LHO endstations, plus prototype cornerstation version: U. Washington







BRS impact at LHO



G1701002-v1





H1 ITMX contamination



- One-day vertex vent requires ~2 week pumpdown before lifting gatevalves
- Additional work: Hartmann y-path, baffle damping G1701002-v1

- Hartmann wavefront sensor images show point absorber on ITMX
- Possible mechanism for beam jitter coupling
- Elected to vent H1 vertex







Cornerstation vent at LHO

- Inspection did not yield obvious contamination at the site indicated by Hartmann analyses
- Found evidence of contamination sites on ITMX, origin not completely clear
- Test-cleaned at limb of optic, FirstContact cleaned HR surface
- Gatevalves opened last week, relocked and find point absorber still present





G1701002-v1





Hanford DOE May 9th event



- 20' cave-in of a train tunnel at the DOE Purex Facility12 miles east of the H1 vertex
- No airborne contamination detected
- Breach filled with 50 truckloads of clean soil

- There are to be 269 calendar days in O2: we vented for 1 day
- The only day (ever) we've been asked to shelter-in-place at LHO was May 9, the same day as our single-day vent of O2



G1701002-v1





Endstation/HAM1 vent at LLO

- Vented L1 EY station and removed camera transport mirrors
- Scattered light peaks mitgated









GEO Astrowatch

- Don't miss a large, "nearby" GW event
- Current GEO 600 instrument science aspects require a working detector: bring GEO back to data taking mode over nights and weekend



- Since end of O1: Astrowatch + instrument science
- No significant reduction of experimental work during O2 → we aim for a duty cycle of >70%.
- Astrowatch will continue past O2

Note: a 2nd ~2week downtime is planned for the 2nd half of 2017 to fix MSR suspension OSEMs.

C. Affeldt/J. Hough





GEO Research

- Squeezing
 - injection loss: new faraday optimization, HOM scattering reduction
 - 4.4dB highest observed squeezing level
- Beam Splitter Thermal Compensation & power up
- heater array imaged on the beam splitter
- imaging lens recently installed (invacuum)

Else:

- Output Mode Cleaner AA (MDWS)
- Polarization Effects (from IFO)
- Noise at medium frequencies
- Optical AC Coupling
- Bilinear Noise Couplings with Signal Recycling







ADVANCED VIRGO

6 EU countries 20 labs, ~250 authors

APC Paris **ARTEMIS Nice** EGO Cascina **INFN** Firenze-Urbino **INFN** Genova INFN Napoli INFN Perugia INFN Pisa **INFN Roma La** Sapienza INFN Roma Tor Vergata INFN Trento-Padova LAL Orsay - ESPCI Paris LAPP Annecy LKB Paris LMA Lyon NIKHEF Amsterdam POLGRAW(Poland) RADBOUD Uni. Nijmegen RMKI Budapest University of Valencia





Virgo status

- Advanced Virgo operating with stable lock on dark fringe
- >85% duty cycle in recent commissioning run
- Sensitivity steadily improving





N. Leroy, A. Rocchi



Advanced Virgo

Virgo pathway to O2

- Path to join O2 includes:
 - Improve power recycling cavity (PRC) stability with thermal compensation (TCS)
 - » Suspend the detection bench (includes output photodiodes)
 - » Employ low noise actuation
 - » Make use of noise subtraction techniques
 - » Initiate weekend engineering/ science runs
 - Increase interferometer input power from 13W to 25W
 - » Noise hunting!



AdV best BNS range (from May 7 to May 27)





Virgo post-O2 work

- Window of opportunity to increase stability and sensitivity
- Minimize interferometer downtime due to installations
- Prioritize with respect to sensitivity gain/impact on commissioning
- Upgrades being considered
 - Monolithic suspension >>
 - » GEO squeezer

These are the priority items

- » High-power laser
- » Signal recycling mirror (requires auxiliary lasers for locking)





Observing scenario







Post-O2 commissioning





