

J-PARC (Particle) Physics

Recent Progress

1. Commissioning of accelerator and beam line
2. T2K (neutrino oscillation exp.)
3. $K^0 \rightarrow \pi^0 \nu \nu$ CP violation study
4. Muon physics $g-2$, μe conversion search
5. Accelerator status and plan

May 21, 2009@FJPPL'09


Koichiro Nishikawa

KEK

KEK Roadmap

2009-2013


Energy Frontier



Flavor Physics at Luminosity/Intensity Frontier



- According to the JAHEP community's master plan,
 - Highest priority is given to ILC
 - Before ILC, promote flavor physics at KEKB and **J-PARC**
- Action before the ILC approval
 - ILC R&D
 - **Completion/commissioning of J-PARC**
 - **Considering the world competition, it is urgent to improve neutrino intensity**
 - Continuation of KEKB/Belle with upgrade



Commissioning Status

J-PARC Facility (KEK/JAEA)

South to North

Linac

3 GeV Synchrotron


Neutrino Beams (to Kamioka)

Materials and Life Experimental Facility


Hadron Exp. Facility

- JFY2007 Beams
- JFY2008 Beams
- JFY2009 Beams

Bird's eye photo in January of 2008



Primary proton beam line:
combined function SC magnets



Slow beam extraction
to Hadron Hall

fluorescence plate just
in front of target




Target station



Graphite target

Recent important milestones:

- December 23, 2008:
 - ❖ 30 GeV beam acceleration and fast extraction to the beam abort dump
 - ❖ MLF user run (20kW)
- January 27, 2009:
 - ❖ 30 GeV beam extraction to the Hadron Experimental hall using slow beam extraction system
- February 19, 2009:
 - ❖ Government inspection for radiation safety (Hadron hall)
- April 23, 2009:
 - ❖ 30 GeV beam extraction to the neutrino target station using fast beam extraction system



T2K Collaboration



~ 400 members from 12 Countries

Japan, US, Canada, **France**, UK, Switzerland, Poland, Korea,
Russia, Spain, Italy, Germany

Tokai-to-Kamioka (T2K) long baseline neutrino oscillation experiment




Super-Kamiokande
(ICRR, Univ. Tokyo)




J-PARC Main Ring
(KEK-JAEA, Tokai)



ν_e appearance (θ_{13})



- Goal
 - **Discover ν_e app.**
 - ν_μ disapp. precision meas.
- Intense narrow spectrum ν_μ beam from J-PARC MR
 - Off-axis w/ 2~2.5deg
 - Tuned at osci. max.
- SK: largest, high PID performance



1600 ν_μ CC/yr/22.5kt
(2.5deg)

Neutrino beamline

- 5 year construction 2004~2009
- Construction completed on schedule!


Neutrino monitor build.



Electromagnetic horn




Graphite target



UA1 magnet donated from CERN installed in Apr-Jun, 2008 on schedule



Beam dump completed




Decay volume completed



Target station completed



Primary proton beam line completed



Superconducting Magnet System



- Installation Completed In Dec. 2008
- Cool Down started Jan 2009
- Excitation Test started Feb 2009

- 4400A (30GeV nominal)
 - quench tests for all the magnets
 - 48 hour excitation test
- 5000A excitation test
 - after full magnet quench
- Main SC Magnet performance
 - OK for spring beam test


Superconducting magnets (II)

- Magnet safety system (MSS) (Saclay)
 - Installation completed on schedule
 - Commissioning successfully completed
 - Working very well!
- Corrector coils (BNL, US)
 - 3 SC Corrector magnets made by BNL installed

MSS (from Saclay)



*Assembled Corrector
Inter-Connect (from BNL)*



T2K beamline started operation!

First shot after turning on SC magnets at 19:09, Apr.23, 2009



Muon monitors

(installed behind beam dump)

Muon monitor signal




Ionization Chambers Silicon detectors



First observation of muons produced in neutrino beamline


T2K beamline started operation!

MR intensity




After ~10 shots for tuning, proton beam hit around target center


Muon monitor signal




Proton beam profile monitor along nu beamline



Muon monitor profile




OTR detector just in front of target (fluorescence plate)



T2K beamline started operation!





280m Near detectors : being installed





On-axis detector: INGRID

LLR/Ecole Polytechnique
IPNL/LYON
Kyoto University
Osaka University



- INGRID : 7 (Hori.) + 7 (Vert.) + 2 (Off-axis) modules
- Module : 9 Iron targets + 11 Scinti. planes + Veto planes
- Scintillator plane : 24 ch x 2 layers
 - Scintillator + WLS Fiber + MPPC
- Assembly of all 228 tracking planes completed
- First module completed and installed. Ready for beam
- Remaining 15 modules will be installed in summer



Off-axis Detectors


FGD(Canada)



TPC(Canada/Fr)




Elec(UK,Fr)



12-FEM board stack-up before burn-in phase



P0D(US)



ECAL(UK)




SMRD(Jp,US,Pol,Rus)

- Under construction and testing in each country
- Installation after August
- To be ready for the beam from Winter

TPC w/ Micromegas

- TPC#0 is equipped with 24 (full) micromegas modules.
- Construction of TPC#1 / #2 going well.




Saclay



ASIC IC for TPC/FGD



Saclay




Beam test @ TRIUMF



KOTO

K^0 CP violation experiment

Rare Kaon Decay $K_L^0 \rightarrow \pi^0 \nu \bar{\nu}$





KEK
E391a
Run2

New
Physics

SM
Step 1

Step 2

- direct CP-violating rare decay for Physics beyond the Standard Model





- NA62 at CERN-SPS for $K^+ \rightarrow \pi^+ \nu \bar{\nu}$

Beam line is being constructed

Beam survey in 2009

J-PARC **KOTO** experiment (K0 at Tokai)

- To study physics beyond SM by measuring branching ratio of $K_L \rightarrow \pi^0 \nu \bar{\nu}$
- Modify KEK-E391a detector
 - (a) Upgraded CsI calorimeter
 - (b) Readout: waveform digitization
 - (c) New photon veto in the beam



Muon programs
g-2, μe conversion


New Generation of Muon g-2@J-PARC

Proposal in preparation

- Current result is 3.4 sigma above from the SM value
- New generation of muon g-2 experiment is being explored at J-PARC
 - To establish the deviation by improving the statistics and systematics
 - To further explore new physics
- With completely new technique
 - Off magic momentum with **ultra-cold muon beam** at 300 MeV/c
 - Stored in **ultra-precision B field** without E-field so that the $\beta \times E$ term drops



H. Okada



Muon EDM


- Direct CPV in Lepton Sector

- Current Exp. Limit $\sim 1e-19$


- Potential Sensitivity of J-PARC

 - $\sim 1e-22$ @ MLF

 - $\sim 1e-24$ w/ PRISM



cLFV Search using high-intensity pulsed muon beam




- Quark mixing
 - Precision meas. at B Factories
- Mixture in charged lepton sector
 - Investigation at J-PARC
 - Most sensitive in $\mu \rightarrow e$
 - Motivated by GUT and Seesaw
- Mixture in neutral lepton sector – Neutrino Oscillation
 - SuperK etc.
 - Precision meas. at K2K, T2K





COMET at J-PARC

- mu-e conversion search experiment at J-PARC
- Target sensitivity $\sim 10^{-16}$ (current limit 7×10^{-13} by SINDRUM II)
- SUSY-GUT models predict $< 10^{-13}$

Muon Capture (MC)




Muon Decay in Orbit (MDO)




Requirements

- Pulsed Proton Beam
 - π -b.g. suppression
- Large μ yields
 - J-PARC/MR 50-60kW
 - π -capture SC-solenoid
 - 10^{11} μ /sec (cf. $10^8 \mu$ /sec at PSI PiE5)
- Curved-solenoid detector
 - Lower detector rate



COMET Activity Status


- Beam Extinction Study
 - Abort line measurement



- Single bunch, single shot operation of MR
- **Count the number of protons in the EMPTY bucket in front of the filled one**


- Secondary beam line measurement
 - Measure secondary particle time structure relative to a reference signal from the MR
 - **MR operation with empty buckets**
 - **Bunched slow extraction**

- Extinction monitoring device development
 - Gating PMT for a Gas Cerenkov detector, 1MHz switching with 10^6




- Super-conducting solenoid
 - Pion capture solenoid


- B=5T
- Radiation transparent
- Technology
 - Detector Solenoid Tech.
 - NbTi+Al conductor
 - Indirect pipe cooling
 - Conductor development in 2009
 - Test coil construction and test in 2-3 years



- Design of high Intensity muon beam line



- AC-dipole development



- Collaboration with FNAL
- Conductor Development



- 1st version corona-tested
- 2nd version built



- Single brick test soon



A possible layout of the beam lines at Hadron Facility.
K1.8, K1.8BR, and KL are implemented as of July, 2009.



K1.8 (Day-1)

- (E05): Spectroscopic study of hypernuclei
- (E13): Gamma-ray spectroscopy of light hypernuclei
- (E19): Pentaquark search in $\pi p \rightarrow K^+ X$

K1.8 (stage-2)

- (E03): Measurement of X-rays from Ξ Atom
- (E07): Double strangeness system

K1.8BR (Day-1)

- (E15): Search for deeply-bound kaonic nuclear states
- (E17): Precision spectroscopy of kaonic ^3He

K1.1

K1.1BR (stage-1)

- (E06): Measurement of T-violation in $K^+ \rightarrow \pi^0 + \mu^+ + \nu$

High- P_T (stage-1)

- (E16): Chiral symmetry in QCD

KL (stage-2)

- (E14): $K_L \rightarrow \pi^0 + \nu \bar{\nu}$

COMET (New beam line, deferred)

- μ -e conversion experiment at sensitivity of 10^{-16}

Accelerator Status and Plan

Beam commissioning has been accomplished on schedule,
BUT with low intensity.

Real challenge toward the power frontier machine just started.

1. Many **issues** (unreliable components, design etc.) to be solved
2. Beam must be provided to the **users**
3. **Power upgrade** should be also accomplished steadily.

- RFQ discharge problem:

- RF core long term stability problem:

- Stability of MR power supply and beam loss

- No problem for fast extraction with a level of 100kW operation



- Need more stability for slow extraction

- Clearly need major improvement for MW operation

Three serious issues which may give impact to the schedule:

1. **Linac: RFQ**
2. **RCS: RF FM core**
3. **MR: Magnet Power Supply**

Discharge problem in the RFQ limits both beam power and availability.







Inside of RFQ

We are earnestly making a **backup RFQ**, which will be replaced during summer shutdown in 2010

Vacuum vessel of RFQ
Poor vacuum design


Pi mode **Stabilizing Loop**

Poor surface fabrication method




Three serious issues which may give impact to the schedule:

1. Linac: RFQ
2. RCS: RF FM core
3. MR: Magnet Power Supply



18枚中11枚のコアに損傷が見られた。予備のコア(2)を入れて4月の運転に備える。至急、新規にコアを製作。


Compression buckling due to thermal stress



200 cores are used for RCS cavities
Unit cost: 40k dollar !




Temperature distribution



Core center
Z-component of stress


Strong thermal stress @ 5kW loss



-70.6MPa 29.0MPa


Slow extraction: Bump magnets ON
 Resonant sextupoles ON
 Tune ramp pattern for QFN: (22.30, 20.78) -> (22.35, 20.78)

Slow extraction tuning and beam loss



It's a "Ripple extraction" using SX system
 We need;
 ->further improvement of magnet power supply
 ->installation of feedback system



Beam intensity during extraction



Spill measurement in HD beamline

RF off, $\xi \sim 0$

RF off, $\xi \sim -2$



Summary

Neutrino

1. **Early achievement of 100kW run (for 10^7 sec, in 2010)**
2. **Create strong team to consider and work for the power upgrade scenario from 100 to 750kW.(2011~)**
1. **The above second step should be the base of the MW-class power frontier machine.**

Hadron

1. **Early realization of spill control by;**
 - **improving magnet power supplies, and**
 - **applying feedback system.**
2. **Early achievement of 10kW-class power by;**
 - **understanding and suppressing and/or localizing the beam loss.**
3. **In order to realize 100kW-class slow beam extraction, we have to develop;**
 - **excellent extraction efficiency,**
 - **more beam loss control, and**
 - **radiation maintenance technology.**