



## Testbeam 2019 – Status at LAL

Dominique Breton, Julien Bonis, Alexandre Gallas, Jimmy Jeglot, Adrian Irles, Jihane Maalmi, Roman Pöschl, Alice Thiebault, Dirk Zerwas




Testbeam preparation meeting 20/3/19


## Objectives:

- Comparison of ASU based on BGA and of ASU based on COB  
Two of each type = 4 ASUs
- Test of new SL-Boards


- FEV-BGA
  - 1 FEV11 completely cabled
  - 2 FEV12 will be cabled until middle of April
- FEV\_COB
  - 1 FEV COB equipped with ASICs,
  - 2 FEV\_COB will be bonded until beginning of April
- 10 SL Boards -> Reminder see next slide
- Huge number of GradConn Connectors
- 1 SMBv4 for check-out of ASUs



Approximately 6cm between Ecal and Hcal




Guiding/receiving signals to/from slabs







SL Board at the end of layer

CORE Kapton – replaces bulky HDMI cables



- Hardware exists:
- Firmware for communication with ASICs about to be written








Rack for short slabs for beam test :


- support dimensioned for for ASU+SL-board
- support can integrate 7 short slabs courts et 8 W layers (or 15 short slabs after some modifs.)
- Vertical positioning of short slabs courts between 2 grooved plates, light tight closing and cables passages


- 
- All ASU (w/o wafers) available or available soon (already now enough for immediate tests)
    - Enough SK2a for chip bonding
  - Check-out with SMBv4 board
  - SMBV4 available but needs to be equipped with GradConn Connectors and need some minor soldiering work
    - **SMBv4 availability is critical to ensure well functioning ASUs**
    - GradConn connectors will get mounted until beginning of April
    - Soldiering work in collaboration with Remi during next two weeks
  - Firmware for SL Board about to be written
    - Will take however at least two more months




- LV crate cabled and available
- About to cable box for HV distribution and current measurement with Keithley
- Patch panel cabling can start soon, i.e. next week
  - Need to settle cable lengths between panel and layers
- In addition several auxiliary cables for testbench work have been manufactured or will be manufactured
- Thanks to Francisco Campos



- 
- Four layers are equivalent to 16 wafers
  - At LAL we dispose 2 full size wafers of 500mm
    - Two more wafers from LLR and from LPNHE in exchange for TLU Purchase
  - Need 10 more from “French Stock”
  - What is the “French Stock”?
  - In contact with LPNHE for availability of gluing robot
  - Schedule depends critically on availability of SMBv4 (see above) but expect that gluing could start ~beginning of may at the latest (modulo bad surprises from ASUs)

- 
- On track for beam test
  - The “scene is settled” but April will be critical month
  - Regular (~weekly) technical briefings at LAL to monitor progress


Heat exchanger:



- Need to bring the individual pieces together

- A first meeting between developers of Cooling system and developers of SL-Card revealed no showstopper on integration

SL-Board:



- R&D for SiEcal addresses all elements relevant for an installation into the ILD detector
- Current effort concentrates on space reduction of individual components (i.e. Digital r/o)
- Altogether we believe that we can build the SiEcal largely as designed
- Design of SiEcal puts several constraints on other detectors
- 5 Hubs of type Hub1/stave between Ecal and Hcal may constitute a heat source ( $\sim 10$  W each)
  - Should not forget the 50 Hub2/stave with  $\sim 3$ -5 W consumption each
- Need a decision on how TPC will be fixed
- Need a decision whether we will be allowed to stay on the platform
  - If not need to find space at corresponding height in service gallery
- Update of ICD in progress

Backup




- **LAL/OMEGA collaboration with Corean Group of SKKU (EOS company for the PCB)**
  - FEV11\_COB: **10 boards of 1.2mm**, good planarity and good electrical response.
  - SK2a wirebonded at CERN (Study by LPNHE and P2IO Platform CAPTINNOV)

- **Successful debugging w/o sensors:**
  - (~4% of noisy channels, good response to injected signals)

- **Debugging with sensors (baby wafers 3x3 px)**
  - The system was not ready for test at DESY@2018.
  - New wafer testbench setup in LAL borrowed from LPNHE.
  - Duplication ongoing at LAL (using the CAPTINNOV platform)

Visual  
inspection of  
the result of  
the gluing




- • 3 baby wafers characterized, glued and tested with cosemics. Test with radioactive sources are in preparation.


A. Example of  
MIP spectrum  
from cosmic  
rays.

B. 3.6pF

**Plot from V.  
Lohezic**



A. Example of MIP spectrum from cosmic rays.



A. Hit map with for  
cosmic runs.

B. (different mapping  
to BGA versions)

C. Baby wafer tested  
in DESY. Some glue  
is spilled.