

# CEPC Accelerator EDR in Synergy with other Accelerator Projects in China

Jie Gao

IHEP



CEPC Workshop EU Edition, April 8-11, 2024, Marseille, France




# Contents


---

- **Introduction**
- **CEPC accelerator development in TDR and EDR**
- **Status of other accelerator projects under construction in China**
- **Synergies issues with CEPC**
- **Summary**

# Timelines in Snowmass Energy Frontier Summary




**CEPC EDR and construction will be in close synergy with other accelerator projects under construction in China (light sources, XFEL, Nuclear physics, etc).**






# CEPC Higgs Factory and SppC Layout in TDR

CEPC as a Higgs Factory: **H, W, Z**, upgradable to **ttbar**, followed by a SppC (a Hadron collider)  $\sim 125\text{TeV}$   
 30MW SR power per beam (upgradable to 50MW), high energy gamma ray 100Kev $\sim$ 100MeV






CEPC collider ring (100km)



CEPC booster ring (100km)

## CEPC TDR S+C-band 30GeV linac injector



CEPC/SppC in the same tunnel



# CEPC Accelerator System Parameters in TDR

## Linac

Parameter	Symbol	Unit	Baseline
Energy	$E_e/E_{e+}$	GeV	<b>30</b>
Repetition rate	$f_{rep}$	Hz	100
Bunch number per pulse			1 or 2
Bunch charge		nC	1.5 (3)
Energy spread	$\sigma_E$		$1.5 \times 10^{-3}$
Emittance	$\varepsilon_r$	nm	6.5


## Booster

		<i>tt</i>		<i>H</i>		<i>W</i>		<i>Z</i>	
		Off axis injection	Off axis injection	On axis injection	Off axis injection	Off axis injection			
Circumfer.	km	<b>100</b>							
Injection energy	GeV	<b>30</b>							
Extraction energy	GeV	<b>180</b>	<b>120</b>		<b>80</b>	<b>45.5</b>			
Bunch number		35	268	261+7	1297	3978	5967		
Maximum bunch charge	nC	0.99	0.7	20.3	0.73	0.8	0.81		
Beam current	mA	0.11	0.94	0.98	2.85	9.5	14.4		
SR power	MW	0.93	0.94	1.66	0.94	0.323	0.49		
Emittance	nm	2.83	1.26		0.56	0.19			
RF frequency	GHz	1.3							
RF voltage	GV	9.7	2.17		0.87	0.46			
Full injection from empty	h	0.1	0.14	0.16	0.27	1.8	0.8		

## Collider

	Higgs	Z	W	<i>t</i> $\bar{t}$
Number of IPs	2			
Circumference (km)	<b>100.0</b>			
SR power per beam (MW)	<b>30</b>			
Energy (GeV)	<b>120</b>	<b>45.5</b>	<b>80</b>	<b>180</b>
Bunch number	268	11934	1297	35
Emittance $\varepsilon_x/\varepsilon_y$ (nm/pm)	0.64/1.3	0.27/1.4	0.87/1.7	1.4/4.7
Beam size at IP $\sigma_x/\sigma_y$ (um/nm)	14/36	6/35	13/42	39/113
Bunch length (natural/total) (mm)	2.3/4.1	2.5/8.7	2.5/4.9	2.2/2.9
Beam-beam parameters $\xi_x/\xi_y$	0.015/0.11	0.004/0.127	0.012/0.113	0.071/0.1
RF frequency (MHz)	650			
Luminosity per IP ( $10^{34} \text{ cm}^{-2} \text{ s}^{-1}$ )	<b>5.0</b>	<b>115</b>	<b>16</b>	<b>0.5</b>

## Transport lines



CEPC Technical Design Report (TDR) includes:  
 1) CEPC Accelerator TDR  
 2) CEPC Detector TDRrd (rd=reference design)  
 will be released by June 2025




# CEPC Key Technology R&D Status in TDR

Specification Met



Prototype Manufactured



Accelerator	Fraction
Magnets	27.3%
Vacuum	18.3%
RF power source	9.1%
Mechanics	7.6%
Magnet power supplies	7.0%
SC RF	7.1%
Cryogenics	6.5%
Linac and sources	5.5%
Instrumentation	5.3%
Control	2.4%
Survey and alignment	2.4%
Radiation protection	1.0%
SC magnets	0.4%
Damping ring	0.2%

Key technology R&D in TDR spans all component lists in CEPC CDR







# CEPC Booster 1.3 GHz 8 x 9-cell High Q Cryomodule

CEPC booster 1.3 GHz SRF R&D and industrialization in synergy with CW FEL projects.

Parameters	Horizontal test results	CEPC Booster Higgs Spec	LCLS-II, SHINE Spec	LCLS-II-HE Spec
Average usable CW $E_{acc}$ (MV/m)	23.1	$3.0 \times 10^{10}$ @ 21.8 MV/m	$2.7 \times 10^{10}$ @ 16 MV/m	$2.7 \times 10^{10}$ @ 20.8 MV/m
Average $Q_0$ @ 21.8 MV/m	$3.4 \times 10^{10}$			



# CEPC High Efficiency High Power Klystron Development and RF Power Distribution System


## CEPC klystron R&D



Klystron No. 1  
Efficiency 65%  
(2020)



Klystron No. 2  
Efficiency 77%  
(2021)



Klystron No. 3 (MBI)  
Efficiency 80.5%  
(under fabrication)

## Power Supply Modulator




**77.2% @ 849kW pulsed in 2024**

2022


**Pulsed RF Mode (30% duty factor, 60ms/5Hz)**

High Voltage vs. Power&Efficiency




**70.5% @ 630kW**



Power vs. Efficiency



To be tested at the end of 2023



## RF distribution plan



- Three prototypes of the **650MHz 800KW CW** klystrons are developed. The efficiency reaches 70%
- PSM is developed with the industrial collaboration
- RF tunnel distribution was planned






# CEPC Accelerator Main EDR Development: Klystrons

Klystron R&D



Klystron No. 1  
Efficiency 65%  
(2020)

Klystron No. 2  
Efficiency 77%  
(2021)





Klystron No. 3 (MB)  
Efficiency 80.5%  
(under fabrication)

**77.2% @ 849kW pulsed in 2024**

Pulsed RF Mode (30% duty factor, 60ms/5Hz)

70.5% @ 630kW



High Voltage vs. Power & Efficiency



Parameters	Value
Frequency	5720 MHz
Output Power	80MW
Pulsed width	2.5us
Repetition rate	100Hz
Gain	54 dB
Efficiency	47%
3dB bandwidth	±5MHz
Beam voltage	420 kV
Beam current	403 A
Focusing field	0.28 T

**CEPC collider ring 650MHz klystron development in TDR phase**

**C band 5720MHz 80MW Klystron**





**C band 5720MHz 80MW Klystron design progress**



# CEPC Plasma Injector (alternative option) and TF Plan<sub>10</sub>

CEPC plasma injector scheme:  
 From 10 GeV → 30 GeV → **TR ≥ 2**

Simulation results show that it works on paper with reasonable error tolerances for both electron and positron beams injected to the booster



- Phase I (Year0-Year2)**
1. Re-design and install transport beamline system, optimize the e- / e+ beam quality
  2. Clean room and high power klystron installation (200TW)
  3. Beam instrumentation
  4. RF Gun platform
  5. Commissioning and optimization systems
- Phase II (Year3-Year4)**
1. High power klystron installation (1PW + 20/40 TW)
  2. Commissioning and optimization systems
- Phase III (Year5-Year6)**
1. Commissioning and optimization systems
  2. Commissioning and optimization systems

**Positron and electron acceleration**  
**Cascading acceleration**  
**Future linear collider technologies**  
**High energy beam for detector R&D**  
**(possible application)**


**PWFA/LWFA TF based on BEPC-II Linac and HPL has been founded by CAS 90M RMB in Sept. 2023**




# CEPC Accelerator International TDR Review and Cost Review June 12-16, and Sept. 11-15, 2023, in HKUST-IAS, Hong Kong



CEPC Accelerator TDR Review  
June 12-16, 2023, Hong Kong



CEPC Accelerator TDR Cost Review  
Sept. 11-15, 2023, Hong Kong



Domestic Civil Engineering  
Cost Review, June 26, 2023, IHEP




9<sup>th</sup> CEPC IAC 2023 Meeting  
Oct. 30-31, 2023, IHEP



Table 12.1.2: CEPC project cost breakdown, (Unit: 100,000,000 yuan)

Total	364	100%
Project management	3	0.8%
Accelerator	190	52%
Conventional facilities	101	28%
Gamma-ray beam lines	3	0.8%
Experiments	40	11%
Contingency (8%)	27	7.4%



Distribution of CEPC Project total TDR  
cost of **36.4B RMB**

**CEPC accelerator TDR has been completed and  
formally released on December 25, 2023**


**CEPC accelerator TDR link:** ([arXiv: 2312.14363](https://arxiv.org/abs/2312.14363))

**CEPC accelerator TDR releasing news:**

[http://english.ihep.cas.cn/nw/han/y23/202312/t20231229\\_654555.html](http://english.ihep.cas.cn/nw/han/y23/202312/t20231229_654555.html)



# CEPC Engineering Design Report (EDR) Goal



## CEPC EDR Phase General Goal: 2024-2027

After completion CEPC accelerator TDR in 2023, CEPC accelerator will enter into the Engineering Design Report (EDR) phase (2024-2027), which is also the preparation phase with the aim for CEPC proposal to be presented to and selected by Chinese government around 2025 for the construction start during the "15th five year plan (2026-2030)" (for example, around 2027) and completion around 2035 (the end of the 16th five year plan).

**CEPC EDR includes accelerator and detector (TDRrd)**

**CEPC detector TDR reference design (rd) will be released by June 30, 2025**

**CEPC Accelerator EDR Phase goals, scope and the working plan (preliminary) of 35 WGs summarized in a documents of 20 pages to be reviewed by IARC in 2024**



# Some Key Issues in EDR (examples)-1

## CEPC Accelerator Main EDR Development: SRF




CEPC collider ring 650MHz 2-cell short test module has been completed in TDR phase



The collider Higgs mode for 30 MW SR power per beam will use 32 units of 11 m-long collider cryomodules will contain six 650 MHz 2-cell cavities, and therefore, a full size 650 MHz cryomodule will be developed in EDR


## CEPC Accelerator Main EDR Development: Klystrons



CEPC collider ring 650MHz klystron development in TDR phase

Parameters	Value
Frequency	5720 MHz
Output Power	80MW
Pulsed width	2.5us
Repetition rate	100Hz
Gain	54 dB
Efficiency	47%
3dB bandwidth	±5MHz
Beam voltage	420 kV
Beam current	403 A
Focusing field	0.28 T

C band 5720MHz 80MW Klystron




C band 5720MHz 80MW Klystron design progress

There are many common challenging issues for future Higgs factories, both circular and linear ones, such as MDI, control and timing, components industrial mass production and alignment/installation, etc.

Dedicated topical international workshops and collaborations are very useful and welcome

## CEPC Magnets' Automatic Production Lines in EDR

To reduce the fabrication cost of the magnets of CEPC, automatic magnet production lines will be demonstrated in EDR and used during construction



Jan.-Sept. 2024 : Complete the CEPC booster magnet automatic fabrication facility design.  
Oct. 2024-Jun. 2025: Complete the small scale demonstration facility for booster iron core fabrication.

## Massive Production Line of NEG Coating Vacuum Chambers in EDR

- The coating device A: Vacuum chambers are connected in parallel to 6 groups, each group of vacuum chambers length should be lower than 3.5m, outer diameter is about 0.47m;
- The coating device B: Antechamber are connected in parallel to 4 groups, each group of vacuum chambers length should be lower than 1.5m, due to its discharge difficulty.
- Two setups of NEG coating have been built for vacuum pipes of HEPS at IHEP Lab. And a lot of test vacuum pipes have been coated, which shows that NEG film has good adhesion and thickness distribution.
- In EDR phase a dedicated CEPC NEG coated vacuum chamber production line is planned**



# Some Key Issues in EDR (examples)-2

## CEPC MDI in EDR

**MDI Layout**

**General Parameters**

**SR Calculation**

**Radiation background**  
Radiative barrier: Beest-Gas, lowen thermal photon scattering

**Injection background**  
Circular beam, Spectral beam

**Radiation Mitigation**  
Masks, collimators, shielding

More detailed works on MDI need to be done in EDR together with detector group: Background, Be pipe, RVC, integration, alignment, mechanics,...


## CEPC Accelerator Control and Timing in EDR

### The basic structure of Timing System

- Event system and RF transmission system
- Event system: Trigger signal and Low frequency clock signal
- RF transmission system: Transmit high stability RF signal

In EDR phase CEPC high precision timing and control technology will be developed

Temperature variation induced drift compensation  
0.7ns for 10km optical fiber with 1 °C change normally



There are many common challenging issues for future Higgs factories, both circular and linear ones, such as MDI, control and timing, components industrial mass production and alignment/installation, etc.


Dedicated topical international workshops and collaborations are very useful and welcome

## CEPC Alignment and Installation Plan in EDR


### Alignment accuracy requirement

Component	$\Delta x$ (mm)	$\Delta y$ (mm)	$\Delta \theta$ (mrad)
Dipole	0.10	0.10	0.10
Arc Quadrupole	0.10	0.10	0.10
IR Quadrupole	0.10	0.10	0.10
Sextupole	0.10*	0.10*	0.10

\*Implement beam-based alignment



## CEPC Tunnel Mockup for Installation in EDR



A 60 m long tunnel mockup, including parts of arc section and part of RF section

To demonstrate the inside tunnel alignment and installation, especially for booster installation on the roof of the tunnel!





# CEPC Evolution Milestones

Year	2012	2013	2015	2017	2018	2023	2025	2027	2030	2035
------	------	------	------	------	------	------	------	------	------	------





# CEPC in Synergy with other Accelerator Projects in China

Project name	Machine type	Location	Cost (B RMB)	Completion time
<b>CEPC</b>	Higgs factory Upto ttar energy	Led by IHEP, China	<b>36.4 (where accelerator 19)</b>	2035 (starting time around 2027)
<b>BEPCII-U</b>	e+e-collider 2.8GeV/beam	IHEP (Beijing)	<b>0.15</b>	2025
<b>HEPS</b>	4 <sup>th</sup> generation light source of 6GeV	IHEP (Huanrou)	<b>5</b>	2025
<b>SAPS</b>	4th generation light source of 3.5GeV	IHEP (Dongguan)	<b>3</b>	2031 (in R&D, to be approved)
<b>HALF</b>	4th generation light source of 2.2GeV	USTC (Hefei)	<b>2.8</b>	2028
<b>SHINE</b>	Hard XFEL of 8GeV	Shanghai-Tech Univ., SARI and SIOM of CAS (Shanghai)	<b>10</b>	2027
<b>S3XFEL</b>	S3XFEL of 2.5GeV	Shenzhen IASF	<b>11.4</b>	2031
<b>DALS</b>	FEL of 1GeV	Dalian DICP	-	(in R&D, to be approved, )
<b>HIAF</b>	High Intensity heavy ion Accelerator Facility	IMP, Huizhou	<b>2.8</b>	2025
<b>CIADS</b>	Nuclear waste transmutation	IMP, Huizhou	<b>4</b>	2027
<b>CSNS-II</b>	Spallation Neutron source proton injector of 300MeV	IHEP, Dongguan	<b>2.9</b>	2029

**The total cost of the accelerator projects under construction:39B RMB more than CEPC cost of 36.4B RMB**



# BEPCL-Upgrade@IHEP

## BEPCL



□ HEP or collision

- Beam energy range
- Optimized beam energy
- Beam current
- Luminosity

Design Goals of BEPCL

- 1-2.1 GeV
- 1.89 GeV
- 910 mA
- $1 \times 10^{33} \text{cm}^{-2}\text{s}^{-1}$  @1.89 GeV

### BEPCL-U 500MHz SC cavity and cryomodule





Beam Energy: 2.35GeV

	BEPCL	BEPCL-U
Lum [ $10^{32} \text{cm}^{-2}\text{s}^{-1}$ ]	3.5	11
$\beta_y^*$ [cm]	1.5	1.3
Bunch Current [mA]	7.1	7.5
Bunch Num	56	120
SR Power [kW]	110	250
$\xi_{y,\text{Lum}}$	0.029	0.036
Emittance [nmrad]	147	152
Coupling [%]	0.53	0.35
Bucket Height	0.0069	0.011
$\sigma_{z,0}$ [cm]	1.54	1.04
$\sigma_z$ [cm]	1.69	1.3
RF Voltage	1.6 MV	3.3 MV

## BEPCL-U

- Luminosity is increased by a factor of 3 @2.35GeV
- Maximum beam energy is increased from 2.1GeV to 2.8GeV.
- **Conventional scheme: Squeeze bunch length and  $\beta_y^*$  by increasing RF voltage + Increase beam current (SR Power)**
- **Cost: 0.15B RMB**
- **Complete in 2025**



BEPCL-U final focus SC quadrupole of 25T/m





# High Energy Photon Source (HEPS) of IHEP

The first high-energy synchrotron radiation light source in China

- Groundbreaking: **Jun. 29, 2019**
- Scheduled completion in **Dec., 2025**
- Cost: **~5B RMB ~750M USD**

Area	650,658.21	m <sup>2</sup>
Circumference	1360.4	m
Beam energy	6	GeV
Emittance	≤0.06	nm•rad
Brightness	>1 × 10 <sup>22</sup>	phs/s/mm <sup>2</sup> /mrad <sup>2</sup> /0.1%BW
Beamlines	≥90	14 BLs in Phase I
Photon energy range	0.2-300	keV



booster

long beam line

linac

storage ring and experiment hall

laboratory building

guest house building

Location: Huairou Science City of Beijing, about 80km away from IHEP





# HEPS Construction Schedule

The construction period was estimated to be six and a half years.

- Date of Groundbreaking ceremony: **Jun. 29, 2019**
- Project is scheduled to be completed in **Dec., 2025**



Dec. 11, 2023, the last magnet was installed in the storage ring.  
 Aug. 8, 2022, the installation in the booster tunnel began.  
 Jun. 28, 2021, HEPS Installs First Piece of Accelerator Equipment in Linac Tunnel.



# HEPS Accelerators

By using the 7-Bending Achromatic (7BA) lattice, the horizontal emittance of the electron beam becomes better than 60pm·rad.

**2400+** Magnets


**700+** BPMs

**~2000** vacuum chambers

## Requirements of girder design

Resolution	Transverse	$\leq 5\mu\text{m}$
	Vertical	$\leq 5\mu\text{m}$
Adjusting range	Horizontal	$\pm 5\text{mm}$
	Vertical	$\pm 9\text{mm}$
Eigen frequency		$\geq 54\text{Hz}$

Weimin Pan



HEPS Booster

HEPS Linac



CEPC Accelerator EDR-J. Gao


CEPC Workshop EU Edition, April. 8, 2024,

Marseille, France





# IHEP PAPS Infrastructure in Huairou, Beijing




## Accelerator key technology R&D and Testing platform:

- SRF cavity and module
- High precision magnet
- Vacuum assembly & coating
- High efficiency Klystron
- Mechanics and alignment
- Beam test facility








# The Southern Advanced Photon Source (SAPS) of IHEP in Dongguan


Sheng Wang

- The **4<sup>th</sup>** generation (**3.5GeV**) diffraction-limited storage ring
- Brightness  $> 10^{22}$  phs/s/mm<sup>2</sup>/mrad<sup>2</sup>/0.1%BW
- SAPS will be located adjacent to CSNS
- Planned to start construction around 2025
- Cost about 3B RMB ~450M USD



**SAPS is located at IHEP, Dongguan campus, Guangdong Province, China**





# Accelerator Main Parameters


- ❑ Linac+Booster+Storage Ring
- ❑ Modified Hybrid-7BA
- ❑ 350mA high brightness mode
- ❑ 500mA high flux mode
- ❑ Swap-out / longitudinal injection
- ❑ Coherent attosecond radiation

Parameters	Value	Unit
Beam energy $E_0$	3.5	GeV
Current	500	mA
Circumference	810	m
Nature emittance	33.4	pm-rad
Cell number	32	-
Long straight section	6	m


## Test Facility Construction and R&D



RF gun research platform




499.8 MHz SC cavity




166.6 MHz SC cavity





# IHEP Dongguan SRF Infrastructure



CEPC Accelerator EDR-J. Gao




CEPC Workshop EU Edition, April. 8, 2024, Marseille, France

# Advanced Light Facility (HALF@Hefei)

Guangyao Feng

On July 12, 2022, the NDRC approved the feasibility study report of HALF project



Parameter	Design Metrics
Energy [GeV]	2.2
Beam current [mA]	350
Circumference [m]	479.86
Natural emittance [ $\text{pm}\cdot\text{rad}$ ]	85.8
Lattice Structure	6BA
Number of straight sections	20×5.3 m+20×2.2 m
Maximum brightness [ $\text{Flux}/\text{mm}^2\text{mrad}^2$ ]	$1.15\times 10^{21}$
Coherence ratio (@ 1 keV)	30%

- Project target: the 4th generation synchrotron radiation light source in the low-energy region in the world
- Ring parameters: 2.2 GeV, 480 meters, 85  $\text{pm}\cdot\text{rad}$
- Beamline stations: 10 for phase I (at least 35 beamline totally)
- Scientific target: To enable accurate measurement of electronic/chemical/spin states of inhomogeneous complex systems
- Service areas: material science, life and health, new energy, new materials, aerospace technology, integrated circuits, etc.
- Building area: 68307  $\text{m}^2$
- Construction period: 64 months (start in 2023 and complete in 2028)
- Project investment: 2.718 billion RBM (tentatively)



# Shanghai Hard X-ray FEL Facility (SHINE)

Zhentang Zhao




**SHINE is based on 1.3GHz SC accelerator technology:**

- 1.3GHz SRF cryomodules : 75
- 1.3GHz 9cell cavities: 600+16
- 3.9GHz SRF modules: 2




- SHINE groundbreaking in April, 2018, aiming at lasing in 2025.



- SHINE cost:~10B RMB or ~1.5B USD



# SHINE: A high-rep rate XFEL based on SCRF



## ➤ XFEL Facility +100 PW Laser Facility


	Nominal	Range
Beam energy/GeV	8.0	4-8.6
Bunch charge/pC	100	10-300
Max rep-rate/MHz	1	up to 1
Beam power/MW	0.8	0 - 2.4
Photon energy/keV	0.4-25	0.4-25
Pulse length/fs	20-50	5-200
Peak brightness	$5 \times 10^{32}$	$1 \times 10^{31} - 1 \times 10^{33}$
Average brightness	$5 \times 10^{25}$	$1 \times 10^{23} - 1 \times 10^{26}$
Total facility length/km	3.1	3.1
Tunnel diameter/m	5.9	5.9
2K Cryogenic power/kW	12	12
RF Power/MW	2.28	3.6

FEL Line	Nominal	Objective
<b>FEL-I</b>		
Photon energy/keV	3-15	3-15
Photon number per pulse @12.4keV	$>10^{10}$	$>10^{11}$
Max pulse repetition rate/MHz	0.66	1
<b>FEL-II</b>		
Photon energy/keV	0.4-3	0.4-3
Photon number per pulse @1.24keV	$>10^{12}$	$>10^{13}$
Max pulse repetition rate/MHz	0.66	1
<b>FEL-III</b>		
Photon energy/keV	10-25	10-25
Photon number per pulse @15keV	$>10^9$	$>10^{10}$
Max pulse repetition rate/MHz	0.66	1

# SHINE Key-Tech: SRF Accelerating Module

Zhentang Zhao

- **Prototypes & infrastructures built for R&D and production**
- **First standard 8-cavity (BCP refurbished) CM**, RF tested in June 2022, has reached its main goal ( $>128$  MV,  $>1.0E+10$ ,  $<1$  nA).
- **First standard 8-cavity (High Q) CMs**, tested in December 2022, including midT-baked and N-doped cavities ( $>128$  MV,  $>2.0E+10$ ,  $<1$  nA).
- **High-Q technologies** (N-doping& midT-baking) have been achieved on 1.3 GHz 9-cell cavities.




**CM with 8 BCP'ed cavities under testing**



CEPC Accelerator EDR-J. Gao



CEPC Workshop EU Edition, April. 8, 2024, Marseille, France













## SRF Module Test Facility (SMTF)


- 2 × Vertical Test Cryostats (VTC)
- 3 × Cryomodule Test Benches (CMTB)
- 1 × Magnet test bench
- 1 × Clean room infrastructure
- 1 × Multipurpose cryo-test Facility
- Cryomodule assembly and integration bench
- Dedicated RF test bench



# Dalian DICP DALS

## DALS Project overview

### Dalian advanced light source layout




Parameter	design
beam energy/ GeV	1
charge/ pC	100
emittance/ mm-mrad	0.5
rep. rate/ MHz	1

CM type	Frequency [GHz]	Number of Cavities	Number of CM
9-cell cavity CM	1.3	80	10
9-cell cavity CM	3.9	16	2



# Dalian DICP DALS

## Current situation of injector test facility for DALS



Parameter	design
Beam energy/ MeV	90
Charge/ pC	100
Emittance/ mm-mrad	0.5-1.5
Rep. rate/ MHz	0.1-1
RMS pulse length/ps	4
Cooling capacity@ 2 K/W	370

# HIAF& CiADS Projects in China

Hongwei Zhao

- **HIAF:** High Intensity heavy ion Accelerator Facility
- **CiADS:** China Initiative Accelerator Driven System
- Being built by IMP in Huizhou of Guangdong Prov.
- Two of 16 large-scale scientific infrastructure facilities approved by China Government during the 12<sup>th</sup> 5-year-plan 2016-2020

- **HIAF:** Nuclear physics research
- **Total budget:** 2.8 B CNY ¥ (424 M USD \$)
- **Schedule:** 2018-2025
- Construction started officially Dec. 2018

- **CiADS:** Nuclear waste transmutation
- **Total budget:** 4.0 B CNY ¥ (606 M USD \$)
- **Schedule:** 2021-2027
- Construction started officially July. 2021





# HIAF Layout and Parameters with SC Technologies

Hongwei Zhao

## External target station

Nuclear Matter  
Hyper-nuclear  
High-E irradiation




**BRing**

Fast cycle ring  
Circumference: 569 m  
Rigidity: 34 Tm

**HFRS: RIB line**  
L: 192m, Bp: 25 Tm

Circumf. 277 m  
Rigidity: 15 Tm

RIB  
Physics station



**SRing**

High precision  
spectrometer ring  
e-ion recombination  
spectroscopy


**iLinac:**  
Superconducting linac  
Length: ~110 m  
Energy: 17-22 MeV/u (U<sup>35+</sup>-45+)

Low energy nuclear structure and irradiation terminal

**SCECR**  
SECRAL II & FECR

## HIAF key parameters

	SECR	iLinac	BRing	HFRS	SRing
Energy (MeV/u)	0.014 (U <sup>35+</sup> )	17 (U <sup>35+</sup> )	835 (U <sup>35+</sup> )	800 (U <sup>92+</sup> )	800 (U <sup>92+</sup> )
Intensity	50 pμA (U <sup>35+</sup> )	28 pμA (U <sup>35+</sup> )	2×10 <sup>11</sup> ppp (U <sup>35+</sup> )	-----	10 <sup>10</sup> ppp (U <sup>92+</sup> )
Operation mode	DC	CW or pulse	fast ramping 12T/s 3Hz	Momentum -resolution 1100	DC, deceleration
Emittance or Acceptance π·mm·mrad dp/p		5 / 5	200/100 0.5%	±30/±15 ±2%	40/40 1.5%



**iLinac:**  
Superconducting linac injector





# HIAF Components Fabrication

■ Most of the components are in mass production




BRing dipole magnets



Components of HFRS superconducting magnets



iLinac HWR015 cavities



Components of SRing electron cooler


BRing collimator



# CiADS Layout and Parameters with SC Technologies

CiADS could be the world first MW-level ADS facility

- T1: Fast reactor, LBE target Hongwei Zhao  
Demonstrate high power ADS and transmutation
- T2: Target exp., liquid metal and granular target
- T3: material irradiation and full power dump
- T4: low power dump 50 kW



## CiADS key parameters

Thermal Power (Reactor + Beam)	10 MW
Proton beam Energy (MeV)	500
Beam density (mA)	5
Operation modes	CW / Pulse
Target Max. power (MW)	$\leq 2.5$
Target material	LBE
Reactor Keff	$\sim 0.75 / \sim 0.96$
Reactor thermal power	$\sim 7.5 / \sim 9.76$






# CiADS Facility in Prototyping and Engineering



650 MHz SSAMP @ 150 kW



HWR010


HWR015



HWR040




Ellip082



Ellip062

## SRF cavities






## Target Prototype





# CSNS-II@IHEP Dongguan



Beam parameters	I	II
Beam Power on target [kW]	100	500
Proton energy [GeV]	1.6	1.6
Average beam current [μA]	62.5	312.5
Pulse repetition rate [Hz]	25	25
Linac energy [MeV]	80	300
Macropulse. ave current [mA]	15	40
Linac RF frequency (MHz)	324	324/648
Linac beam width(μs)	400	600



# CSNS-II Double-Spoke Module Prototype Assembly







# Main Synergies with CEPC in Summary

- From **2018~2027** is the CEPC accelerator TDR +CEPC EDR phases before the construction
- During **2018~2027** there will be **more than 20B RMB** other accelerator projects will be completed in China (including IHEP) (**experiences related**)
- The project related experienced accelerator physicists, engineers, technicians, administration teams, etc. with wide range of expertise will have a significant increase to an unprecedented level (**human resource reservoir related**)
- The industrial sector's capability, capacity, availability, participation and contribution, etc. in accelerator related fields will have a significant increase to an unprecedented level (**industrial preparation related**)
- The accelerator R&D and industrial production facilities and platforms will have a significant increase to an unprecedented level (**R&D, test and industrial fabrication facilities related**)
- The international collaboration and participation (**including foreign industries**) will reach a new level (**International involvement related**)



# Acknowledgements

Special thanks go to Hongwei Zhao, Zhentang Zhao, Weimin Pan, Guangyao Feng, Sheng Wang, Jiyuan Zhai, and Yuan Zhang for their kind helps in providing and collecting the materials and information during preparation of this presentation

