

# CEPC Accelerator EDR Status and Perspectives

**-Towards construction through EDR Phase**

**Jie Gao**

**IHEP**

On behalf of the CEPC-SppC team

15th France China Particle Physics Laboratory workshop (FCPPN/L2024)  
June 10-14, 2024, University of Bordeaux, France




# Contents

---

- **Introduction**
- **CEPC EDR goals, plans and development towards construction**
- **CEPC accelerator EDR progress status based on TDR completion**
- **CEPC industrial preparation and international collaborations**
- **Summary**




# A Brief Historical Recall: High Energy Colliders and Factories




# Worldwide High Energy Physics Goal Timelines and Common Efforts


The common physics goals



Large colliders (LC) have the **common physics, accelerator and detector technologies:** SC accelerator technologies, positron source, damping ring, final focus, MDI, cryogenic system, sustainability, industrial promotion and participation. **Also, common outreach activities**




**Complementarity between Circular and Linear colliders**




# CEPC Higgs Factory and SppC Layout in EDR

CEPC as a Higgs Factory: **H, W, Z**, upgradable to **ttbar**, followed by a SppC (a Hadron collider)  $\sim 125\text{TeV}$   
 30MW SR power per beam (upgradable to 50MW), high energy gamma ray 100Kev $\sim$ 100MeV






CEPC collider ring (100km)




CEPC booster ring (100km)

## CEPC TDR S+C-band 30GeV linac injector



CEPC/SppC in the same tunnel





# CEPC Accelerator System Parameters in TDR and EDR

## Linac

Parameter	Symbol	Unit	Baseline
Energy	$E_e/E_{e+}$	GeV	<b>30</b>
Repetition rate	$f_{rep}$	Hz	100
Bunch number per pulse			1 or 2
Bunch charge		nC	1.5 (3)
Energy spread	$\sigma_E$		$1.5 \times 10^{-3}$
Emittance	$\varepsilon_r$	nm	6.5


## Booster

		<i>tt</i>		<i>H</i>		<i>W</i>	<i>Z</i>	
		Off axis injection	Off axis injection	On axis injection	Off axis injection	Off axis injection		
Circumfer.	km	<b>100</b>						
Injection energy	GeV	<b>30</b>						
Extraction energy	GeV	<b>180</b>	<b>120</b>		<b>80</b>	<b>45.5</b>		
Bunch number		35	268	261+7	1297	3978	5967	
Maximum bunch charge	nC	0.99	0.7	20.3	0.73	0.8	0.81	
Beam current	mA	0.11	0.94	0.98	2.85	9.5	14.4	
SR power	MW	0.93	0.94	1.66	0.94	0.323	0.49	
Emittance	nm	2.83	1.26		0.56	0.19		
RF frequency	GHz	1.3						
RF voltage	GV	9.7	2.17		0.87	0.46		
Full injection from empty	h	0.1	0.14	0.16	0.27	1.8	0.8	

## Collider

	Higgs	<i>Z</i>	<i>W</i>	<i>t</i> $\bar{t}$
Number of IPs	2			
Circumference (km)	<b>100.0</b>			
SR power per beam (MW)	<b>30</b>			
Energy (GeV)	<b>120</b>	<b>45.5</b>	<b>80</b>	<b>180</b>
Bunch number	268	11934	1297	35
Emittance $\varepsilon_x/\varepsilon_y$ (nm/pm)	0.64/1.3	0.27/1.4	0.87/1.7	1.4/4.7
Beam size at IP $\sigma_x/\sigma_y$ (um/nm)	14/36	6/35	13/42	39/113
Bunch length (natural/total) (mm)	2.3/4.1	2.5/8.7	2.5/4.9	2.2/2.9
Beam-beam parameters $\xi_x/\xi_y$	0.015/0.11	0.004/0.127	0.012/0.113	0.071/0.1
RF frequency (MHz)	650			
Luminosity per IP ( $10^{34} \text{ cm}^{-2} \text{ s}^{-1}$ )	<b>5.0</b>	<b>115</b>	<b>16</b>	<b>0.5</b>

## Transport lines



CEPC Technical Design Report (TDR) includes:  
 1) CEPC Accelerator TDR  
 2) CEPC Detector TDRrd (rd=reference design)  
 will be released by June 2025



# CEPC Operation Plan and Goals in EDR

Particle	$E_{c.m.}$ (GeV)	Years	SR Power (MW)	Lumi. per IP ( $10^{34}cm^{-2}s^{-1}$ )	Integrated Lumi. per year ( $ab^{-1}$ , 2 IPs)	Total Integrated L ( $ab^{-1}$ , 2 IPs)	Total no. of events
$H^*$	240	10	50	8.3	2.2	21.6	$4.3 \times 10^6$
			30	5	1.3	13	$2.6 \times 10^6$
Z	91	2	50	192**	50	100	$4.1 \times 10^{12}$
			30	115**	30	60	$2.5 \times 10^{12}$
W	160	1	50	26.7	6.9	6.9	$2.1 \times 10^8$
			30	16	4.2	4.2	$1.3 \times 10^8$
$t\bar{t}$	360	5	50	0.8	0.2	1.0	$0.6 \times 10^6$
			30	0.5	0.13	0.65	$0.4 \times 10^6$

\* Higgs is the top priority. The CEPC will commence its operation with a focus on Higgs.

\*\* Detector solenoid field is 2 Tesla during Z operation, 3Tesla for all other energies.

\*\*\* Calculated using 3,600 hours per year for data collection.

# CEPC Key Technology R&D Status in TDR


Specification Met



Prototype Manufactured



Accelerator	Fraction
✓ Magnets	27.3%
✓ Vacuum	18.3%
✓ RF power source	9.1%
✓ Mechanics	7.6%
✓ Magnet power supplies	7.0%
✓ SC RF	7.1%
✓ Cryogenics	6.5%
✓ Linac and sources	5.5%
✓ Instrumentation	5.3%
✓ Control	2.4%
✓ Survey and alignment	2.4%
✓ Radiation protection	1.0%
✓ SC magnets	0.4%
✓ Damping ring	0.2%



Key technology R&D in TDR spans all component lists in CEPC CDR





# Power Consumption of CEPC @ Higgs

SN	System	Higgs 30MW							Higgs 50MW						
		Collider	Booster	Linac	BTL	IR	Surface building	Total	Collider	Booster	Linac	BTL	IR	Surface building	Total
1	RF Power Source	96.90	1.40	11.10				109.40	161.60	1.73	14.10				177.40
2	Cryogenic system	9.72	1.71			0.14		11.57	9.17	1.77			0.14		11.08
3	Vacuum System	5.40	4.20	0.60				10.20	5.40	4.20	0.60				10.20
4	Magnet Power Supplies	44.50	9.80	2.50	1.10	0.30		58.20	44.50	9.80	2.50	1.10	0.30		58.20
5	Instrumentation	1.30	0.70	0.20				2.20	1.30	0.70	0.20				2.20
6	Radiation Protection	0.30		0.10				0.40	0.30		0.10				0.40
7	Control System	1.00	0.60	0.20				1.80	1.00	0.60	0.20				1.00
8	Experimental devices					4.00		4.00					4.00		4.00
9	Utilities	37.80	3.20	1.80	0.60	1.20		44.60	46.40	3.80	2.50	0.60	1.20		54.50
10	General services	7.20		0.30	0.20	0.20	12.00	19.90	7.20		0.30	0.20	0.20	12.00	19.90
	<b>Total</b>	204.12	21.61	16.80	1.90	5.84	12.00	<b>262.27</b>	276.87	22.60	20.50	1.90	5.84	12.00	<b>339.71</b>

**Various measures will be studied and implemented towards a green collider, as discussed in the Mini workshop of accelerator, Jan. 18-19, 2024, HKUST-IAS, Hong Kong**  
<https://indico.cern.ch/event/1335278/timetable/?view=standard>


# CEPC Accelerator International TDR Review and Cost Review June 12-16, and Sept. 11-15, 2023, in HKUST-IAS, Hong Kong



CEPC Accelerator TDR Review  
June 12-16, 2023, Hong Kong



CEPC Accelerator TDR Cost Review  
Sept. 11-15, 2023, Hong Kong



Domestic Civil Engineering  
Cost Review, June 26, 2023, IHEP




9<sup>th</sup> CEPC IAC 2023 Meeting  
Oct. 30-31, 2023, IHEP



Table 12.1.2: CEPC project cost breakdown, (Unit: 100,000,000 yuan)

Total	364	100%
Project management	3	0.8%
Accelerator	190	52%
Conventional facilities	101	28%
Gamma-ray beam lines	3	0.8%
Experiments	40	11%
Contingency (8%)	27	7.4%




Distribution of CEPC Project total TDR  
cost of **36.4B RMB**

**CEPC accelerator TDR has been completed and formally released on December 25, 2023:**  
[http://english.ihep.cas.cn/nw/han/y23/202312/t20231229\\_654555.html](http://english.ihep.cas.cn/nw/han/y23/202312/t20231229_654555.html)  
**CEPC accelerator TDR has been published formally in Journal Radiation Detection Technology and Methods (RDTM) on June 3, 2024:**  
 DOI: 10.1007/s41605-024-00463-y  
<https://doi.org/10.1007/s41605-024-00463-y>



# CEPC Engineering Design Report (EDR) Goal



## CEPC EDR Phase General Goal: 2024-2027

After completion CEPC accelerator TDR in 2023, CEPC accelerator will enter into the Engineering Design Report (EDR) phase (2024-2027), which is also the preparation phase with the aim for CEPC proposal to be presented to and selected by Chinese government around 2025 for the construction start during the "15th five year plan (2026-2030)" (for example, around 2027) and completion around 2035 (the end of the 16th five year plan).

**CEPC EDR includes accelerator and detector (TDRrd)**

**CEPC detector TDR reference design (rd) will be released by June 30, 2025**

**CEPC Accelerator EDR Phase goals, scope and the working plan (preliminary) of 35 WGs summarized in a documents of 20 pages to be reviewed by IARC in 2024**



# CEPC EDR Goal, Plan and Scope

## CEPC Accelerator EDR Phase Working Plan (preliminary) 2024 - 2027 (Oct. 16, 2024 draft)

### CEPC EDR general goals:

According to the general CEPC plan, CEPC Conceptual Design Report (CDR) was completed in Nov. 2018, after the completion of CEPC accelerator TOR in 2023. CEPC accelerator will enter into the Engineering Design Report (EDR) phase (2024-2027), which is also the preparation phase with the aim for CEPC to be presented to and selected by Chinese government for the construction start during the "15th five year plan" (under way).  
 - Work closely with CAS and MOST and to prepare CEPC to be put in the "15th five year plan" (under way).  
 - Work closely with local governments towards a construction site (under way).  
 - Work closely with local government, CAS and MOST on EDR-related funds (under way).

### CEPC Accelerator EDR Plan and Scope:

According to the general CEPC plan, CEPC Conceptual Design Report (CDR) was completed in Nov. 2018, and the CEPC accelerator Technical Design Report (TDR) will be formally released in 2028 after international review(s) (including a CEPC accelerator cost review). Thereafter, CEPC accelerator will enter into the Engineering Design Report (EDR) phase (2024-2027), which is also the preparation phase with the aim for CEPC to be presented to and selected by Chinese government for the construction start during the "15th five year plan" (under way).  
 - Work closely with local government for the project cost, with regard to the around 2027) and completion around 2035 (the end of the 15th five year plan).  
 - Breakdown of CEPC Accelerator EDR working plan and goals (2024-2027).  
 - According to the CEPC and CEPC Accelerator EDR general goals described in the working plan and goals, each year to do list (Tern) and deliverables are as follows:

- (A) Based on the CEPC TDR accelerator design, demonstrate a design which will guarantee the construction, commissioning, operation and 2 pole, with little or no upgrade possibility, and complete the CEPC TDR accelerator key technology R&D achievement, and complete the CEPC TDR accelerator key technology R&D achievement.
- (B) Complete a practical procurement strategy and negotiate with both domestic and international suppliers, and in collaboration with local government, CAS and MOST (central government), CEPC also converge from several candidates to a EDR construction site satisfying the required geological conditions, electric power and water resources, social and environment conditions, domestic and international transportation relevant conditions, international science city and sustainable development, etc.
- (C) Complete detailed construction site geological studies and corresponding site dependent cost engineering design and general utility facility design.
- (D) Complete the radiation, security, environment assessment studies and necessary documents (including EDR report) ready for the application to the central government to get the formal approval of construction.

**Accelerator EDR Phase Working Plan (preliminary) of 35 WGs is a documents of 20 pages. The Accelerator EDR plan and progress will be reviewed by IARC from Sept. 18-20, 2024 at IHEP.**



# CEPC IARC Members in EDR Phase

	Name	Institution	Country/Region	Email
1	A. Sidorin	JINR	Russia	sidorin@jinr.ru
2	Makoto Tobiyama	KEK	Japan	makoto.tobiyama@kek.jp
3	Marica Biagini	(chair)	INFN	Italy marica.biagini@Inf.infn.it
4	Phillip bambade	LAL	France	bambade@lal.in2p3.fr
5	Eugene Levichev	(IAC)	BINP	Russia e.b.levichev@inp.nsk.su
6	Steinar Stapnes	(IAC)	CERN	Norway steinar.stapnes@cern.ch
7	Katsunobu Oide	(IAC)	KEK	Japan oide1@icloud.com
8	Brian Foster	(IAC)	Oxford	U.K brian.foster@physics.ox.ac.uk
9	In-Soo Ko	POSTTECH	Korea	isko@postech.ac.kr
10	Zhentang Zhao	SINAP	China	zhaozhentang@sinap.ac.cn
11	Carlo Pagani	INFIN-Milano	Italy	carlo.pagani@mi.infn.it
12	Norihito Ohuchi	KEK	Japan	norihito.ohuchi@kek.jp
13	Paolo Pierini	ESS, Linac and Klystrons and SRF		Paolo.Pierini@esss.se
14	Michael Koratzinos	CERN, IR quadrupole design		michael.koratzinos@cern.ch
15	Roberto Kersevan	CERN, vacuum		roberto.kersevan@cern.ch
16	Akira Yamamoto	KEK, cryogenics		akira.yamamoto@kek.jp
17	K. Furukawa	KEK, injection		kazuro.furukawa@kek.jp
18	Gero Kube	DESY, instrumentation and diagnostic		Gero.Kube@desy.de
19	Hiroyuki Nakayama	KEK, backgrounds and MDI		hiroyuki.nakayama@kek.jp
20	Xiaoye He	USTC, alignment		xyhe@ustc.edu.cn

IARC will review CEPC accelerator EDR progress and report to IAC

The first IARC EDR review meeting will take place in Sept. 18-20, 2024, IHEP



# CEPC Magnet Automatic Production Line in EDR

~15000 dipole magnets in the CEPC booster

Plan: Middle of 2024 design completed, Middle of 2025 completed

**Stacking of 1/3 length core**


**Production of full length cores**

**Assembly of the magnet**



**Field measurement of the magnet**

The image displays a 3D architectural rendering of an automated magnet production line. At the top, three small inset images show a cross-section of a magnet, a perspective view of a long core, and a close-up of a magnet assembly. A red text box indicates the project schedule: 'Plan: Middle of 2024 design completed, Middle of 2025 completed'. A blue text box at the top right states '~15000 dipole magnets in the CEPC booster'. The main rendering shows a long, narrow factory floor with four distinct workstations. Each workstation is supported by a blue frame and contains various mechanical components and robotic arms. Below the main rendering, four blue boxes with white text label the stations: 'Stacking of 1/3 length core', 'Production of full length cores', 'Assembly of the magnet', and 'Field measurement of the magnet'. At the bottom, four smaller 3D images provide detailed views of each of these stations, showing the complex machinery and robotic systems involved in the production process.


# CEPC NEG Coated Vacuum chamber Automatic Production Line in EDR




Layout of production line



Production line of NEG coating, spraying



AGV(Automatic Guided Vehicle) transport



7-axis robot for assembling

**Plan: Middle of 2024 design completed, Middle of 2025 to be completed**

# CEPC 650MHz High Efficiency High Power Klystron Development and RF Power Distribution System


## CEPC klystron R&D



Klystron No. 1  
Efficiency 65%  
(2020)



Klystron No. 2  
Efficiency 77%  
(2021)





Klystron No. 3 (MBI)  
Efficiency 80.5%  
(under fabrication)

## Power Supply Modulator




**Pulsed RF Mode (30% duty factor, 60ms/5Hz) 77.2% @ 849kW pulsed in 2024**



### High Voltage vs. Power & Efficiency



To be tested in 2024



## RF distribution plan





- Three prototypes of the **650MHz 800KW CW** klystrons are developed. The efficiency reaches 77.2%
- PSM is developed with the industrial collaboration
- RF tunnel distribution was planned




# CEPC 80MW C-band Klystron Development in EDR

Plan: Middle of 2024 design completed, March of 2025 high power test




Gun and collector beam optics

Parameters	Value
Frequency	5712 MHz
Output Power	80MW
Drive power	350W
Gain	54 dB
Efficiency	47%
3dB bandwidth	±10MHz
Beam voltage	420 kV
Beam current	403 A
Focusing field	~0.27 T maximum




Beam dynamic with CST code




Mechanical configuration

# CEPC Accelerator Development in EDR

## CEPC 650MHz SC Full Size Cryomodule Development in EDR



CEPC collider ring 650MHz 2\*cell short test module has been completed in TDR phase



The collider Higgs mode for 30 MW SR power per beam will use 32 units of 11 m-long collider cryomodules will contain six 650 MHz 2-cell cavities, and therefore, a full size 650 MHz cryomodule will be developed in EDR


**Plan: Middle of 2024 design completed, End of 2025 to be completed**

## CEPC MDI in EDR

**More detailed works on MDI need to be done in EDR together with detector group: Background, Be pipe, RVC, integration, alignment, mechanics,...**

**Radiation Mitigation**  
Masks, collimators, shielding

## CEPC Mockup Tunnel in EDR



A 60 m long tunnel mockup, including parts of arc section and part of RF section

To demonstrate the inside tunnel alignment and installation, especially for booster installation on the roof of the tunnel

**Plan: Middle of 2025 to be completed**

## CEPC Alignment and Installation Plan in EDR

**Geoid refinement**

**Visual instrument**

**Component Pre-alignment**

**GPS receiver**

**Surface Control network (14Points)**

**Backbone Control network (short line:300m; long line 600m)**

**Tunnel Control network (interval of 6 meters)**

**Alignment accuracy requirement**

Component	$\Delta x$ (mm)	$\Delta y$ (mm)	$\Delta z$ (mm)
Dipole	0.10	0.10	0.10
Acc Quadrupole	0.10	0.10	0.10
RF Quadrupole	0.10	0.10	0.10
Solenoid	0.10*	0.10*	0.10

\*Implement beam-based alignment


# CEPC Accelerator Alternative Options

## CEPC Plasma Injector (alternative option) and TF Plan

CEPC plasma injector scheme:

From 10 GeV → 30 GeV →  $TR \geq 2$

Simulation results show that it works on paper with reasonable error tolerances for both electron and positron beams injected to the booster



CEPC IARC, 2022.06



- Phase I (Year0-Year2)**
1. Re-design and install transport beamline system, optimize the e<sup>-</sup> / e<sup>+</sup> beam quality
  2. Clean room and high power (100 TW) installation
  3. Beam instrumentation
  4. RF Gun platform
  5. Commissioning and start-up of systems
- Phase II (Year3-Year4)**
1. Upgrade the linac to 100 TW (1PW + 20/40 TW) and install it on the site
  2. Upgrade the damping ring the bunch compression and improve the e<sup>+</sup> quality
  3. Upgrade the FEL studies



**Positron and electron acceleration**  
**Cascading acceleration**  
**Future linear collider technologies**  
**High energy beam for detector R&D**  
**(possible application)**

PWFA/LWFA TF based on BEPC-II Linac and HPL has been founded by CAS 90M RMB in Sept. 2023



**Plasma accelerator technology** development towards CEPC injector and **future e<sup>+</sup>e<sup>-</sup> linear colliders**

## CEPC Polarization Studies (alternative option)



Both the transverse and longitudinal polarization and Z, W, are feasible (Higgs under study)

- Implement the lattice design to accommodate polarized beams: spin rotator, wiggler, Compton polarimeters, dumping ring and booster design, etc.
- R&D of Compton polarimeter, polarized electron sources, spin rotator, etc.
- Simulate the process and effects of errors
- Carry out experiments at BEPCII & HEPS booster








**Polarization beam technology** development towards **precision physics experiments**


# CEPC Conventional Facility and Civil Engineering

Cables installed!

Electrical Equipment General Layout in Auxiliary Tunnel/500m along 100km




# CEPC Evolution Milestones and Timeline





# CEPC Planning, Schedule and Teams

TDR (2023), EDR(2027), start of construction (2027-8)



## CEPC team (domestic)

CEPC accelerator and detector/experiments/theory group is an highly experienced team with strong international collaboration experiences. It has demonstrated its expertise and achievements in the following related projects, both domestic and international ones, such as: BEPC-BEPCII (BES-BESIII), BFELP, CSNS, ADS, HEPS, LEP, LHC, LHCb, ILC, EXFEL, HL-LHC, BELLE, BELLE-II, CLEO, Daya Bay, JUNO, etc.

## CEPC international partners and collaborators



# CEPC in Synergy with other Accelerator Projects in China


Project name	Machine type	Location	Cost (B RMB)	Completion time
<b>CEPC</b>	Higgs factory Upto ttar energy	Led by IHEP, China	<b>36.4 (where accelerator 19)</b>	Around 2035 (starting time around 2027)
<b>BEPCII-U</b>	e+e-collider 2.8GeV/beam	IHEP (Beijing)	<b>0.15</b>	2025
<b>HEPS</b>	4 <sup>th</sup> generation light source of 6GeV	IHEP (Huanrou)	<b>5</b>	2025
<b>SAPS</b>	4th generation light source of 3.5GeV	IHEP (Dongguan)	<b>3</b>	2031 (in R&D, to be approved)
<b>HALF</b>	4th generation light source of 2.2GeV	USTC (Hefei)	<b>2.8</b>	2028
<b>SHINE</b>	Hard XFEL of 8GeV	Shanghai-Tech Univ., SARI and SIOM of CAS (Shanghai)	<b>10</b>	2027
<b>S3XFEL</b>	S3XFEL of 2.5GeV	Shenzhen IASF	<b>11.4</b>	2031
<b>DALS</b>	FEL of 1GeV	Dalian DICP	-	(in R&D, to be approved, )
<b>HIAF</b>	High Intensity heavy ion Accelerator Facility	IMP, Huizhou	<b>2.8</b>	2025
<b>CIADS</b>	Nuclear waste transmutation	IMP, Huizhou	<b>4</b>	2027
<b>CSNS-II</b>	Spallation Neutron source proton injector of 300MeV	IHEP, Dongguan	<b>2.9</b>	2029

**The total cost of the accelerator projects under construction:39B RMB more than CEPC cost of 36.4B RMB**



# CEPC Project Development towards Construction

- **TDR has been completed** (review + revision) to be **formally released on Dec. 25, 2023**.
- **CAS is planning for the 15<sup>th</sup> 5-years plan for large science projects**, and a steering committee has been established, **chaired by the president of CAS**.
- **High energy physics and nuclear physics**, is one of the 8 groups (fields).
- **CEPC is ranked No. 1**, with the **smallest uncertainties, by every evaluation committee both domestic and international one** among all the collected proposals.
- **A final report has been submitted to CAS for consideration.**
- **The above mentioned actual process is within CAS and the following national selection process will be decisive.**







# Participating and Potential Collaborating Companies in China and Worldwide

	System
1	Magnet
2	Power supplier
3	Vacuum
4	Mechanics
5	RF Power
6	SRF/ RF
7	Cryogenics
8	Instrumentation
9	Control
10	Survey and alignment
11	Radiation protection
12	e-e+Sources

## CEPC Industrial Promotion Consortium (CIPC, established in Nov. 2017)



## Potential international collaborating suppliers and partners worldwide





# CEPC International Collaboration-1

## CEPC attracts significant International participation and collaborations

**Accelerator TDR report:** 1114 authors from 278 institutes ( including 159 International Institutes, 38 countries ) [arXiv: 2312.14363](https://arxiv.org/abs/2312.14363)



- More than 20 MoUs have been signed with international institutions and universities
- CEPC International Workshop since 2014
- EU-US versions of CEPC WS since 2018
- Annual working month at HKUST-IAS (mini workshops and HEP conference) since 2015



CEPC workshop in Chicago, 2019





# CEPC International Collaboration-2

**HKIAS23 HEP Conference**  
Feb. 14-16, 2023

<https://indico.cern.ch/event/1215937/>



The 2024 HKUST IAS Mini workshop and conference were held from Jan. 18-19, and Jan. 22-25, 2024, respectively.

<https://indico.cern.ch/event/1335278/timetable/?view=standard>

The 2023 International Workshop on Circular Electron Positron Collider, EU Edition, University of Edinburgh, July 3-6, 2023

<https://indico.ph.ed.ac.uk/event/259/overview>



The 2024 international workshop on the high energy Circular Electron Positron Collider (CEPC) will be held from **Oct. 23-27, 2024, Hangzhou, China**

<https://indico.ihep.ac.cn/event/22089/>

The 2023 international workshop on the high energy Circular Electron Positron Collider (CEPC)

<https://indico.ihep.ac.cn/event/19316/>



The 2024 international workshop of CEPC, EU-Edition were held in Marseille, France, **April 8-11, 2024.**

<https://indico.in2p3.fr/event/20053/overview>



Professor Peter Higgs passed away on **April 8, 2024**. We miss him.



# Summary

---

- CEPC addressed most pressing & critical science problems in particle physics
- Accelerator design and technology R&D are reaching maturity, TDR completed in 2023, ready for construction in 3-5 years after EDR phase
- CEPC proposal for the China's 15<sup>th</sup> 5-year plan will be submitted in 2025
- CEPC has a strong and experienced group, backed by IHEP and international teams
- Schedule will follow China's 15<sup>th</sup> 5-year plan, Call for collaboration and proposals once CEPC is (preliminary) approved
- Continue to work with government and funding agencies to get support
- **International collaborations are mostly welcome.**



**Thanks for your attention**