

Preparation of BT DESY-2020-03

Vincent, Jérôme, Frédéric, Fabrício, ...

Institut Polytechnique de Paris

LM



Set-up & Goals

Technical:

- Validation of CompactDAQ on ≥ 4 layers (max)
- Validation of FEV12-COB with full wafers
 - Calibration with mips, response to showers
- Preparation of running with maximum number of layers
 - Full calorimeter:
 - 8–9 FEV11–320 μm
 - 5 FEV13 ($1 \times 320\mu\text{m} + 4 \times 650\mu\text{m}$)
 - 2 FEV12–COB–500 μm
 - 2 FEV12–500 μm
 - 16 – 18 layers $\rightarrow$ 2 stacks.

Physics:

1. Calibration to mips :

- 1) Stability of old layers, Calib of new layers.
- 2) Comparison of S/N $\neq$ Si thickness + angles (30° ?)
 - 1) Estimation of effective thickness
 - 2) Estimation of thresholds

- Movable stage
-

2. Optimisation of S/N:

- 1) HV curve on mips:
 - 1) noise and mip curves:
At the center to hit 4 wafers; beam as large as possible

3. Response to EM Showers

- 1) Comparison of profiles $\rightarrow$ response to higher energy density (core of showers)
 - 1) Complete shower profile (calo)
 - 2) Put W for max of showers ($\sim 5 X_0$) + nothing:
 $\rightarrow$ shower core in most layers (ign. dispersion)

W configurations

GeV	Max_gerbe EM/X0
1.0	3.9
3.0	5.0
6.0	5.7

Positionnement «idéaux» à 3 GeV (max intensité)

Wanted Position/max	0,5	1	1,5	2	3
X0 @ 3GeV	2,5	5	7,5	10	15
	2,5	2,5	2,5	2,5	5
mm of W	8,75	8,75	8,75	8,75	17,5
Épaisseur de 2,1	4,0	4,0	4,0	4,0	8,0
Matériaux (1=2,1)	1+2+1	1+2+1	1+2+1	1+2+1	2,5 cm Pb
Effective X0	2,4	2,4	2,4	2,4	4,6
int du début	2,4	4,8	7,2	9,6	14,2

Plaques W dispo:

- 10 plaques de 2.1 ($0.6X_0$) $\rightarrow 6X_0$
- 4 plaques de 4.2 ($1.2X_0$) $\rightarrow 4.6X_0$
- Briques de Pb (2.5cm / 0.56cm = $4.6X_0$)
- Plaques de Pb 1cm ($1.8X_0$)

Technical

Refurbishing of 1st stack

- Additional layers + security.
 - Holders & spacers for FEV13's + FEV11's

Re-test of FEV11's before modifications

- Redo passports
- Update of DIF's FW
- Upgrade of PYRAME (incl. DIF ID)
 - Adapt to CompactDAQ

Open questions:

- How many PS HV ?
- How many PS BT ?
- Grounding scheme
- Mechanical holding ?

2 DAQ à synchroniser

- Fequence ? 50 MHz, 5 MHz, ILC SK2 = 40MHz, 5 MHz
- Spill Number → Re-config à chaque début de run
- Timeout ? StartAcq ?
- Busy ?

SW sync.

- EUDAQ2 ? Pyrame ?
- CCC/TLU ? même polarité

SW = config active!

- en %
- FW : 50 ou 40 MHz ?

Organisation

LLR:

- Technical coordin: Jérôme
- On site:
 - Jérôme (all week) + Fred (2 days ?) + Thibault (2 days) + Rémi Guillaumat (2 days)
 - Fabricio (all week) + Jonas (all week) + VB ($\leq$ Thursday)