

SPIRAL 2 status and available beams

- 1 – SPIRAL 2 Commissioning
- 2 – What the LINAC can do (and how)
- 3 – Available beams



G. Normand GANIL

on behalf of the GANIL teams and SPIRAL2 collaborations


Special thanks to: Marco Di Giacomo, Jean-Michel Lagniel , Angie Karina Orduz and Didier Uriot

SP2 commissioning

Spiral 2 scheme



Commissioning timeline



Authorization to operate SPIRAL2, Jul 8th, 2019

Qualification of the ion sources and LEBT (LPSC-Grenoble and CEA-Saclay)

Construction building and tools

Qualification of the injector on a Diagnostic Plate (GANIL)

- RFQ performance
- 2014 1st H⁺ beam @ 2 mA H/D (Dec)
- 2015 1st Ar⁹⁺ beam @ 230 μ A HI source (Jul) / 1st RFQ H⁺ (Dec)
- Beam characteristics at RFQ exit

SC linac beam commissioning up to the main beam dump

- 1st beam in the linac, Oct. 28th
- 1st beam in NFS, Dec. 11th
- 33 MeV H⁺ (2019)
- 40 MeV ⁴He²⁺, D⁺ (2020)
- 50 μ A D⁺ NFS (2021)

First year of SPIRAL2 operation in NFS room

- 50% beam time for physics
- Pre-commissioning for S³
- 7 MeV/A ¹⁸O⁶⁺, ¹⁸O⁷⁺, ⁴⁰Ar¹⁴⁺
- 0.73 MeV/A ¹⁸O⁶⁺, ¹⁸O⁷⁺, ⁴⁰Ar¹⁴⁺
- First cavity failure test


SPIRAL2 operation

- 65% beam time for physics
- 14% for studies
- Pre-commissioning for S³
- 14.5 MeV/A ¹⁸O⁶⁺
- Cavity failure test and pressure variation in warm sections

2009-2012



2014-2018




2019-2021





2022



2023






Tuning strategy and losses



Neutrons backscattered from main beam dump

- Losses $< 1\text{ W/m}$ for 165 kW protons and 200 kW deuterons
- For heavy ions at energy $< 7\text{ MeV/A}$ current transmission and vacuum evolution are more relevant than neutrons : we used them for fine tuning.

Single bunch selector (MEBT), scattering issue





SBS meander to slow down the E wave

1 bunch selected ($\sim \text{ns}$) on 100 (until 10000), for time of flight purpose

SBS beam dump


- The **beam dump** receiving the bunches deviated by the SBS (until 7.5 kW) was affected by **Coulomb scattering** which has created important heating and beam current measurements issues ($\approx 100 \mu\text{A}$ in 2019).
- The **beam dump was redesigned** (surface changed from flat to staircase), which has **successfully decreased the temperature and the current offset**.



Simulation code Tracewin (IRFU-CEA)


- This code predicts very well the beam behavior after the RFQ if the starting beam distribution is accurate (emittancemeter in MEBT + backtracing).
- Starting from calculated parameters in the machine, very few matching changes, with 4 quadrupoles and one rebuncher, are needed to obtain a well matched beam to the linac with very low losses.

Reference simulation 600 μA $^{18}\text{O}^{6+}$



Transversal emittances in the MEBT


Measurement 600 μA $^{18}\text{O}^{6+}$



Energy along the LINAC
(Measurement vs Simulation)

What the LINAC can do (and how)


Maximum/minimum energies




Minimum energy : 0.73 MeV/A (id output energy of the RFQ)

Cavities voltage vs species and acceleration scheme

Each cavity must be tuned one after the other :
Voltage and Phase




All species



Electrical field used in each cavity for different species and energies ($k = \text{normalized}/\text{max}$, $\text{max} = 6.5 \text{ MV}$)

Low electric fields to keep a good acceptance


Deuteron 20 MeV/A



Low synchronous phases to keep a good acceptance


Cavities tuning : time needed

1. **Advanced method** (1-2 days) - No voltage and phase calibrations known
 - Signature matching + **avoid the phase measurements errors** (non-linear effects deforming the bunch shape)
 - **1 tuning per year**: phase and voltage calibration for all tunings.
2. **With reference method** (<60 min) - Voltage and phase calibration previously done
 - **No detuning, no phase scan.**
 - Phase measurement at cavity entrance + simulation.
 - Verification with phase measurement at the PU1.
 - Sensitive to accuracy of phase measurements.
3. **Ratio A/Q** (<10 min + LBE new tuning)
 - If the BPMs (phasemeters) do not see the beam, a **"pilot ion"** with a "visible" current and the same acceleration pattern as the one required for the **"objective ion"** is used for an initial tuning.
 - All the \vec{E} and \vec{B} fields will be multiplied by $c = \frac{A_1/Q_1}{A_2/Q_2}$
 - New tuning of the LEBT for the new ion



Heavy ions

$^{18}\text{O}^{6+}$




$$\Delta E/E = 0.1 \text{ MeV rms} / 126 \text{ MeV} = 0.08 \%$$

Accelerated with success in 2022

« Invisible » beams.

Objective : tune the accelerator even for species with very low intensities not seen by some diagnostics ($< 10 \mu\text{A}$).



From $^{18}\text{O}^{6+}$ to $7+$ (test case):

$$(A1/Q1) / (A2/Q2) = 0,86$$


Method : multiply all magnetic and electric fields from source voltage until the last quadrupole before the target by this factor.

Simulation of $^{18}\text{O}^{7+}$ in MEBT, linac and HEBT using the scaling method

Used with success in 2022

Linac tuning without acceleration for $^{18}\text{O}^{6+}$

Beam requested to tune the spectrometer (0.73 MeV/A).



All A cavities and 1 over 2 of the B ones are in rebuncher mode.


... we succed to not accelerate this beam in 2022



Linac tuning if a cavity is out of order

As the **energy** \uparrow the **debunching** \downarrow


- High β cavity failure: solution easy to find.
- Last low β cavity failure, possible to recover a beam dynamics without losses but not obvious.
- Low β cavity failure: **very difficult to tune** at low energy due to a **high debunching** between two cavities.



Deutons
CMB1 cav 2 out of order



Work is currently underway :




Low β section

High β section

Retune the up and downstream cavities

- Phase acceptance reduction (more losses, but if 2 kW are requested instead of 200 kW, some margins)
- Reduction of the final energy or/and an increase of the cavity voltages (8 MV/m available now vs 6.5 MV/m at the beginning).

Longitudinal acceptance (in white)



Cavity A6 out of order :

900 μA $^4\text{He}^{2+}$ @ 64 MeV (instead of 80)

2 kW produced with success in 2023

Available beams

Heavy ions

INTENSITIES

	Q/A = 1/3 AVAILABLE NOW	Q/A = 1/6 (NEWGAIN) 2028	Q/A = 1/7 (NEWGAIN) >2030
Energies	0.73 to 14.5 MeV/A	0.73 MeV/A to 8.5 MeV/A	0.73 to 6.33 MeV/A, or maybe 7 MeV/A
Maximum power	(if 1 mA) 43.5 kW	<6 kW	(Uranium) 15 kW

beam intensities	injector1 2023	NEWGAIN (injector2) 2028 ≥ 2030	
	Intensity (pμA) Phoenix V3 RFQ A/Q≤3	Intensity (pμA) Phoenix V3 RFQ A/Q≤7	Intensity (pμA) SC Ion Source RFQ A/Q≤7
¹⁸ O	80	*	375
¹⁹ F	>15	>40	>40
³⁶ Ar	16	70	45
⁴⁰ Ar	3.6	70	45
³⁶ S	2.3	*	*
⁴⁰ Ca	2.9	10	20
⁴⁸ Ca	1.2	10	20
⁵⁸ Ni	1.1	4	8
⁸⁴ Kr	0.1	10	20
¹³⁹ Xe	0.001	7	>10
²³⁸ U	<<0.001	0.1	6

Measured Estimated * -> no estimation

Thanks to the ion source GANIL and the NEWGAIN teams

Light ions (p, deuterons, ^4He)


	I peak	Power already done	With SBS 1/100 (NFS)	Maximum power	Min/Max energy
Deutons	5 mA	10 kW	2 kW	200 kW	0.73 to 20 MeV/A
Proton	5 mA	16 kW	2 kW	165 kW	0.73 to 33 MeV/A
^4He	1 mA	10 kW		40 kW	0.73 to 20 MeV/A

Time structure	Min	Max
Duration of macro-pulse LBET Chopper	100 μs^*	1 s
Frequency LBET Chopper	1 Hz	100 Hz - 1 kHz (Future)
Selection rate MEBT Single bunch selector	1/10000	1/100

*10 μs available but beam not stable due to space charge compensation time


NEWGAIN

MEBT + LINAC



$^{48}\text{Ca}^{11+}$ $^{238}\text{U}^{34+}$

MEBT + LINAC



The construction phase has just started

(NEWGAIN beam dynamic team's simulations)

Thank you for your attention, see you in Spiral2