<u>cea</u> irfu

SEASON update

Tests and mounting

Mathilde Ragot

Supervisors : Damien Thisse Marine Vandebrouck Iain Moore

ISOL-France workshop - 03/04/2025

SEASON development team :

Project Managers : O. Cloué (technic) M. Vandebrouck (scientific)

Mechanical conception : S. Cazaux, P. Daniel-Thomas

Detection/Acquisition : F. Bouyjou, T. Chaminade, D. Thisse

Control & Command : A. Gaget, J. Relland, A. Roger

Electrical engineering : J. Noury, Y. Reinert

Simulations : E. Rey-herme








SEASON decaystation and context




SEASON's environment

- Study of heavy and super heavy nuclei
 - single particle structure Ο
 - nuclear deformation \cap
 - stability 0
- Designed for S³-Low Energy Branch (LEB) at Spiral2






Counter for laser spectroscopy Detailed α , e-, y decay spectroscopy Coupling of atomic and nuclear approaches



simulation done by Emmanuel Rey-herme





simulation done by Emmanuel Rey-herme








Mounting at GANIL





- 1st week: mounting of the tunnel and the rest of the detectors on their copper frames.






- 1st week: mounting of the tunnel and the rest of the detectors on their copper frames.
- 2nd week: installation of the chamber on the frame and in room 51.






- 1st week: mounting of the tunnel and the rest of the detectors on their copper frames.
- 2nd week: installation of the chamber on the frame and in room 51.
- 3rd week:
 - vacuum tests and installation of detectors, cables and cooling circuit.
 - first polarization.






- 1st week: mounting of the tunnel and the rest of the detectors on their copper frames.
- 2nd week: installation of the chamber on the frame and in room 51.
- 3rd week:
 - vacuum tests and installation of detectors, cables and cooling circuit.
 - first polarization.
 - sewing of the sources on their support.







- 1st week: mounting of the tunnel and the rest of the detectors on their copper frames.
- 2nd week: installation of the chamber on the frame and in room 51.
- 3rd week:
 - vacuum tests and installation of detectors, cables and cooling circuit.
 - first polarization.
 - sewing of the sources on their support.
 - connecting to the acquisition (NUMEXO2)






- 1st week: mounting of the tunnel and the rest of the detectors on their copper frames.
- 2nd week: installation of the chamber on the frame and in room 51.
- 3rd week:
 - vacuum tests and installation of detectors, cables and cooling circuit.
 - first polarization.
 - sewing of the sources on their support.
 - connecting to the acquisition (NUMEXO2)
- 4th week: installation of the calibration arms








- 1st week: mounting of the tunnel and the rest of the detectors on their copper frames.
- 2nd week: installation of the chamber on the frame and in room 51.
- 3rd week:
 - vacuum tests and installation of detectors, cables and cooling circuit.
 - first polarization.
 - sewing of the sources on their support.
 - connecting to the acquisition (NUMEXO2)
- 4th week: installation of the calibration arms



March : finishing the mounting and starting the acquisitions

- 5th week:
 - installation of the back table for HPGe, with translation motor (but mechanical problems).
 - leakage issues (partly solved now 2*10⁻⁵ mbar).



March : finishing the mounting and starting the acquisitions

- 5^{th} week:
 - installation of the back table for HPGe, with translation motor (but mechanical problems).
 - leakage issues (partly solved now 2*10⁻⁵ mbar).
- 6th week: First acquisitions with sources !
- 7th week: First acquisitions with sources and with timestamps (issues with GTS cards fixed).






First results of thesource commissioning





First acquisitions:

- No time alignment : issues with the injection (now solved)
- Missing strips : possibly due to issues in the "éclateurs"








First acquisitions:


- No time alignment : issues with the injection (now solved)
- Missing strips : possibly due to issues in the "éclateurs"
 - Detector DU at 30 mm from the source:
 - 1 ASIC with higher count rate
 - 1 missing strip





First acquisitions:


- No time alignment : issues with the injection (now solved)
- Missing strips : possibly due to issues in the "éclateurs"
 - Detector DU at 30 mm from the source:
 - 1 ASIC with higher count rate
 - 1 missing strip
 - Detector MD at 9.5 mm from the source:
 - 1 ASIC with higher count rate
 - 1 missing strip






Calibration per ring

- First: calibration per strip
- Due to straggling: calibration per pixel
- Due to low statistics on the sides: calibration per ring






Example: Resolution vs ring number for MD

Comparison per strip with simulation

MD- 9.5 mm from source

Spectrum from simulation

Spectrum from acquisition




Cea ISOL-France



Comparison per strip with simulation

Spectrum from simulation (strip per strip)








Comparison per strip with simulation

Spectrum from simulation (strip per strip)















SEASON's schedule in 2025



Conclusions

- Mechanical mounting is almost over.
- All DSSDs are functioning, although more acquisitions and analysis are needed.
- What is next:
 - Mechanical and vacuum issues should be fixed soon
 - During the summer, sent to Jyväskylä for the commissioning experiment and the experimental campaign, before being sent back to GANIL







Thank you !

SEASON development team :

Thomas Bey¹, Florent Bouyjou¹, Sandrine Cazaux², Thomas Chaminade¹, Olivier Cloué² (technical project manager), Olivier Corpace², Philippe Daniel-Thomas², Jules Dartois¹, Antoine Drouart³, Alexis Gaget², Olivier Gevin¹, Thomas Goigoux³ (postdoc), Jean-Christophe Guillard². Mariam Kebbiri¹, Fabien Prunes¹, Jorge Mendes-Ribeiro², Julien Noury², Mathilde Ragot³ (PhD student), Yann Reinert², Johan Relland², Emmanuel Rey-herme³ (PhD student), Arnaud Roger², Barbara Sulignano³, Christophe Theisen³, Damien Thisse³, Marine Vandebrouck³ (scientific project manager).

1. Irfu/DEDIP (Département d'Électronique des Détecteurs et d'Informatique pour la Physique)


2. Irfu/DIS (Département d'Ingénierie des Systèmes)


3. Irfu/DPhN (Département de Physique Nucléaire)



Back-up







-motor to rotate the wheel

Upstream system: motorised to slide the tunnel part of the main station and one of the two detectors in the deported station

ISOL-France


cea



Deposing carbon foils onto the metal holders








Already tested twice in experiment & survived the vacuum test in SEASON's chamber






Example for the MD at 9.5 mm (30 min acquisition)

Low coincidence rate since no time alignment



Merged Rings Visualization









Analysis method for fixed gain acquisitions

Signal from FEANICS digitized by NUMEXO2





Optimization of the trapeze parameter: for alphas



- L should be as large as possible on the front side and around 1250 ns on the back side
- G should be set at about 1/10 of L




Experimental conditions : depletion voltage

I (nA) LAUDA -20 °C (6 °C FEANICS) 600 LAUDA 0 °C (16 °C FEANICS) LAUDA 20 °C (28 °C FEANICS) 500 400 300 200 100 20 40 60 80 100 120 ñ U (V)

Current vs Voltage

Energy resolution (FWHM) vs voltage





Leakage current comparison


(NA) LAUDA -20 ºC (6 ºC FEANICS) LAUDA 0 °C (16 °C FEANICS) LAUDA 20 ºC (28 ºC FEANICS) T (V)

Courbe courant tension BB7 3562-1





High efficiency for both electron and α -particle




Most compact configuration:

Alpha efficiency = 84 %

Electron efficiency = 56 %



FEANICS



Front End Adaptive gaiN Integrated CircuitS:


- double gain preamplifier with automatic gain switch
- CSA floor noise (no detector): ~2.3 keV variable threshold for gain switch
- can also be set to fixed gain
- → Directly connected to the detector to limit the noise
- → Outputs a differential signal to be sent to the digitizer



SEASON's commissioning experiment


- 1. proton beam onto ²³²Th target
- 2. reaction of fusion evaporation
- 3. production of actinides
- 4. study of ²²⁵Pa decay towards ²²¹Ac

Considered experiments : 232 Th(α , xn) $^{236-x}$ U 233 U(p, xn) $^{234-x}$ Np 233 U(α , xn) $^{237-x}$ Pu Coupling with mass measurement (trap)






Why this reaction? ²³²Th(p,xn)^{233-x}Pa



E. Rey-herme, PhD thesis (2023)

• Use previous experimental results as a benchmark to characterize SEASON



 Improved efficiency => look for new transitions that were not visible before