



Optical network issues in MEUST


P. Lamare

Network constraints

- ❑ MEOC with 36 optical fibres
 - 4 fibres for CC and Sea Sciences
 - Up to 32 fibres available for the detector network for node 1
- ❑ Node in series
- ❑ Node designed for a life time of 15 years
- ❑ 4 DUs connected in series from one node user port (Up to 5 wet-met connectors in series)
- ❑ Optical components for the detector to be integrated in the node (definition, availability...)


Optical network overview

- 3 independent networks:
 - Infrastructure CC
 - Sea science
 - KM3NeT detector (*main focus of this talk*)




MEOC cable

- Cable ordered to Alcatel reference OALC-7
- 36 LEAF-EP fibres
- Cable under manufacture



Fibre type	LEAF EP (NZDSF G655)
Typical CD (ps/nm/km) @ 1550nm & 20°C	- 4.0
Zero Dispersion temperature coefficient	0.03nm/°C
Typical Dispersion slope @ 1550nm (ps/nm ² /km)	0.123
Typical core effective area (μm ²) @ 1550nm	68
Typical Mode field diameter (μm) @ 1550 nm	9.2
Effective refractive index	1.470
Non linear parameter n ₂ @ 1550nm (10 ⁻²⁰ m ² /W)	2.5
Cable Cut - off λ _{cc} (nm)	< 1520
Fibre diameter (μm)	125 ± 1
Core Concentricity error (μm)	≤ 0.6
Fibre non-circularity (%)	< 2
Coating diameter (μm)	250 ± 5
Local attenuation discontinuity (dB)	< 0.1
Typical PMD (ps/km ^{1/2}) @ 1550nm	≤ 0.15
Proof Test (kpsi)	≥ 200

KM3NeT optical scheme




Transposition in MEUST

- ❑ To minimize active components in the node
- ❑ To minimize the dependence of the DUs optical network definition on the node development (different time scale)
- ❑ To allow network adaptation (before deployment!!!)
- ❑ Some parts moved from node to DU

Possible implementation in MEUST

Very preliminary proposal, several issues to solve



Main issues to solve

- ❑ Definition of DU optical network
- ❑ Definition of components to be integrated in the node
- ❑ Validation of the DU in series concept

Answers needed urgently to finalize the design of the node

Summary

- ❑ Construction of the infrastructure underway
- ❑ Design done to be flexible... with some limits!!!
- ❑ Several issues to be solved

Critical items:

- ❑ For infrastructure development
 - DU optical network
 - Validation of DUs in series