Status of GSDC, KISTI

Ilyeon-Yeo, for the GSDC Tier-1 Team ilyeon9@kisti.re.kr

KISTI GSDC

GSDC

- Global Science Data hub Center
- Subdivision of National Institute of Supercomputing and Networking in KISTI
- Providing computing and storage resources for collaborations with HEP experiments (ALICE, BELLE, CDF, LIGO, STAR and so on.)
- Tier-I candidate for the ALICE

ALICE Tier-2

- Start from mid of 2007
- 120 core / 50 TB Disk

ALICE Tier-I

- Start test-bed in July 2010
- ▶ I500 core / IPB Disk / IPB Tape
- Currently under evaluation
- ▶ EMI-2 middleware migration done
 - OS upgrade : Scientific Linux 6
- Dec. 2012: Tape system installation complete
 - ▶ IBM TS3500
 - Dual Caches: Xrootd, GPFS (High Availability)
- Mar. 2013: start of raw data migration to KISTI
 - > 310 TB with 400k files

GSDC Team


ROLE	Name
Representative	Haeng-Jin Jang
	Hee-Jun Yoon
System Administration	Seung-Hee Lee
	Jeong-Heon Kim
Storage: Disk & Tape	Hee-Jun Yoon
	Sang-Oh Park
	Hyeong-Woo Park
Network	KISTI support (Dr. Bu-Seung Cho)
Grid Middleware	II-Yeon Yeo
	Sang-Un Ahn
ALICE(KiAF) support & Production	Sang-Un Ahn

Resource

	KISTI_CREAM (T2)	KISTI_GSDC (T1)
CPU (core)	120	1512
DISK	50 TB	I PB
TAPE	-	I PB


- ▶ TI: I5I2 cores (63 WNs * 24 cores) with 3GB memory/core
- ▶ T2: I20 cores (I5WNs * 8 cores) with 2GB memory/core
- I PB Tape space for data archiving
 - 8 tape drives (total 2GB/s throughput) with 260 media (4TB per medium)
 - For cache,
 - 200 TB xrootd pool
 - > 275 TB GPFS pool
 - Optimization of the policy (migrate/purge) for xrootd and GPFS is in progress

Tape System of GSDC



Operation

- Concurrent job capacity: 1512
- ▶ 3 months average: I328 (~ 88% of job capacity)
 - > Requirement: 85% of job capacity at least for 2 months
- Announced shutdown for maintenance, no critical outage
- Correlation with production/user job activities, central service



Site Availability/Reliability




Availability of WLCG Tier-0 + Tier-1 Sites

ALICE

April 2013

Target Availability for each site is 97.0%. Target for 8 best sites is 98.0%

Availability Algorithm: 'And' of all Service Flavours




Detailed Monthly Site Reliability (ops tests)

Site	Nov 2012	Dec 2012	Jan 2013	Feb 2013	Mar 2013	Apr 2013
CH-CERN	98	100	99	100	100	100
CA-TRIUMF	99	99	100	100	100	100
DE-KIT	97	100	100	100	100	100
ES-PIC	100	99	100	99	100	100
FR-CCIN2P3	100	97	99	100	100	100
IT-INFN-CNAF	98	99	92	100	100	100
KR-KISTI-GSDC	95	98	96	97	100	100
NDGF	100	100	100	100	100	100
NL-T1	97	100	97	100	98	98
NL-T1	99	94	98	94	97	96
TW-ASGC	100	98	97	98	100	100
UK-T1-RAL	89	99	100	100	99	100
US-FNAL-CMS	98	99	100	100	100	100
US-T1-BNL	100	100	99	100	98	100
Target	97	97	97	97	97	97

2013 RAW data replication

- Raw data transfer started on 7th March
 - Passed periodic functional test by ALICE (100% availability after tape configuration)
 - Requirement: 90% Storage Element availability (functional tests) for at least 2 months
 - Total data size: 309.9 TB (400k files are in queue)
 - ▶ 90 runs done out of 177 runs (29th May) : ~ 149 TB (48% of total)
 - Transfer speed: 24MB/s on average
 - Requirement: High speed transfer of data from CERN to KISTI at the speed required to receive and archive 10% of the ALICE AA raw data foreseen for 2012 over a continuous period of 2 weeks
 - ▶ Effort to improve the network performance in on-going together with KISTI network expert



Network

- Currently IGbps (dedicated) bandwidth between CERN-KISTI is now being fully used
 - Requirement: 3Gbps or higher bandwidth to join LHC OPN
- ▶ In June 2013, dedicated 2Gbps link will be deployed:
 - Connection: GLORIAD-KR NLR* SURFnet CERN
 - Before: (IGbps) GLORIAD-KR CAnet, CANARIE SURFnet CERN
- With 2Gbps, discussion among network experts (KISTI-CERN) to join LHC OPN will soon be started



* National Lambda Rail(U.S.)

Pledged

Pledged resources

- Based on WLCG & ALICE Collaboration MoU
- Meeting ALICE requirement by 2013

	Current	Pledged (% of ALICE request for T1's)		
		2012	2013	
CPUs (HS06)	17,200	18,800 (12%)	25,000 (21%)	
Disk (TB)	1,000	1,000 (9%)	1,000 (9%)	
Tape (TB)	1,000	700 (2%)	1,500 (7%)	

Milestones (Summary of Requirements)

Objective		Target date	
		Target	
Nominate KISTI/GSDC representatives in the WLCG Management Board and the GDB	Jun. 2012	-	
Establishment of a IGbps connectivity to CERN	Apr. 2012	-	
Installation of tape system	Dec. 2012	-	
High speed transfer of data from CERN to KISTI at the speed required to receive and archive 10% of the ALICE AA raw data foreseen for 2012 over a continuous period of 2 weeks	-	Aug. 2013	
Provide a precise plan for 3Gbps (or higher) connectivity to CERN	-	Jul. 2013	
Present a plan for providing on-call support according to the T1 specifications as laid out in the WLCG MoU		Jun. 2013	
85% of the job capacity running for at least 2 months	Apr. 2013	-	
90% Storage Element availability (functional tests) for at least 2 months	Apr. 2013	-	
Running of the reliability tests (both OPS and ALICE-specific) and publishing those to the new SAM infrastructure	Feb. 2013	-	
Integration with the APEL accounting system and publishing accounting data	Jan. 2013	-	
90% of the WLCG TI service targets for at least 2 months	-	Sep. 2013	
Integration in the WLCG OPN (with 2Gbps)	-	Jul. 2013	
Functional tests of the OPN (with 2Gbps)	-	Aug. 2013	

Remaining requirements: plans for

- Improving network bandwidth/performance and joining LHC OPN
- Establishing a system to support Tier-1 services in 24/7

Conclusion

- KISTI-GSDC has been demonstrating WLCG Tier-1 for ALICE experiment f ollowing the proposed plan
- ▶ Full sets of RAW data is being replicated to KISTI tape storage
- In June, dedicated 2Gbps bandwidth will be established between CERN and KISTI, and discussion to join OPN will be started



Thank you for listening!

Q&A

