


# DBD realization studies

Vincent Boudry  
*École polytechnique*



**Journées Collisionneur Linéaire**  
**13-14 mai 2013**

# ILD Philosophy

## 1) Particle Flow **calorimetry**

- ▶ “basic requirement”: sep of  $H \rightarrow WW/ZZ \rightarrow 4j$ 
  - ◆  $\sigma_z/M_z \sim= \sigma_w/M_w \sim= 2.7\% \oplus 2.75\sigma$  sep  $\Rightarrow \sigma_E/E$  (jets) < 3.8%
  - ◆  $60\%/vE \rightarrow 30\%/vE \Leftrightarrow +\sim 40\% \mathcal{L}$

## 2) Large TPC

- ▶ Precision and low  $X_0$  budget
- ▶ pattern recognition

## 3) Precision by Silicon detectors: vertex & Calo SET

- ▶ flavour tagging

## 4) Large acceptance

- ▶ Fwd Calorimetry:  
lumi, veto, beam monitoring
- Merging of LDC & GLD  $\rightarrow$  ILD
  - ▶ “best dimension”
  - ▶ Optimisation studies





# Geometry: dimensions at large

- Mix of LDC & GLD parameters  
+ optimisation studies based on PandoraPFA

- Basic measuring rod
  - $\sigma_{E_j}/E_j$  (& Bgd) vs
    - TPC dimensions
    - Radius Magnet (HCAL thickness)
    - B field

- Other perfs:
  - $\tau$  reconstruction
  - ...
- Done for the baseline (Si-W ECAL + Scint HCAL)
- TO BE REDONE**

From ILD LoI



# Calorimeter options

B = 3.5T

## HCAL


- Analog: Scint/Fe
  - 50 Layers
  - $3 \times 3 \text{ cm}^2$
- Semi-Digital: Rpc/Fe
  - 48 layers...
  - $1 \times 1 \text{ cm}^2$

## ECAL

- Si/W
  - $0.5 \times 0.5 \text{ cm}^2$
- Scint/W
  - $0.4 \times 45 \text{ cm}^2$
- Sc $\oplus$ Si/W

## FCAL


- LumiCAL (Si/W); LHCAL (SiW); BeamCal (GaAs)




# Geometries for the HCALs

- Sensor agnostic

DESIGN 1 (TESLA [DESY])



DESIGN 2 ("a la Videau" [LLR, IPNL])



Better access to electronics

Better hermiticity


Larger radius

Mechanical rigidity


"Classical" challenge: sound mechanics with minimal dead mat. and inhomogeneities

## Parameters for acceleration spectrum

- Peak Ground Acceleration:  $1.5 \text{ m/s}^2$
- Damping ratio for steel structure: 2%
- Soil type: hard soil





- ❖ With the acceleration response spectrum applied along the detector axis, the fundamental mode of the structure dominates: back and forth motion of the yoke ring
- ❖ The max displacement is around 23mm, which is quite high
- ❖ The peak stress is located in the feet. The level seems acceptable but the results need to be checked with a proper design and model
- ❖ Attaching the 3 rings together is probably the way to go to increase the overall stiffness and reduce the peak displacement



From O.Fereirra (LLR)




# Interaction length profile (TESLA)



# Integration studies : Procedure & tools

Courtesy of C. Clerc (ILD'2012)  
(and MDI group)

## AHcal integration sequences






From K.Gadow( Desy)

ILD workshop 2012, Kyushu University

## SDHcal integration studies : the 5 wheels concept .


### Building SCENARIO :

- 8x48 in position on specific tool
- 1 face put down
- 8\*48 plates welded on one face
- One other tool in place
- 180° rotation
- 8\*48 plates welded on this other face




From J.C.Ianigro (IPNL)


## Ecal integration scenario ( Barrel)



From One stave



To full barrel ...



From M.Anduze( LLR)

24 May 2012

Task	Description / constraint	tooling	FTE	Time
1	Handling of 1 ( over 40) module. Weight 1t	repeated 5 times	2T	9 days
2	Alignment			
3	Module 1 in position on frame		2T	
4	Stave 1 and its frame on the support structure			
5	Insertion of 375 slabs per stave. 1 Slab >10 to 15 kg alignment within alvela = 500 µm over 1.8 m	2T		
6	Electrical connections up to LDA boards	2T		2 weeks
7	Cooling blocks ( 5 ) up to Module edge, over LDA up to main distribution line position	2T		
8	Electrical and cooling distribution lines on top of the stave			
9	Tests ( electronic and signal)	2T part-time		2 months

to be repeated 8 times.

Some parts can be done in parallel  
(depends on the available manpower, because not the same qualification) :  
Tasks 1-4 of stave (n+1) and Tasks 5 to 9 of the stave (n)

Needed space :

For a stave assembly : 7\*4 m<sup>2</sup>  
Per Beam , for storage : 6\*3 m<sup>2</sup>

Stave ( fully equipped)+ frame + support

about 12 t


21 May 2012

These studies include estimation of :

- the timescale ( assembly hall and experimental area
- Manpower
- Needed space for Assembly, test, storage & integration work
- Tooling

# Challenges of high granularity for calorimeters



- High number of channels  $\sim 10^8$ 
  - ▶ Calibration
  - ▶ Readout
    - ◆ Triggering
- Embedded Electronics,
  - ▶ Heat
    - ⇒ Power-Pulsed modes with DT of  $\sim \leq 1\%$  [1ms every 200ms]
      - ◆ Stability;
      - ◆ Pulsed currents ⇒ Vibrations ⇒ aging
        - PCB design; Cable geometry
  - ▶ Zero Suppr. by Auto-triggering
    - ⇒ (Gain) Stability ⇒ Monitoring
      - ◆ Calibration DB
  - ▶ Local Storage ⇒ Noise taming
  - ▶ Radiation hardness & interactions ✓
- Industrialisation
  - ▶ **TO BE DONE**



# Integration & Services: Power

## ■ Cabling

- ▶ Power Pulsing ⇒ local energy storage
- ▶ Power studies
  - ◆ Need of an optimized Front-End Electronics



## ■ Simulation

- ▶ Simplified model in Mokka

# Integration & services: Cooling




- Services & cabling

- ▶ cooling philosophy

- ◆ Each detector should remove its own heat
    - ◆ ECAL  $120 \text{ Mch} \times 25\mu\text{W} \Rightarrow 3 \text{ kW}$ 
      - with 200 gain from Power Pulsing


- ▶ DAQ

- ◆ 1 Concentrator board per Module
      - + power
      - + capacitors



# Global Leakless Cooling system

ECAL / Cooling / EUDET prototype




March 20<sup>th</sup>, 2013 Hambourg

ECAL End-Cap & cooling studies

10

Courtesy of Julien GIRAUD, Denis GRONDIN (LPSC)

Vincent.Boudry@in2p3.fr



Pipe Path

ECAL / Leak less test loop




#### Test loop goal :


- Validate the theory of the whole leak less system.
- Find maximum leak less zone versus pipe diameter.
- Minimum equipment needed for control (pressure transmitter, fluid flow transmitter...)
- Test heat exchanger / pipe connection

#### 2013 :

- Skid assembling and testing
- First test with 3 loops => fall 2013



Cooling skid



LPSC test loop

# DAQ & data flux

- DAQ structure fixed
  - ▶ concentrator board on detector
- on-going work
  - ▶ (DAQ for TB)
  - ▶ Protocols
  - ▶ Stability
  - ▶ Extensibility  
(LDA with 50 layers)
- Still to be done
  - ▶ mechanics (and local links).
  - ▶ power consumption

## DAQ electronics: GDCC

Link Data Aggregator (LDA):

- difficult to maintain firmware (Xilinx licence is needed for Ethernet interface, current version is obsolete; understanding of packet management requires reverse engineering)
- not sufficiently reliable (grounding, shielding, connections)

**Gigabit Data Concentrator Card (GDCC)** will replace LDA. Same software, reuse of some hardware parts.

First iteration of tests has been performed, a few bugs resolved → next iteration in May. Main source of packet losses (1-2%, bug in LDA) is discovered and understood.

Plan: final version in July for tests, decision on production in September.



# Outlook

- Lot of engineering work in the conception of the ILD calorimetry since the LOI; good part of it in DBD
- Redo the optimization studies
  - ▶ for 250-500 GeV (is 1000 GeV)
    - ◆ Current model still a mix of GLC and LDC...
    - ◆ ⇔ with improving SW...
- Still much work on
  - ▶ mechanics (vibrations),
  - ▶ integration procedure,
  - ▶ cooling,
  - ▶ power,
  - ▶ VFE zero suppression
  - ▶ DAQ
  - ▶ ...