



**General Electronics for TPC** 

# A project based on the **µTCA**<sup>™</sup> standard

(MTCA.0 specifications)

# design status

xTCA DAQ Meeting - June 21, 2013



Collaboration based on an "ANR" grant for the French labs



## Choice of µTCA standard for the project





« Dual Star » topology shelf (redundancy)

SCHROFF & VADATECH (VT893) shelves approved



Up to 6.5 Gbit/s by serial port (1TX/1RX)



#### Associated Field Replaceable Units:

- MicroTCA Carrier Hub (MCH)

Carrier management / Network Switch

- Power Module (PM)
- Advance Mezzanine Card (AMC)
- JTAG Switch Module (JSM)
- Cooling Units (CU)



xTCA DAQ Meeting - June 21, 2013

Gilles Wittwer







Distribution of a 100 MHz clock to every CoBo of each crate, phase aligned (skew< 1ns - TDC) ⇒ µTCA-CLK1

Distribution of a synchronous start/stop sampling (phase aligned)  $\Rightarrow \mu TCA-CLK2$ 

Exchanging data in parallel with the CoBo @ 800 Mbit/s (TX/RX) with its own shelf or slave shelves



xTCA DAQ Meeting - June 21, 2013



xTCA DAQ Meeting - June 21, 2013





### MUTANT in terms of schedule



### MUTANT module is on track

- Board A is tested

(as a kit on the table then inside the crate with management)

- One board is running at NSCL/MSU (USA)
- Electronic study of board B is ready PCB design is in progress
- Full MUTANT prototype is expected in October 2013
- CoBo module is also under test @ NSCL
  - 3 boards tested
  - Production is foreseen by the end of this year

### First µTCA configuration (CoBos + MUTANT) end 2013/early 2014

- > First use at GANIL/SPIRAL II with ACTAR TPC and S<sup>3</sup> (Spiral2 Super Spectrometer)
- Beyond the laboratories concerned by the collaboration (GANIL,NSCL,IRFU Saclay, CENBG), other foreign laboratories are interested by the GET system:
  - -> Tokyo & Riken labs (Japan), INFN Catania (Italy), IBS Daejeon (South Korea), ...



