







中国科学院高能物理研究所

SRF2013, 26th Sept., 2013, Paris

SRF Cavities for ADS Project in China

Y. He, W. Yue, S. Zhang, and Linac Group

Institute of Modern Physics (IMP)

W. Pan, J. Dai, Z. Li, Z. Liu, and RF Group

Institute of High Energy Physics (IHEP)








- Introduction of ADS Project in China
- Cavities for Injector I
- Cavities for Injector II
- Cavities for Main Linac
- Summary





Roadmap of ADS Project in China






"strategic Priority Research Program" of the Chinese Academy of Sciences Stage 3: Demo facility (~1000 MW_t, ~2040)





Layout of Accelerator for C-ADS





IHEP and IMP co-work on the accelerator. Final project has two identical injectors. Two designs of injector is due to technical uncertainty at very low energy segment.



Injector I



General Specifications of the Cavities



	Spoke	HWR	HWR	Spoke	Spoke	Ellip	Ellip	TI-s:4
	012	010	015	021	040	063	082	Unit
Freq.	325	162.5	162.5	325	325	650	650	MHz
βg	0.12	0.09	0.14	0.21	0.40	0.63	0.82	-
Aperture	35	40	40	50	50	100	100	mm
Uacc	0.82	0.78	1.82	1.64	2.86	10.26	15.63	MV
Epeak	32.5	25	32	24/31	25/32	29/38	28/36	MV/m
Bpeak	46	50	40	50/65	50/65	50/65	50/65	mT
Temp.	4.5	4.5	4.5	4.5	2	2	2	K
Ploss	10	10	15.5	16.8	6.5	21	39	W
1 1055	$(70n\Omega)$	$(70n\Omega)$	$(70n\Omega)$	$(70n\Omega)$	0.5	<i>L</i> I	37	VV
Number	12	6	6	28	72	28	85	-

Criteria: Bpeak = 50 mT for nornal operation, and 65 mT for compensation.

Operation temperature: 4.5 K is considerated for injectors or before 2015. 2 K may be the final decision, depends on the operation of demo injectors..





Contents




- Introduction of ADS Project in China
- Spoke012 for Injector I
- HWR010 for Injector II
- Spoke021 and Ellip063 for Main Linac
- Plan for the furture








Spoke012 for Injector I











Jointly designed and fabricated by IHEP, PKU, and HIT






Design of Spoke012



Parameter	Value
G	61 Ω
$\rm E_{peak}/E_{acc}$	4.5



Geometry Parameters


Parameter	Value
W	82
Factor	1.25
R2in	199
R2out	164
Liris	73





Simulation of Mutipacting and Detuning





Ports free or			df/dP		
locked	Stiff ribs	Peak deform.(mm)	Peak stress (MPa)	Frequency shift (MHz)	(kHz/torr)
Free	No	3.256	157	-8.28	-10.9
Locked	No	0.218	389	-0.21	-0.278
Free	1 st	0.11	<44.3	0.049	0.065
Locked	1 st	0.065	<45.6	-0.044	-0.058
Free	2 nd	0.848	89	-1.7	-2.24
Locked	2 nd	0.11	118	0.014	0.018







Fabrication of Spoke012





















Vertical Testing of Spoke012-02









- \checkmark Q0=5.8x10⁸ @6MV/m, 4K;
- ✓Q0=3.4x10 8 @7MV/m, 4K


No quench but heavy MP and FE. Testing ended of FE.






High Power Coupler for HT














● 1# outer conductor ▲ 2# outer conducto








Horizontal Testing of Spoke012-2









Piezo tuner was used for frequency loop and closed. The tuning range is +/- 1 kHz.


Level meter was used to measure the heat loading. The static loading is 15.1 W.





Results of horizontal testing






The testing lasted 5 days in Sept. 2013. The heavy multipactor ocured and was overcomed. Q0=2.2E8 was reached at Eacc = 6.5 MeV/m. It just 30% degraded from VT.








6-cavity Cryomodule for Injector I














5704 mm,6 spokes, 6 couplers, 5 solenoids, 5 BPMs, 2 valves inside





Contents





- Introduction of ADS Project in China
- Cavities for Injector I
- Cavities for Injector II
- Cavities for Main Linac
- Summary



HWRs for Injector II














RF Design of HWR010





30 G		ш	
		u W k	
	-		

B _{pk} /E _{acc}	; E _{pk} /E _{acc}
R/Q_0	; G

Rin (mm)	40
Rout (mm)	92
Liris (mm)	110
T (mm)	45
W (mm)	90
D1	100
D2	300
Rblend2	15


	HWR010 Squeezed
Freq(MHz)	162.5
βopt	0.101
Uacc(MV)	0.78
Eacc(MV/m)	4.5
Epeak(MV/m)	25
Bpeak(mT)	50
$G=Rs*Q0(\Omega)$	28.5





Simulation of Multipacting







1000

500



Fabrication of HWRs



- Material
 - TIC, RRR>300, partly RRR>380
- Drawing, machining and BCP
 - ▶ Punching die, Al 7075
 - Surface survey before every step of fabrication
 - ▶ BCP (65%HNO₃:40%HF:85%H₃PO₄=1:1:2) 10um, resin by UPW, drying in cleanroom of class 100
 - ▶ Polishing every seam and BCP 10um before EBW

▶ E-beam welding

- **EWB** by two different parameters:
 - ▶ #01, #02;
 - ▶ #03, #04, #05.







Surface Processing of HWRs




Cavity #	Test #	Bulk removal	Degassing	Light removal	Bake	Addition
2	12/01/12	120 um	680 C 3 hours	20 um	150~250C 48 hours	At SINAP w/o HPR
2	01/29/13	-	-	30 um	200 C 48 hours	At IMP
3	05/18/13	140 um	650 C 10 hours	30 um	120 C 48 hours	
3	07/16/13	-	850 C 3 hours	30 um	120 C 48 hours	
4	06/08/13	130 um	650 C 10 hours	30 um	120 C 48 hours	
5	03/23/13	160 um	650 C 10 hours	30 um	120 C 48 hours	Caps annealing
5	09/09/13	-	850 C	30 um	120 C 48 hours	He Vessel



VT results of HWR010-S-02~05





Epeak (MV/m)

1E8-

0.1


X Ray HWR010-S-5 with

Helium vessel



VT results of HWR010-S-02~05





Cryoperm shielding,

< 20 mGs, at room temp.,

<7mT at 4 K, Rmag=0.8 n Ω

Rs of #5 is around 10 n Ω . #3 after 850 C baking is around 2 n Ω .








Mechanical analysis



	Simulation result		Test result		
Cavity	Bared cavity	With He vessel	Bared cavity	With He vessel	
Bandwidth	235.5 Hz				
Pressure sensitivity	25.1	14.2	70	50	Hz/mbar
Helium fluctuation (+/-1.5mbar)	37.6	21.3	-	-	Hz
LFD coefficient	-4.66		-16.77	-	Hz/(MV/m) ²












Ribs to reduce df/dp










Horizontal Testing of HWR




Op. Temperature	4.4 K
Op. Pressure	1.25 bar
Cooling	bath
Pressure	±1.5 mbar
Dynamic load	10 W
Solenoid storage	27KJ













HWR Coupler and high power testing







The outer conductor was designed to be cooled by helium gas through the spiral grooves around the outer surface while the inner conductor was cooled by water.






The coupler has passed a RF power of 20kW in continuous travelling wave mode limited by the RF source available.

		el le
		8 3
)-(
(E. a.		

Spiral grooves

_				
Date	Start time	Stop time	Pf1 max	Elapsed time/hrs
2013-6-1	13:50	20:00	~212W	5.3 hrs
2013-6-2	9:25	16:30	~738W	7 hrs
2013-6-3	9:10	17:17	~Peak 1.3kW	6 hrs
2013-6-4	9:55	23:47	~2.90kW	12.3hrs
2013-6-5	9:10	22:32	~5kW	12 hrs
2013-6-6	9:13	21:56	~9.42kW	8 hrs
2013-6-7	9:07	20:50	~10.6kW	10hrs
2013-6-8	9:13	18:00	~20.0kW	8.6 hrs

Total conditioning time: 63~69 hrs



window-up

windowdown

• outer conduct-up





Contents



- Introduction of ADS Project in China
- Cavities for Injector I
- Cavities for Injector II
- Cavities for Main Linac
 - **Spoke021**
 - **Ellip082**
- Summary





Type

Monitor

Frequency

Loaded Freq

External Q

Phase

0.324978

0 degrees

729359

0.028921 Max

0.010394 -0.0081325

-0.026659

-0.045186

-0.063712

-0.082239


-0.10077

-0.11929

-0.13782 Min


Specifications of Spoke021





Directional De	eformation
@1 atm & 80	Okg tuning
force	

Para.	
E _p /E _{acc} /(void)	3.88
$B_p/E_{acc} / mT/(MV/m)$	8.13
β_{opt}	0.246
$\mathbf{r}/\mathbf{Q}/\Omega$	206
\mathbf{G} / Ω	87
Df/dL /kHz/mm	632
R_{BCS} /n Ω	0.68
Q0@Rres=5nΩ	1.38E10
Q _{e,opt}	7.28E5
Le @Q _{e,opt} /mm	22.3
E _p /MV/m @1J	12.04
H _p /kA/m @1J	21.22
Vc @32.5MV/m /MV	1.75
Vc @65mT /MV /MV	1.58




Equivalent Stress @1 atm & 800kg tuning force



MP Simulation of Spoke021










Fabrication of Spoke021









Contents



- Introduction of ADS Project in China
- Cavities for Injector I
- Cavities for Injector II
- Cavities for Main Linac
 - Spoke021
 - **Ellip082**
- Summary






Design of Ellip082



Design Objective: 650MHz 5-cell SC Cavity, Eacc=15MV/m, $Q_0>3E9$ Design Principle:

- ✓ Large beam pipe and iris
- ✓ low Epk/Eacc and Bpk/Eacc
- ✓No MP
- ✓ Reasonable Lorentz factor




		-
	Center cell	End cell
L (cm)	9.461	9.461
Riris (cm)	5	5
D(cm)	20.0207	20.0207
A(cm)	7.027	7.166
B(cm)	7.027	7.883
a(cm)	1.681	1.667
b(cm)	2.522	2.501
α(°)	7	6.678
E_p/E_{acc}	2.1	12
$B_p/E_{acc} mT/(MV/m)$	4.0	05
r/Q [Ω]	514	4.6
G [Ω]	235	5.5
k [%]	0.9	0/0
Field flatness [%]	>98	







MP and LF Simulation of Ellip082














Fabrication of Ellip082















Contents



- Introduction of ADS Project in China
- Cavities for Injector I
- Cavities for Injector II
- Cavities for Main Linac
- Summary





Summary



- In 2015, ADS project in China will has two 10 MeV, 10 mA and CW superconducting linac commission.
- The prototype of Spoke012 for injector I is qualified with VT and HT. Mass production now! A 6-cavity CM will be assembled and tested with beam by the end of 2014.
- The four cavities of HWR010 for injector II are qualified with VT. Mass production is on going. HT in TCM1 of will be done in early of 2014. And the first 6-cavity CM will be assembled and tested with beam in early of 2015.
- ▶ The SRF cavities for main linac are in fabrication and will be tested soon.







PLS read more details in the poster:

THP 021,	Z.Q. Li,	Design of Spoke021
THP 016,	W.M. Yue,	Development of HWR010
THP 081,	S.B. He,	Testing of Tuner for HWR010
THP 028,	P. Sha,	Research on Spoke040
THP 050,	X. Chen,	High Power Coupler for Spoke012
THP 098,	J. Zhang,	LLRF and Data Acq. for VT of Spoke012

Thanks!

