
DE LA RECHERCHE À L'INDUSTRIE



## CHALLENGES TO ASSEMBLE 100 CRYOMODULES FOR E-XFEL





SRF13 Catherine MADEC






### **QUICK OVERVIEW**











































# To assemble 100 accelerator cryomodules with a throughput of 1 per week!

operated by an industrial contractor on the Saclay site and CEA infrastructures with CEA supervision





#### **CHALLENGES**



#### Technical:

- Get the infrastructure ready
- Get the tooling ready
- Get the assembly procedure ready
- Get the CEA team trained
- Get the quality insurance system implemented
- Set-up QA/QC and MBOM
- Get results

#### Calendar:

- 1 CM per week
- Nov 2015

#### Ressources :

- Industrial ressource
- CEA ressource
- Performances
- Components availability







#### PHASES OF THE PROJECT



1. Preliminary study subcontracted 2007 – 2008

2. Preparation of Infrastructure and Tooling 2009 – 2010

3. Pre-industrial study and prototyping 2010 – 2012

Preindustrial study

 Training and Commissioning at Saclay with XFEL Prototype Modules (PXFEL2 and PXFEL3)

➤ Leading to Restricted Call for Tender signed in July 2012


4. XFEL module assembly by industry operator 2012 - 2015






### **PHASE 2: DEDICATED ASSEMBLY BUILDINGS**








### **PHASE 2: WORKSTATIONS IN ASSY HALLS**





#### **PHASE 2: WORKSTATIONS IN ASSY HALLS**





## PHASE 2: TOLLING, RENOVATION, CLEAN ROOM















#### PHASES OF THE PROJECT



1. Preliminary study subcontracted 2007 – 2008

2. Preparation of Infrastructure and Tooling 2009 – 2010

3. Pre-industrial study and prototyping 2010 – 2012

Preindustrial study

 Training and Commissioning at Saclay with XFEL Prototype Modules (PXFEL2 and PXFEL3)

➤ Leading to Restricted Call for Tender signed in July 2012

4. XFEL module assembly by industry operator 2012 - 2015





#### **PHASE 3: PROTOTYPING**



### GOAL: to get the « Factory » ready

- Implement the pre-industrial study
- Check the infrastructures
- Check the tools
- Check the procedures
- Train the CEA-IRFU team
- Prepare all the documentation templates
- Set-up the QA/QC and MBOM
- Feedback from the assemblies
- With the support of DESY coleagues





#### **PHASE 3: PROTOTYPING**



### The team (~10 persons) has operated:

- the module disassembly of PXFEL2\_1 (started 24/08/2010)
- the module re-assembly of PXFEL2\_1
- the string and module assembly of PXFEL3\_1 (02/05/2011 26/10/2011)

using DESY cavity posts and clean room tools

the string and module assembly of PXFEL2\_2 (30/01/2012 – 04/09/2012)

### using CEA cavity posts and clean room tools

Prototype modules PXFEL2&3 were made from a special production of cryogenic distribution systems ('cold mass') and vacuum vessels, and from 'FLASH' recycled cavities, couplers, tuners, etc...



#### **PHASE 3: PROTOTYPING**











- ✓ Infrastructures
- ✓ Tools
- **Procedures**















**CEA** team trained



#### PROTOTYPES TEST RESULTS IN CMTB







Operating Gradient (Xray <= 10<sup>-2</sup> mGy/min)



- $\rightarrow$  PXFEL2 2;
- → Average gradient ~ 24 MV/m , XFEL conform!
- But individual performance were

   operating gradient degraded



#### **CRYOMODULE MBOM**



In the process of assembling cryomodule, it is mandatory for traceability to **gather**, **record**, **process and archive** the complete configuration and fabrication information for each cryomodule



The MBOM also includes inspection to be performed, the tests to be recorded, the assembly procedures etc... The XFEL cryomodule MBOM contains roughly 500 lines

It uses DESY's Engineering Data Management System (EDMS).





#### **EXAMPLE: XM-2 MBOM**



EDM S-ID	Name	Description	Quantity	Work Status
□	XM-2_STR: Cavity String	Cavity string assembly for XM-2		Working (in Vault)
	XM-2_CCC: Cavity + Cold Coupler	Cavity with cold coupler assembly for XM-2	8	Working (in Vault)
	BQU: BPM-Quadrupole-Unit	BPM-Quadrupole-Unit, VAT main body and BPM	1	Released
	CBL: Cavity Bellows	Cavity bellows	8	Released
	Cavity Dichtung NW78 (Al seal)	Cavity aluminium seal (Dichtung NW78)	17	Released
	Bellow Cavity Assembly Set	Bellow cavity assembly set	7	Released
	Bellow Qpole Assembly Set	Bellow Qpole assembly set	1	Released
	VGV: Gate Valve Assembly	Gate valve assembly	1	Released

The MBOM defines how a specific part type (fabrication part) is produced and from which components.

The part gets fabricated in a physical part and assembled to other physical parts to form one cryomodule. This is recorded in the Bill of Material








### **EXAMPLE: XM-2 BOM**





Summary Poly Properties Poleted Come Next Steps All Versions Access

Configuration: No saved configuration.

Export Ta	able As ● CSV ● HTML ●	XML				
EDMS	S-ID	Serial Number▼	Description	Work Status	Disposition Type	Installation Date/Time
	□ D000000111111189,A,1,1	XM-2_CMAS	XM-2_CMAS: Cold Mass + Aligned String	Working (in Vault)	)	
	□ 🐼 D00000010985499,A,1,1	XM-2_CMS	XM-2_CMS: Cold Mass + String	Working (in Vault)	)	17.09.2013 16:14:45
		XM-2_STR	XM-2_STR: Cavity String	Released	In-Service	01.08.2013 10:31:53
		XM-2_SIN2K	SIN2K: Super Insulation 2K	Working (in Vault)	)	01.08.2013 16:01:59
		SET No 2	Cab-CAV: Cavity RF Cables	Released	In-Service	01.08.2013 11:53:55
	D00000010520869,A,1,1	EZ004	CM: Cold Mass Assembly	Released	In-Service	01.08.2013 11:42:58
		3_08_9610/2.C00 #0002	2Ph Cav1 End Connect	Released	In-Service	31.07.2013 14:22:58
	D00000010169569,A,1,1	3_06_8326/0.000 #0002	Cav1 Gate Valve Support	Released	In-Service	31.07.2013 14:23:01
	D00000010178409,A,1,1	3_06_8322/0.000 #0014	Ti-Bellow DN76	Released	In-Service	31.07.2013 14:33:41
	D00000010178389,A,1,1	3_06_8322/0.000 #0013	Ti-Bellow DN76	Released	In-Service	31.07.2013 14:42:36
	D00000010178369,A,1,1	3_06_8322/0.000 #0012	Ti-Bellow DN76	Released	In-Service	31.07.2013 14:51:40
	D00000010178349,A,1,1	3_06_8322/0.000 #0011	Ti-Bellow DN76	Released	In-Service	31.07.2013 15:00:45
	D00000010178329,A,1,1	3_06_8322/0.000 #0010	Ti-Bellow DN76	Released	In-Service	31.07.2013 15:10:02
	D00000010178309,A,1,1	3_06_8322/0.000 #0009	Ti-Bellow DN76	Released	In-Service	01.08.2013 11:07:35
	D00000010178289,A,1,1	3_06_8322/0.000 #0008	Ti-Bellow DN76	Released	In-Service	01.08.2013 11:08:08
4						






### **EXAMPLE: PHYSICAL PARTS**





Coupler venting for coupler cold part assembly



old Part (TTF3)





### **EXAMPLE: NON-CONFORMANCE REPORTS**



Physical Part , D0000001047	72569,A,1,1 . It	tem Info : Sum	mary					
Summary BOM F	Properties R	elated Items	Next Steps	All Versions	Access			
Related Items			NON	CONFORMANCE REP	ORT	Reference	CEA-XFE	EL-RNC-12-036
Has Fabrication Documentation : 5.0 bje		W European XFEL		CHANGE REQUEST		Page	1	
Name		AFEL		CHANGE REQUEST		Date	25/09/12	2
ASS CR 26,A,1,1  CTR CR 16,A,1,1	EQUIPMENT:	ССР	SERIAL NUMBER:	AC3C32 & AC3C33 (TV AC3C27 & AC3C28 (TV AC3C37 & AC3C38 (TV	VG 33)	FILLED OL	JT BY:	C.Cloué
REC_CR_3,A,1,1	Occurrence pha	se :			Integration level	<u>:</u>	Workstati	on :
SUP CR 9,A,1,1	Control :	x	Reception :	Х	Part	Х	ISO4-CC	
TST CR 39,A,1,1	Manufacturing:		Acceptance :		Subassembly		1	
Has Description : 1 object	Design/validation	:	Destockage :		Equipment		1	
Name	Integration :		Others:		Others			
III IR XM-3 CCP TWG36 - AC3C32,A,1,1	TITLE :	Cold ceramics cap	s: missing holes, mis	-oriented valves, protruc	ding screws			
III XIII-3 COI TWO30-AGGGGZ,A,T,T	DESCRIPTION:							
Is Instance of : 1 object	Vis du capot de p	rotection de la cérar	mique non-percés + t	rous de fixation manqua	ints + vannes à po	sitionner		
Name	Cold ceramics ca	ps from XFEL-Thale	es production: missing	g holes, mis-oriented va	lves, protruding so	crews		
XM-3 CCP: Coupler Cold Part (TTF3),A,1								
Is Affected by : 2 objects	Reference docu	ments :						
Name	TECHNICAL INV	ESTIGATIONS :		Responsible (s)				
CEA-XFEL-RNC-12-036,A,1,1								ange of the cold coupler
CEA-XFEL-RNC-12-038,A,1,1	, ·	,		tween each screw and t	•		on of the va	alve around its fixation
Is Used By Physical Part : 1 object	The missing hole	s will allow the inser	tion of the only 3 inst	, rendering this assembe ead of 4 rods necessary below (see picture 2 bel	to assemble the s		) K interface	e shells at a later stage.
Name				(3.3)	- /			
C00450 A 4 4								



#### PHASES OF THE PROJECT



1. Preliminary study subcontracted 2007 – 2008

2. Preparation of Infrastructure and Tooling 2009 – 2010

3. Pre-industrial study and prototyping 2010 – 2012

Preindustrial study

 Training and Commissioning at Saclay with XFEL Prototype Modules (PXFEL2 and PXFEL3)

➤ Leading to Restricted Call for Tender signed in July 2012

4. XFEL module assembly by industry operator 2012 – 2015

Pre-serie modules: XM-3, XM-2, XM-1

Serie module: XM1 to XM100





#### **INDUSTRIAL CONTRACT: INTRODUCTION**




- Tender process: ALSYOM, best technical offer, has been selected by CEA.
- The contract has to be awarded on 27 July 2012 for the integration of 83 cryomodules + 20 in option.
- Up to 29 people will be on Saclay site during ~2 ½ years
- Kick-off meeting : 05/09/2012
- Review of Quality Plan and Management Plan : 27/09/12 with DESY
- After one year, these people are GOOD and the CEA-Alsyom collaboration is EXCELLENT!





## INDUSTRIAL CONTRACT: ALSYOM MANAGEMENT PLAN







## INDUSTRIAL CONTRACT: OBSERVATION PHASE



Observation phase which covers the assembly of XM-3 by CEA with ALSYOM staff as observers.

Initially, this phase starts at T0 (20 August 2012) until T0 + 4 months (20 December 2012). Extended to April 2013

XM-3 first pre-series module is made with parts from XFEL production lines, except for cavities (large-grain RI cavities) and couplers (TTF3 RI couplers).








## INDUSTRIAL CONTRACT: XM-3 NCR







In total 43 Non-Conformance Reports (NCR) were issued for XM-3, some global, about 13 NCR under the responsibility of CEA: one main reason for 7 month assembly.

C. Madec | SRF13-THIOA02 | 26/09/2013 | PAGE 24



#### **XM-3 TEST RESULTS**



quench limit operating gradient


XFEL goal

28.1

38.138.1

31.5 31.5

AC114 AC156 AC146 AC154 AC157 AC158 AC151 AC152



- ✓ Gradient is 29 MV/m when cavities are powered by pairs 40.8 40.8 38.5 3
- ✓ Seven cavities are reproducing VT 38.5 38.5 value of the seven cavities are reproducing VT gradient
- ✓ cavity 1 is degraded from 31 MV/m down to 23 MV/m useable gradient 31.5 31.5
- ✓ Three³eavities reached gradients above 38 MV/m. 26.1
- ✓ Cryogen cs losses are lower than specified (MOP029)
- ✓ This successful test is qualifying CEA team and procedures and partially CEA infrastructure and industrial feasibility.
- The partial qualification lays in the fact that cavities and couplers are pre-industrial and the clear room vacuum system was not complete.
- ✓ Weldings certification would have to be AC157 AC158 AC151 AC152 reworked in order to install this module in the injector for 2014.



quench limit

31.6314

38.40

30

20

10

26.1

40.840.8

38.538.5



## INDUSTRIAL CONTRACT: TRAINING PHASE



Training phase which covers the assembly of XM-2 and XM-1 by mixed CEA-Alsyom teams (co-activity or transfer of knowledge) from T1 = T0 + 4 months till T1 + 6 months.

XM-2 first pre-series module was made with parts from XFEL production lines, e.g first eight EZ cavities, except for couplers (TTF3 RI couplers); 18 wks/14wks. XM-2 is at DESY getting ready for testing

XM-1 has started on August 2013 first pre-series module made with parts from XFEL production lines, including cavities and couplers; still under assembly





### XM-2 NCR



	XM-2 NCR's								
NCR Reference	NCR EDMS ID	Ref	Sub-assembly	Serial N*	Acronyme	WS	Origin	Detection	Description
CEA-XFEL-RNC-12-047	D*1019155	XM-2	XM-3_CCP: Coupler Cold Part (TTF3)	AC3C43, AC3C44, TWG012	CCP	REC	PRODUCT	PRODUCTION	Bad position of screws on ceramic protection cap + Presence of water inside cold ceramic cap
CEA-XFEL-RNC-12-077	D*1024275	XM-2	Cavity fully equipped	CAV00512	CAV_FE	REC	PRODUCT	PRODUCTION	Threaded rods too long on cavity beantube adapter flange - short side
CEA-XFEL-RNC-12-081	D*1024345	XM-2	Cavity fully equipped	CAV00510	CAV_FE	REC	PRODUCT	PRODUCTION	High Q Antenna flange misoriented
CEA-XFEL-RNC-12-082	D*1024395	XM-2	Cavity fully equipped	CAV00510	CAV_FE	REC	PRODUCT	PRODUCTION	Cavity elbow valve mispositionned
CEA-XFEL-RNC-12-083	D*1024465	XM-2	Cavity fully equipped	CAV00509 & CAV00512	CAV_FE	SUP	PROCESS	PRODUCTION	Water entered inside 2Ph He pipe and tank during washing operation in the Bellimed
CEA-XFEL-RNC-12-085	D*1024985	XM-2	XM-3_CCP: Coupler Cold Part (TTF3)	AC3C45 & AC3C47	CCP	REC	PRODUCT	PRODUCTION	Protective plastic bags are damaged (holes)
CEA-XFEL-RNC-12-086	D*1025055	XM-2	XM-3_CCP: Coupler Cold Part (TTF3)	AC3C45 & AC3C47	CCP	REC	PRODUCT	PRODUCTION	Valve on the cold ceramic cap misoriented
CEA-XFEL-RNC-12-087	D*1025115	XM-2	XM-3_CCP: Coupler Cold Part (TTF3)	AC3C45 & AC3C47	CCP	REC	PRODUCT	PRODUCTION	Connectors on the cold ceramic caps not properly screwed
CEA-XFEL-RNC-12-089	D*1025245	XM-2	XM-3_CCP: Coupler Cold Part (TTF3)	AC3C48 & AC3C50	CCP	REC	PRODUCT	PRODUCTION	Stainless steel screws on cold ceramic caps of the coupler
CEA-XFEL-RNC-12-090	D*1025305	XM-2	Cavity fully equipped	CAV00510 & CAV00514	CAV_FE	cc	PROCESS	PRODUCTION	Water inside cavity elbow valve
CEA-XFEL-RNC-12-090	D*1024545	XM-2	BQU: BPM Quadrupole Unit	BQU 002_C	BQU	REC	PRODUCT	PRODUCTION	Residual pressure of 2 10-2 mbar was read from the two PKR 261 gauges
CEA-XFEL-RNC-12-088	D*1025185	XM-2	XM-3_CCP: Coupler Cold Part (TTF3)	AC3C30 & AC3C31	CCP	REC	PRODUCT	PRODUCTION	Fingerprints and dust on the TWG
CEA-XFEL-RNC-12-092	D*1025365	XM-2	XM-3_CCP: Coupler Cold Part (TTF3)	AC3C30 & AC3C31	CCP	REC	PRODUCT	PRODUCTION	Coupler bellow clamps in contact with pick-up flange
CEA-XFEL-RNC-12-093	D*1025605	XM-2	Warm up tube	E2004	CM	AL	PROCESS	PRODUCTION	EZ0004 warm-up pipe damaged
CEA-XFEL-RNC-12-094	D*1025725	XM-2	Cavity fully equipped	CAV00509, CAV00510, CAv00513, CAV00514, CAV00526.	CAV_FE	REC	PRODUCT	PRODUCTION	Five cavities are out RF-measurement acceptance regarding the HOM RF rejection criteria
CEA-XFEL-RNC-12-095	D*1025855	XM-2	XM-3_CCP: Coupler Cold Part (TTF3)	AC3C31	CCP	œ	PRODUCT	PRODUCTION	Light scratches on the antenna of the cold part
CEA-XFEL-RNC-12-096	D*1025775	XM-2	Cavity fully equipped	CAV00509	CAV_FE	SA	PRODUCT	PRODUCTION	Presence of visible particules inside beam tube
CEA-XFEL-RNC-12-097	D*1025435	XM-2	Cavity fully equipped	CAV00523	CAV_FE	REC	PRODUCT	PRODUCTION	High Q Antenna flange and Cavity flange (Long side) misoriented
CEA-XFEL-RNC-12-098	D*1025495	XM-2	Cavity fully equipped	CAV00513	CAV_FE	REC	PRODUCT	PRODUCTION	Flange of elbow valve is dirty
CEA-XFEL-RNC-12-099	D*1027325	XM-2	Cavity fully equipped	ALL CAVITIES	CAV_FE	SA	PROCESS	PRODUCTION	Quick Cavity venting up to 6 mbar
CEA-XFEL-RNC-12-100	D*1025555	XM-2	CBL: Cavity Bellows	FEL VBI 000004-043	CBL	SA	PRODUCT	PRODUCTION	Marks on Inside waves of the cavity bellow
CEA-XFEL-RNC-12-101	D*1025915	XM-2	BQU: BPM Quadrupole Unit	BQU 005_C	BQU	REC	PRODUCT	PRODUCTION	Residual pressure of 2 10-2 mbar was read from the two PKR 261 gauges
CEA-XFEL-RNC-12-102	D*1027265	XM-2	Needle Support assembly (type 1 and 2)	EZ004		RO	PRODUCT	PRODUCTION	Metalic chips in threads of needle supports
CEA-XFEL-RNC-12-103	D*1027445	XM-2	Cavity bellows	Cavites 7 et 8	CBL	RO	PROCESS	PRODUCTION	Chocs on CBL of cavities 7 et 8
CEA-XFEL-RNC-12-107	D*1027505	XM-2	PT1000 sensor		TMP-PT	AL	PROCESS	PRODUCTION	70K Interface screw in contact with the sensor
CEA-XFEL-RNC-12-111	PP not created in EDMS	XM-2	XM-3_CWP: Coupler Warm Part (TTF3)	AC3H42	XM-3_CWP	co	PRODUCT	PRODUCTION	M5 screw antenna seized in the warm part
CEA-XFEL-RNC-12-112	D*1026715	XM-2	Actuator Assembly (TTF3)	THRI-AC-002, 004, 010, 016, 019, 022	ACT	co	PRODUCT	PRODUCTION	THRI-AC-002/THRI-AC-016/THRI-AC-019
CEA-XFEL-RNC-12-113	PP not created in EDMS	XM-2	XM-3_CWP: Coupler Warm Part (TTF3)	AC3H34	XM-3_CWP	со	PRODUCT	PRODUCTION	Copper Plater missing on the outer conductor of the Warm Part
CEA-XFEL-RNC-12-115	PP not created in EDMS		Capacitor Assembly (TTF3)	CP3KS1 and CP3KS3		co	PRODUCT	PRODUCTION	Mechanical choc on capacitor CP3KS1 and Mark of electrical flash on CP3KS3
CEA-XFEL-RNC-12-116	D*1027265	XM-2	CLW: Current Leads Warm Assembly	003	αw	co			
CEA-XFEL-RNC-12-117	PP not created in EDMS	XM-2	Cryomodule	XM-2	XM-2	со	TOOUNG	PRODUCTION	Quick pumping of cavity string

NOTA: For Physical Parts not released in EDMS, the NCRs cannot be uploaded in the system.

02/08/2013

30's NCR Decreasing number





## INDUSTRIAL CONTRACT: RAMP-UP IN PRODUCTION PHASE





7 assembly area +1 => 8 weeks of assembly



Ramp-up: XM1 to XM8: 2 weeks per area => 16 weeks



Ramp-up from Sept. 2013 to Dec. 2013



Production: Dec. 2013 on











## INDUSTRIAL CONTRACT: PRODUCTION PHASE



Production phase which covers the assembly of XM1 to XM80 by Alsyom from T2 = T0 + 9 months (September  $2^{nd}$  2013) till T2 + 24 months (20 May 2015).

Production phase (option) which covers the assembly of XM81 and XM100 by Alsyom from T3 (5 April 2015) till T3 + 6 months

(5 October 2015).





C. Madec | SRF13-THIOA02 | 26/09/2013 | PAGE 29



Le futur est toujours beau ..... .... Le présent est difficile

Future is always beautiful.....

.... Present is tough



Commissariat à l'énergie atomique et aux énergies alternatives Centre de Saclay | 91191 Gif-sur-Yvette Cedex T. +33 (0)1 69 08 69 39

Irfu SACM LIDC2



### **BACK UP SLIDES**







### **CHALLENGE: TOOLING VS. INDIAL CONTRACT**



Ideally the tooling definition should be included in the industrial contract.

This was impossible with our project timeline and readiness: e.g. the clean room was delivered in Nov. 2009.

The contract specifies that the Industrial Operator is only responsible of the standard tools, while CEA is responsible for the specific tools and their maintenance.

The contract is essentially 'Man and Engineering Power'

As a consequence, the industrial operator will criticize the infrastructure layout and the tooling made available to him:

- e.g. cavity reception area,
- e.g. cavity support and pre-alignment tools in the clean room,
- e.g. layout of shipment vs. VV strorage area

Some of the criticisms come too early, missing the global scheme. Some of the criticisms will lead to a better optimized production.





## INPUT DATA READINESS FOR THE INDUSTRY TRANSFER



				26/09/2013
	@	CfT	Kick-off	₽rod
<ul> <li>Infrastructure and Tooling</li> </ul>		80%	90%	100%
(in the broad sense, e.g. cavity supports)				
<ul> <li>Cryomodule Configuration</li> </ul>		70%	85%	100%
<ul> <li>Cryomodule Documentation</li> </ul>				
<ul><li>PBS (or MBOM)</li></ul>		30%	70%	100%
<ul> <li>Availability of Drawings</li> </ul>		30%	70%	100%
<ul> <li>Assembly Documentation (WBS)</li> </ul>				
<ul> <li>Availabitity of Assembly Procedures</li> </ul>	3	50%	75%	100%
<ul> <li>Availabitity of Control Procedures</li> </ul>		50%	75%	100%
<ul> <li>Availabitity of Regulation (PED, Saf</li> </ul>	ety)	20%	75%	100%
		(qual	itative %)	

Ratios are 100 % (cf. cavity production, or AMTF).


Industry start production with 100% of Input Data in their Resource Planning software (ERP)


• Overall Quality of the Process (RF acceptance) 60% 60% 100%





## **ASSEMBLY STEPS**













## PRE-SERIES TRAINING PHASE: INITIAL SCHEDULE (1/3 BIS)



### Couplers NonConformity

				Reference	CEA-XFEL-RNC-13-073
	European XFEL	NON CONFORMANCI	E REPORT	Page	1
$\sim$ IIII	XFEL			Date :	19.03.2013
Enter either the "Physica	Part EDMS-ID*, or the *Fab. Part Name	e" + "Fab. Part EDMS-ID" + "Physical Part Ser.	ial Number".	Physical Part EDMS-ID :	??
Fab. Part Name :	??	Fab. Part EDMS-ID :	??	Physical Part Serial No.	??
Recorded by :	O. Napoly	Location :	CEA XFEL Coupler A	rea	
TITLE :	Water and broken ceramics in the colo	d part of the coupler AC3C28			
DESCRIPTION:					
Nater may have entered t The level of water staying 2) a broken ceramics (cf. p	cap, and indeed the copper coating is oxide the cap though the valve during the washi in the cap for about 6 months, is indicated pictures n°1 at 4h30 orientation, and n°4) ikken ceramics on the cap (cf. picture n°5)	ing of the coupler pair since one can see a trace d by the darker lower area on the picture.	of oxidation inside the cap i	in front of the valve hole (cf. picture n°3	)).
TECHNICAL INVESTIGA 1) The location (flange, va		he washer-dryer is under investigation. There is	no indication that the valve	Responsible (s) was S. Berry, F. Hoffmann	
loose. 2) We are investigating wh the coupler pair, or when o		ed: due to the presence of water, it could have ha	appened only before the wa	shing of	
CORRECTIVE ACTIONS	(on Physical Part, or Equipment) :			Responsible (s)	
localy removed completely	y (cf. picture n°7)	th sullfamic acid and rinsing with ethanot. Unfortu material layer (cf. picture n°8) was bend and fold			
PREVENTIVE ACTIONS	(on Fabrication Part, or Equipment) :			Responsible (s)	
	oupler pairs in the ISO4 clean room through be defined when the origin of the ceramics	gh the washer-dryer until the origin of the water less breaking is found.	eak is found.	S. Berry	
CATEGORY:		FINAL DECISIONS :			
CATEGORY :		FINAL DECISIONS : Action on Part :	Repair		

Clearance for actions	Fabrication Engineer (Technical Manager)	Quality Manager	Project Manager (WPL)
Unit responsible for involved product:	S. Berry, T. Trublet	C. Cloué	O. Napoly
Accelerator Consortium Manager :	E. Vogel		W. Kaabi, W-D. Möller








## PRE-SERIES TRAINING PHASE: INITIAL SCHEDULE (1/3 BIS)



#### Alignment CEA Procedure Non Conformity

				Reference	CEA-XFEL-RNC-12-068
	European	NON CONFORMANC	E REPORT	Page	1
	XFEL			Date	20.12.2012
Enter either the "Phys	ical Part EDMS-ID", or the "Fab. Part N	ame" + "Fab. Part EDMS-ID" + "Physical Par	Serial Number".	Physical Part EDMS-ID :	
Fab. Part Name :		Fab. Part EDMS-ID :		Physical Part Serial No.	XM-3
Recorded by :	O.Napoly/M.Fontaine	Location :	CEA XFEL Alignment Area	1	
TITLE :	Cavity Alignement				
DESCRIPTION :	Problems during the cavity and qua	adrupole alignment			
	t (20/02/13), the allignment was accepted ontinued.	with good agreement between CEA and DESY by DESY, with a derogation for longitudinal po			nd n°5, tbc).
tororonoo documento					
TECHNICAL INVESTIG				Responsible (s)	
was found 1.5 mm awa expanded towards its u 3) the torques of the bu	ay from its nominal position. By mistake, c upstream end and cavity n°1 has been me	n the coupler side of the cavity string (vertical a	ar rod: as a result, the string	J M. Fortaine, 3-1 . Chamer	
		iot on specifications.			
<u> </u>	NS (on Physical Part, or Equipment) :	or on specifications.		Responsible (s)	
CORRECTIVE ACTION 1) DESY sent us the tor 2) CEA implemented the 3) The torque of the bu- attributed to their seizur	ols needed to displace the cavities longitude correct reference frame in the post-prosses was checked along the string. The fure since the problem was fixed after manifered.	udinally and the longitudinal alignment of the st cessing of the raw data. Agreement was then it wo bushes of cavity in 3 and in 5 were found in pulation of the bush by hand. Some bushes w	eached with DESY. correctly fastened. This is	M. Fontaine, J-P. Charrier	
CORRECTIVE ACTION  1) DESY sent us the too  2) CEA implemented th  3) The torque of the bu- attributed to their seizur  the springs were not co	ols needed to displace the cavities longitude correct reference frame in the post-prosses was checked along the string. The fure since the problem was fixed after manifered.	udinally and the longitudinal alignment of the st cessing of the raw data. Agreement was then r wo bushes of cavity n°3 and n°5 were found in putation of the bush by hand. Some bushes w	eached with DESY. correctly fastened. This is	M. Fontaine, J-P. Charrier	
CORRECTIVE ACTION 1) DESY sent us the tot 2) CEA implemented th 3) The torque of the bu attributed to their seizur the springs were not co  PREVENTIVE ACTION 3) In order to prevent the	ols needed to displace the cavities longiti ne correct reference frame in the post-pro shose was checked along the string re- tre since the problem was fixed after mani precity piled up.  18 (on Fabrication Part, or Equipment) he seizure of the bushes, it is envisaged to	udinally and the longitudinal alignment of the st cessing of the raw data. Agreement was then r wo bushes of cavity n°3 and n°5 were found in putation of the bush by hand. Some bushes w	eached with DESY. correctly fastened. This is are dismounted and in one case	M. Fontaine, J-P. Charrier	
CORRECTIVE ACTION 1) DESY sent us the to 2) CEA implemented th 3) The torque of the bu attributed to their seizu the springs were not co PREVENTIVE ACTION 3) In order to prevent if In general, CEA will imp	ols needed to displace the cavities longiti ne correct reference frame in the post-pro shose was checked along the string re- tre since the problem was fixed after mani precity piled up.  18 (on Fabrication Part, or Equipment) he seizure of the bushes, it is envisaged to	udinally and the longitudinal alignment of the st cessing of the raw data. Agreement was then r wo bushes of cavity n°3 and n°5 were found in pulation of the bush by hand. Some bushes we :  o use vacuum grease. The depth of the bushe	eached with DESY. correctly fastened. This is are dismounted and in one case will also be checked ment operations.	M. Fontaine, J-P. Charrier  Responsible (s)	
CORRECTIVE ACTION 1) DESY sent us the tot 2) CEA implemented th 3) The torque of the bu attributed to their seizur the springs were not co  PREVENTIVE ACTION 3) In order to prevent the	ols needed to displace the cavities longiti ne correct reference frame in the post-pro shose was checked along the string re- tre since the problem was fixed after mani precity piled up.  18 (on Fabrication Part, or Equipment) he seizure of the bushes, it is envisaged to	udinally and the longitudinal alignment of the st cessing of the raw data. Agreement was then r wo bushes of cavity in "3 and in "5 were found in putation of the bush by hand. Some bushes we : o use vacuum grease. The depth of the bushe is not involved in the cavity-quadripole re-align	eached with DESY. correctly fastened. This is are dismounted and in one case will also be checked ment operations.	M. Fontaine, J-P. Charrier  Responsible (s)	

Clearance for actions	Fabrication Engineer (Technical Manager)	Quality Manager	Project Manager (WPL)
Unit responsible for involved product:	M. Fontaine, J6P. Charrier	C. Cloué	O. Napoly
Accelerator Consortium Manager :	E. Vogel		K. Jensch, M. Schlösser



The Cavity Alignment Procedure had to be repeated 4 times, essentially due to mishandling by CEA and a technical problem on the needle bearings fixtures:

 $\rightarrow$  1 calendar month, instead of 3 days.





#### PHASE 3: PRE-INDUSTRIAL STUDY



Ajilon was subcontracted to perform the pre-industrial study with

the achieved goal of:

- Tools definition
- Assembly Procedures with the non mechanical operations
- Schedule
- PBS EBOM
- Risk Analysis
- Interruption Scenarios
- Inventory Management
- List and implantation of Services and Fluid Distribution
- Listing of Parts and Its Packaging
- Description of Reception Process & Controls
- Using experience gained at DESY








#### PXFEL2 2 RESULTS





#### Conclusion

- seven cavities are degraded ⊗ with ∆Eacc = 7 MV/m lost on average ⊗
- very strong field emission on cavity n°1 (AC128), again ! ⊗⊗ (*string vented and pumped from cavity n*°1 *end*)
- Z162 has experienced two cold coupler connections, with the same coupler ©
- all cavities but Z139 (position n°3) have suffered from one (seldom two) non-conformity during the cold coupler or string assembly (e.g. water in the angle valve body)
- AC128 (pos. n°1) and AC115 (pos. n°2) share the same non-conformity, namely the accidental fast venting of the common coupler traveling waveguide box.



## INDUSTRIAL CONTRACT: NCR



#### Cavities Non Conformity

Irfu European XFEL		NON	Reference	CEA-XFEL				
			CHANGE REQUEST			1		
			CHANGE REQUEST		Date	23/10/12		
EQUIPMENT:	CAVITY	SERIAL NUMBER:	L NUMBER: XM-3		FILLED OU	ГВҮ:		
Occurrence phase	<u>e :</u>			Integration level		Workstatio		
Control :		Reception :		Part	X	Reception Ha		
Manufacturing :		Acceptance :		Subassembly				
Design/validation :		Destockage :		Equipment				
Integration :	Х	Others :		Others				
TITLE :	Deviation of the Pin	eviation of the Pin in the longitudinal position						

#### **DESCRIPTION:**

We observed on the cavity AC158 that the assembly of the newly produced magnetic shield was too tight (cf. pictures page 2).

Under the indication from DESY, this led to the systematic measurement of the distance from the middle of the cavity bracket to the AC1 103 mm instead of he nominal 93 mm +- 2 mm

This result was reproduced for all eight XM-3 cavities AC114, AC146, AC151, AC152, AC154, AC156, AC157, AC158

Reference documents :

TECHNICAL INVESTIGATIONS :	Responsible (s)
----------------------------	-----------------

On the cavity was measured a deviation on the PIN (draw. 02L, pos. 4) in the longitudinal position: The nominal distance from the cavity bracke centert to the PIN center is 93mm – measured ~103mm The nominal distance from the coupler flange center to the PIN is (100,02mm) – measured ~96mm


CORRECTIVE ACTIONS (item concerned by NCR/CR)	Responsible (s) :		CLASS:
The connection of the cavity string to the cold mass will have	MINOR:		
the shrinkage of the cold mass during cool-down.			MAJOR:
		FINAL DECISIONS :	
			USE AS IS
			WAIVER
PREVENTIVE ACTIONS (further item) :	Responsible (s):		REPAIR
Check of the helium tank dimensions for the industrially produ	iced cavities.	•	DOCUMENTATION

Clearance for actions	Technical Manager	Quality Assurance Manager	Project
CEA	J-P. Charrier	C.Cloué	O.Ni
Accelerator Consortium manager :	D. Reschke (CO)	-	E. Vog

		Reference	CEA-XFE
European	NON CONFORMANCE REPORT / CHANGE REQUEST	Page	2
XFEL	CHANGE REGUEST	Date	23/10/12
	CONTINUATION SHEET		

Assembly of the magnetic shield on the cavity AC158 :






Cavity drawing:

CHANGE

MODIFICATION
ACTION ON OTHER
PRODUCT





## PHASE 3: OUTPUT OF PRE-INDSUTRIAL STUDY ASSEMBLY PROCEDURES




Tall ( =	GOM WASS_AREPS	V 3.0
	Juning system proposity on ca-	Page 1/17
C XFE	app nn-[2,8]	Date: 21/09/2

Tuning system assembly on cavity n n=[2:8]



Written by		Checked by		Approved by	
Name	Vanick SAUCE	Name	Joan-Pierre CHARRIER	Name	Catherine 1
Punction	Teravelan	Punction	describly had manager	Punction	System que
Date		Date		Date	
Signature		Signature		Signature	







 Place the two smallest ball bearings 19x7x6 in the corresponding hole in the motor housing of the drive unit.



- 51. Molding the drive unit by hand, place it briefly in the cornect position in order to evaluate the required position of the nut along the Cyclic serve. Then move it as needed to install it easily.
- 752. Place the drive unit in place with the motor wints pointing up (to ease cabling after the magnetic shielding installation), insert the two special drive unit sos.
- Sorew the 6 M4 12 mm scrows to fix the drive unit exis, install the two last ball bearings 24x8x8 over the nut and fix them with two safety washers








- While holding this position start screwing (with the proper special tool) the adjusting screw on the bottom (the one with spherical head)
- Serew the adjusting serew at the bottom until a good confact between frame, solid joint and early is reached, then serew 1/5 turn more for further fastering.






## Magnetic Shieldings: PXFELs & XM-3

Prototype by MecaMagnetic for PXFEL configuration (warm-up tube with flange)



Pre-series by MecaMagnetic for XFEL configuration (warm-up tube with Ti/SS transition): benchmarking XM-3 cavities!









X-Ray Free-Electron Laser

## Magnetic Shieldings: XM-2



Pre-series by MecaMagnetic for XM-2 cryomodule





## DE LA RECHERCHE À L'INDUSTRIE

### Super-insulation Blankets



Super-insulation blankets have been qualified (PXFEL2\_1 and PXFEL3\_1).

The 40/80 K super-insulation blanket (2x15 layers):

- costs about 4 k€
- saves 1 day on cantilever and about 7 p.day (balance at ~600 € / day)
- saves about 30 W @ 40 K with respect to multilayers (30 + 29 separators).



Cryo loss at	PXFEL 3	PXFEL 3_1 cooldown Dec 2011	PXFEL 3_1 cooldown Feb 2012	PXFEL 2_3 cooldown March 2013
40 / 80 K	134 W	96 W	97-102 W	95 W

Negotiations with Jehier allowed about 10% reduction / CfT offer, through:

- more flexible (rapid) delivery rate
- simplification of 2K blankets fabrication


70 K-blankets ordered in advance for XM-3, XM-2, XM-1 (delivered in June 2012)



## 70 K Blankets: Prototype by Jehier for PXFEL2\_2









## 2 K Blankets: Prototype by Jehier for XM-2









